

Electricity Industry Act 2004

Electricity Networks Access Code 2004

(Unofficial consolidated version)

[date]

This is an unofficial version of the Electricity Networks Access Code 2004, as originally Gazetted on 30 November 2004, including amendments made by:

- WAGG, No 207, 8 November 2005, Operational 8 November 2005;
- WAGG, No 59, 31 March 2006, Operational 1 April 2006;
- WAGG, No 152, 1 September 2006, Operational 1 September 2006;
- WAGG, No 206, 8 December 2006, Operational 8 December 2006;
- WAGG, No 137, 29 June 2007; Operational 29 June 2007;
- WAGG, No 176, 29 August 2007; Operational 29 August 2007;
- WAGG, No 13, 25 January 2008, Operational 25 January 2008;
- WAGG, No 180, 22 October 2008, Operational 22 October 2008;
- WAGG, No 182, 30 September 2011, Operational 30 September 2011;
- WAGG, No 61, 17 April 2012, Operational 17 April 2012;
- WAGG, No 183, 21 November 2014, Operational 21 November 2014;
- WAGG, No 231, 23 December 2016, Operational 23 December 2016;
- WAGG, No 108, 26 June 2020, Operational 26 June 2020;
- WAGG, No 157, 18 September 2020, Operational 18 September 2020;

- WAGG, No 118, 2 July 2021, Operational 2 July 2021;
- WAGG, No 134, 30 July 2021, Operational 30 July 2021; and
- WAGG, [No], [date], Operational [date].

Footnotes and references to “[Heading not used]” and “[Not used]” are included for readability of this document only and do not form part of the Electricity Networks Access Code 2004.

Disclaimer

No warranty is given as to the accuracy or completeness of this document. The State of Western Australia and its agents and employees disclaim liability, whether in negligence or otherwise, for any loss or damage resulting from reliance on the accuracy or completeness of this document.

Copyright

Copyright in this document is reserved to the Crown in right of the State of Western Australia. Reproduction except in accordance with copyright law is prohibited.

Approval by Minister

I, ERIC RIPPER, Minister for Energy for the State of Western Australia, under section 104(1) of the *Electricity Industry Act 2004* hereby establish the Electricity Networks Access Code contained in this document.

In accordance with section 41 of the *Interpretation Act 1984*, this Code comes into operation on the day of its publication in the Gazette.

ERIC RIPPER

Dated at Perth this 29th day of November 2004.

Contents

Chapter 1 – Introductory	15
Citation.....	15
Commencement	15
Definitions	15
Interpretation	44
Chapter 2 – General Principles	46
Code objective	46
Code objective with other objectives, requirements and factors etc	46
Freedom to contract	47
Service provider to use reasonable endeavours to provide access to covered services	49
Requirement to undertake work and funding of work.....	50
Chapter 3 – Coverage	51
Subchapter 3.1 – Covered networks	51
Western Power Network is covered	51
When coverage starts for Horizon Power’s Pilbara network	51
Other networks may be covered	52
Subchapter 3.2 – Criteria for coverage	52
Minister’s decision on coverage	52
Coverage criteria	52
Factors the Minister must have regard to.....	53
Subchapter 3.3 – Coverage process	53
Applications for coverage	53
Minister may dismiss a coverage application	53
Invitation for submissions and issues paper.....	53
First round public submissions	54
Draft coverage decision by the Minister	54
Second round public submissions	54
Final coverage decision by Minister	55
Final coverage decision has effect	55
Late submissions.....	55
Reasons.....	55
Service provider agrees to network coverage.....	55
Extensions of time under this Chapter	55
Subchapter 3.4 – Revocation of coverage	56
Revocation of coverage.....	56
Subchapter 3.5 – Miscellaneous	57
Advertising	57
Publishing	57
Automatic coverage.....	57
Notification of network modification.....	57
Subchapter 3.6 – Transitional matters relating to form of regulation decision	58
Contracts preserved	58
How applications and disputes in progress are managed.....	58
Chapter 4 – Access Arrangements: Approvals and Review	61
Subchapter 4.1 – Approval process	64
Submission of first access arrangement	64

Access arrangement information.....	64
Invitation for submissions and issues paper.....	65
First round public submissions	66
Draft decision by Authority.....	66
Second round public submissions	67
Revised proposed access arrangement.....	67
Final decision by Authority.....	67
[Heading not used]	68
[Heading not used]	68
[Heading not used]	68
Access arrangement start date	68
Subchapter 4.2 – Criteria for approval.....	69
[Heading not used]	69
Criteria for approval of a proposed access arrangement	69
Factors the Authority must have regard to	70
[Heading not used]	70
Access arrangement must not override prior contractual rights.....	70
Conditional approval – price lists.....	71
Subchapter 4.3 – Revision and review	71
Trigger events.....	71
Revision of price control or pricing methods during an access arrangement period	71
Revision of access arrangement if Code is amended.....	72
Other revisions during an access arrangement period	72
Mid-period revisions do not necessarily involve full review.....	73
Procedure for amendments under sections 4.41 and 4.41A.....	73
Review of access arrangement	73
Subchapter 4.4 – Miscellaneous	74
Late submissions.....	74
No confidentiality for certain documents	74
Authority drafting and approving own access arrangement if no access arrangement submitted	75
Interim access arrangement in the event of delay	75
Extensions of time under this Chapter 4	76
Suspension of deadlines when Authority obtains information.....	77
Suspension of deadlines for judicial proceedings	77
Suspension of deadlines for Code amendment	78
[Heading not used]	78
[Heading not used]	79
“Review of access arrangement for the Western Power Network after first 2020 Code change..	79
Amendments of model documents for Western Power Network.....	79
Chapter 5 – Access Arrangement: Content	81
Required contents of an access arrangement.....	81
Reference services.....	82
Standard access contract for each reference service	82
Service standards for each reference service	83
Applications and queuing policy	84
Contributions policy	87
Contributions for certain Western Power Network work.....	89
Headworks scheme	89
Efficiency and innovation benchmarks	91
Supplementary matters	91
Revisions submission	92
Trigger events.....	93
Multi-function asset policy	93
Assessment of model documents	94

Chapter 6 – Price Control	95
Subchapter 6.1 – Target revenue	95
Form of price control.....	95
Form of price control for first access arrangement.....	95
Price control objectives.....	95
Recovery of deferred revenue.....	97
Recovery of advanced metering communications infrastructure expenditure.....	97
Target revenue may be adjusted for unforeseen events.....	98
Target revenue may be adjusted for technical rule changes.....	99
‘Investment adjustment mechanism’ defined.....	99
Requirement for an investment adjustment mechanism.....	100
‘Gain sharing mechanism’ defined.....	100
Requirement for a gain sharing mechanism.....	100
Objectives for gain sharing mechanism.....	101
‘Surplus’ defined.....	101
‘Deficit’ defined.....	101
Prior surpluses may be retained.....	102
Determining the above-benchmark surplus or below-benchmark deficit.....	102
Determining the increase or decrease to the target revenue.....	102
‘Service standards adjustment mechanism’ defined.....	102
Requirement for service standards adjustment mechanism.....	103
Authority may make a determination of excluded services for a covered network.....	105
Tariff equalisation contributions may be added to target revenue.....	106
Subchapter 6.2 – Calculation of Service provider’s Costs	106
When this Subchapter 6.2 applies.....	106
Non-capital costs.....	107
Capital-related costs.....	108
Determining the capital base.....	108
Capital base for the start of the first access arrangement period.....	108
Capital base for the start of subsequent access arrangement periods.....	109
Capital base must not include forecast new facilities investment.....	109
Test for adding new facilities investment to the capital base.....	110
New facilities investment test.....	110
Authority must make guidelines.....	112
Recoverable portion.....	112
Speculative investment.....	112
Redundant capital.....	113
Calculating weighted average cost of capital.....	113
Authority may make a determination of a methodology for calculation of weighted average cost of capital.....	114
Depreciation.....	115
Consultation with AEMO.....	115
Subchapter 6.3 – Service provider may seek approval for costs	115
Approval for new facilities investment.....	115
Approval for non-capital costs.....	116
Approval for access reform costs.....	117
Subchapter 6.4 – Multi-function assets	117
Chapter 6A – Alternative options	119
Network Opportunity Map.....	119
Alternative options strategy and vendor register.....	121
Net Benefit Valuation Guidelines.....	122
Model alternative option service contract.....	123
Chapter 7 – Pricing methods and tariff structure statements	125
‘Pricing methods’ defined.....	125
Tariff structure statements.....	125

Form of pricing methods.....	126
Pricing objective	126
Application of the pricing principles	126
Pricing principles	127
[Heading not used]	129
[Heading not used]	129
Tariff components	129
Postage stamp charges in certain cases.....	129
'Equivalent tariff' defined	130
Prudent discounts	130
Discounts for distributed generating plant.....	130
Access arrangement must detail policies regarding discounts	130
Tariff equalisation contributions must be included as a tariff component for distribution network users	131
Chapter 8 – Price lists.....	132
Submission and approval of price lists if required	132
Contents of price list.....	134
Revision of reference tariff change forecast.....	135
Publication of information about tariffs	135
Chapter 9 – Regulatory test	136
Subchapter 9.1 – Introductory	136
Objectives of this Chapter 9	136
No major augmentation without regulatory test determination.....	136
'Regulatory test' defined	137
'Committed' defined.....	137
Authority may make a determination that an augmentation is or is not a major augmentation ..	137
Service provider must make information available.....	138
Subchapter 9.2 – Regulatory test process	138
Regulatory test as part of access arrangement approval process	138
Regulatory test not as part of access arrangement approval process	139
Regulatory test may be expedited, otherwise modified or waived	140
Vexatious etc alternative options.....	141
Subchapter 9.3 – Anti-avoidance provisions	141
Anti-avoidance provisions.....	141
Chapter 10 – Dispute Resolution	143
Subchapter 10.1 – Introduction	143
Commercial Arbitration Act 2012 does not apply	143
Procedural rules	143
Subchapter 10.2 – Access Disputes	143
Notification of a dispute	143
Other parties joining	143
Conciliation and reference to arbitration.....	144
Authority not required to conciliate	144
Expedited hearing of disputes under applications and queuing policy	144
Factors which the arbitrator must have regard to.....	145
The arbitration	145
Arbitrated tariff to be guided by access arrangement and price list	145
Arbitrated tariffs for reference services	145
Arbitrated terms for reference services	146
Arbitrated tariffs for non-reference services	146
Award by the arbitrator	147
Restrictions on access awards.....	148
Arbitrated award requiring work to be undertaken	148

Effect of awards	148
Costs of arbitration	149
Subchapter 10.3 – Application of the regulatory test in an arbitration	149
Arbitrator must make proposed award if award would require major augmentation	149
Service provider must consult and submit major augmentation report	150
Service provider’s costs of compliance, if applicant withdraws	150
Authority must publish determination regarding major augmentation report	150
Arbitrator must have regard to Authority’s determination	151
Subchapter 10.4 – Contractual Disputes	151
Jurisdiction of arbitrator	151
Procedural rules	151
Chapter 11 – Service standards	153
Service provider must comply with service standards	153
Authority to monitor service standards	153
Penalties for breach of service standards	153
Chapter 12 – Technical Rules	155
Objectives of the technical rules	155
Persons bound by technical rules	155
Limited application of technical rules in respect of certain non-covered networks in an interconnected system	155
Technical rules prevail over contract	156
Covered networks must have technical rules	156
[Heading not used]	156
Approval process for technical rules – Covered network	157
[Heading not used]	158
Have regard to current regulation in case of deadlock	158
Commencement of technical rules	159
Technical rules committee	159
Recommendations from the technical rules committee	162
Authority may observe the technical rules committee	162
Scope and content of technical rules	162
Person applies to service provider for exemption from technical rules	162
Service provider applies to Authority for authorisation to grant exemption from technical rules	163
Amendments to technical rules	165
Notification of changes to technical laws	168
Review of technical rules	168
Coordination with other service providers in an interconnected system	168
[Heading not used]	169
[Heading not used]	169
[Heading not used]	169
[Heading not used]	169
Support services for technical rules committee	170
Reporting by the Authority	170
Chapter 13 – Ringfencing	171
Service provider must comply with ringfencing objectives and rules	171
Application of ringfencing objectives and rules to integrated providers	171
‘Ringfenced business’ defined	171
Other business must have deemed access contract	171
Associate contracts	172
Amendments to associate contracts and deemed access contracts	172
Ringfencing objectives	172
Factors the Authority must have regard to	174
Authority may approve ringfencing rules	174
Ringfencing rules and compliance procedures are not confidential	175
Additional ringfencing rules for an integrated provider	175

Service provider to procure compliance by its associates	175
Commencement time for ringfencing rules.....	176
Exemptions from ringfencing requirements.....	176
Compliance monitoring and compliance reporting	177
Breach of ringfencing requirements	177
Service provider to provide information to Authority and arbitrator	178
Chapter 14 – Administration and Miscellaneous	179
Service provider to provide information on access arrangements	179
Data collection regarding target revenue	179
Public register.....	179
Register of interested persons.....	181
Protection for the Authority	181
Treatment of confidential information	181
How this Code applies to multiple service providers	182
How this Code applies to successor service providers	183
Authority may seek advice.....	183
CPI adjustment	183
General process for public consultation	184
Detailed provisions regarding contributions for certain work on the Western Power Network ..	184
Guidelines by the Authority.....	184
Chapter 15 – Transitional.....	186
Minister may make determinations.....	186
Access arrangements for SWIS to be compatible with market	186
Access arrangements to be compatible with changes to contestability	186
Preservation of Western Power Network actions	186
[Heading not used]	187
Transitional arrangements for 2020 (No. 2) amendments	187
Appendix 1 – Flowchart of access arrangement approval process	189
Appendix 2 – Model Applications and Queuing Policy	190
Subappendix 2.1 – Interpretation	190
Definitions and Interpretation.....	190
Transition of prior applications.....	194
Negotiations in good faith	194
Classes of applications	194
Subappendix 2.2 – The application.....	195
Informal communications.....	195
Confidentiality	195
Costs of processing application.....	196
Lead times for applications.....	197
Access application.....	197
Errors or omissions in an application	199
Additional information	199
Subappendix 2.3 – Capacity increase notices and customer transfer requests.....	199
Capacity increase notice	199
Lodgement fees for capacity increase notices	200
Lead times for capacity increase notices	200
Form of capacity increase notices	200
Additional information	200
Customer transfer requests	201
Subappendix 2.4 – The Queue.....	201
Queuing rules apply only when there are competing applications	201
Queuing rules determine priority of applications	201
More than one queue	202

First come first served principle	202
Bypass	202
Applications in relation to tender projects etc	203
Reserve capacity auctions for SWIS	204
Processing of applications not affected	204
Exercising an option not affected	204
Priority of withdrawn applications	205
Provision of information about position in queue	205
Subappendix 2.5 – Amendment and withdrawal of application	206
Amendment to application	206
Amending application to address necessary work	206
Priority of amended applications	206
Withdrawal of application	207
Applications do not expire	207
Subappendix 2.6 – Processing the application and making the <i>access offer</i>	208
Service provider must be expeditious and diligent	208
Conditions precedent permitted in access contract	208
Conditions precedent and determination of spare capacity	208
Security	208
Initial response	210
Preliminary assessment	211
Progress reporting	211
Service provider must make access offer	212
Extension of time to perform obligations	212
Terms of access offer – If application requests reference service	213
Terms of access offer – If application requests non-reference service	214
Arbitrator’s powers preserved	214
Access offer is not a contract	214
Applicant’s options on receipt of an access offer	214
If applicant accepts access offer	215
Appendix 2A – Transitional Western Power Network Applications and Queuing Policy	216
Appendix 3 – Model Standard access contract	217
Parties	218
Background	218
Definitions and interpretation	218
Interpretation	229
Duration	231
There must be both a capacity contract and a technical compliance contract	231
When the parts of this contract apply	232
Provision and use	232
Contracted capacity	232
Contracted maximum demand and declared sent-out capacity	232
Variation to contracted capacity	233
Relocation	233
Customer transfer	234
Provisions of access arrangement on supplementary matters apply	234
Curtailment	234
Title to electricity	235
Designated controllers	235
Tariff and charges	237
Invoicing and payment	239
Security	242
Good electricity industry practice	243
Cooperation	244
Directions from system operator	244

User must provide information	244
Technical rules	244
Actions of third parties causing user to breach technical rules	244
Tariff and charges.....	244
Invoicing and payment.....	245
Security.....	245
Service provider must comply with service standards	245
Representations and warranties.....	245
Liability and indemnity	247
Insurances	249
Force majeure	250
Default	251
Termination.....	252
Access to premises	253
Disputes.....	254
Set off	254
Transfer by user	255
Corporate restructuring of service provider	255
Confidentiality	256
Ring fencing.....	258
Miscellaneous.....	260
Schedule 1 to Appendix 3 – Access Contract Information	262
Schedule 2 to Appendix 3 – Services.....	262
Schedule 3 to Appendix 3 – Details of Connection Points and Metering Points.....	263
Schedule 4 to Appendix 3 - Tariffs	263
Schedule 5 to Appendix 3 - Contribution (Provision in Kind Contract or Payment Contract) ...	263
Schedule 6 to Appendix 3 – Service provider’s works	263
Schedule 7 to Appendix 3 – UserCo’s works	263
Schedule 8 to Appendix 3 – Insurances and Limitation of Liability	264
Schedule 9 to Appendix 3 – Notices	264
Schedule 10 to Appendix 3 - Electronic Communications Protocol	265
Schedule 11 to Appendix 3 - Guarantee	268
Appendix 3A – Transitional Western Power Network standard access contract.	271
Appendix 4 – Model Contributions Policy	272
Subappendix 4.1 – Introductory	272
Definitions and interpretation.....	272
Application of this contributions policy.....	273
Subappendix 4.2 – Contributions	273
Contribution	273
Reasonable rate of return.....	274
Manner of contribution	274
Provision of contribution in kind.....	275
Provision of contribution by financial payment	276
Rebates and recoupment	276
Subappendix 4.3 – [Not used]	277
Appendix 4A – Transitional Western Power Network Contributions Policy.....	278
Appendix 5 – Procedural Rules for Arbitration	279
Application	279
Definitions.....	279
Informality and expedition.....	279
Arbitrator may request information	279
Hearing to be in private	279
Right to representation	280
Procedure	280
Particular powers of arbitrator	280

Determinations	281
Contempt	281
Disclosure of information	281
Power to take evidence on oath or affirmation	281
Failing to attend as a witness	282
Failing to answer questions etc.	282
Intimidation etc.	282
Party may request arbitrator to treat material as confidential.....	283
Costs.....	283
Appeal to Court.....	284
Copies of decisions to be given to the Authority	284
Effect of appointment of new arbitrator on evidence previously given and awards and determinations previously made.....	284
Decision of the Arbitrator	285
Appendix 6 – Matters to be Addressed by Technical Rules.....	287
Appendix 7 – General process for public consultation	289
Application of this Appendix 7	289
Where the decision maker is not the Authority.....	289
Issues paper	289
Submissions from the service provider	290
First round public submissions	290
Draft decision by the Decision Maker.....	290
Second round public submissions (if applicable)	290
Final decision by decision maker	291
Publication of submissions	291
Late submissions.....	291
Additional consultation.....	291
Extension of deadlines	291
Appendix 8 — Detailed provisions regarding contributions for certain work on the Western Power Network.....	293
Definitions.....	293
Scope of Appendix 8 work to Western Power Network.....	294
General principles.....	295
Subdivisions	295
Pole to pillar connections.....	295
Development of buildings	296
Initiating or joining an SES	296
Contribution for applicant initiating a scheme.....	296
Contribution for applicant joining an existing scheme	297
Rebate to continuing scheme members.....	297
Rebates will not be paid after 10 years	297
Work in excess of standard requirements	297
Temporary connections	298
Streetlights, unmetered connections, relocations, undergrounding and some temporary connections	298
If required work comprises more than just Appendix 8 work.....	298
Appendix 9 — [Appendix not used].....	299
[Heading not used]	299
[Heading not used]	299
[Heading not used]	299
[Heading not used]	299
[Heading not used]	299
[Heading not used]	300
[Heading not used]	300
[Heading not used]	300

Introduction

{This Code is made by the Minister under Part 8 of the *Electricity Industry Act 2004* (“**Act**”).

The Code may be amended from time to time in accordance with the procedure set out in sections 108 to 110 of the Act and must be reviewed every 5 years under section 111 of the Act.

The Code aims to be, where appropriate given conditions prevailing in Western Australia:

- consistent with the National Electricity Code and National Gas Code; and
- capable of certification as an effective *access* regime under Part IIIA of the *Trade Practices Act 1974*.

This Code establishes a framework for third party *access* to electricity transmission and distribution networks with the objective of promoting the economically efficient investment in, and operation and use of, *networks* and *services of networks* in Western Australia in order to promote competition in markets upstream and downstream of the *networks*.

Regulations made under section 118 of the Act may prescribe penalties for failure to comply with certain provisions of this Code.}

Chapter 1 – Introductory

Citation

1.1 This Code may be cited as the Electricity Networks Access Code 2004.

Commencement

1.2 This Code comes into operation on the date on which this Code is *published* in the Gazette.

Definitions

1.3 In this Code, unless the contrary intention appears:

"2020 (No. 2) amendments" means the amendments made to this Code by the *Electricity Networks Access Code Amendments (No. 2) 2020*.

{Note: The *Electricity Networks Access Code Amendments (No. 2) 2020* were Gazetted on 18 September 2020.}¹

"above-benchmark surplus" has the meaning given to it in section 6.25.²

"access", in relation to *services*, has a meaning corresponding with the meaning that it has when used in that context in the *Competition and Consumer Act 2010* of the Commonwealth.³

"access application" means—

- (a) an application lodged with a *service provider* under an *access arrangement* to establish or modify an *access contract* or to modify any other *contract for services*⁴; and
- (b) a *prior application* and a *transitioned application*,

and includes any additional information provided by the *applicant* in relation to the *application*.

"access arrangement" means an arrangement for *access* to a *covered network* that has been approved by the *Authority* under this Code.

"access arrangement information", in relation to an *access arrangement*, means the information submitted by the *service provider* under section 4.1 as described in

¹ Section 1.3 amended by WAGG No 157, 18 September 2020

² Section 1.3 amended by WAGG No 157, 18 September 2020

³ Section 1.3 amended by WAGG No 137, 29 June 2007; Section 1.3 amended by WAGG No 157, 18 September 2020

⁴ Section 1.3 amended by WAGG No 180, 22 October 2008

sections 4.2 and 4.3, as amended from time to time, and is not part of the *access arrangement*.

“**access arrangement period**”, in relation to an *access arrangement*, means a period:

- (a) between the *access arrangement start date* and the first *revisions commencement date*; or
- (b) between a *revisions commencement date* and the next *revisions commencement date*.

“**access arrangement start date**” means the day on which an *access arrangement* (other than an *interim access arrangement*) takes effect, and is determined in accordance with 4.26.

{Note: See definition of “**review**” for *access arrangement review*.}

“**access contract**” has the same meaning as ‘access agreement’ does in Part 8 of the Act, and under section 13.4(d) includes a *deemed access contract*.

{Note: At the time this Code was made, the definition in section 103 of the Act was:

‘ “**access agreement**” means an agreement under the *Code* between a network *service provider* and another person (a “network user”) for that person to have *access to services*. ’}

“**access dispute**” means a dispute, in connection with an *access application*, between the *applicant* and the *service provider*, including a dispute in relation to any one or more of the following (and the paragraphs of this definition do not limit each other):⁵

- (a) whether the *applicant* or the *service provider* has complied with, or the manner in which the *applicant* or the *service provider* has purported to comply with, the *applications and queuing policy*; and
- (b) the terms and conditions, including *service standards*, on which the *applicant* should be permitted to acquire *covered services* from the *service provider*; and
- (c) whether *work* is *required work* and the terms and conditions applying, or proposed to apply, to any such *work*; and⁶
 - (ca) anything connected with or arising out of a proposed *contribution*; and⁷
 - (cb) a matter heard under section 15.7; and
 - (cc) anything connected with or arising out of Appendix 8; and

⁵ Section 1.3 amended by WAGG No 180, 22 October 2008

⁶ Section 1.3 amended by WAGG No 180, 22 October 2008

⁷ Section 1.3 amended by WAGG No 180, 22 October 2008

- (cd) [not used]⁸
- (d) whether the *service provider* should grant the *applicant* an exemption to the *technical rules* under section 12.34; and
- (e) the arrangements which will apply in respect of a *supplementary matter* connected with the *access application*.

“**access reform costs**” means costs incurred by a *service provider* to undertake and deliver the *access reform work*, including costs incurred prior to the commencement of the *2020 (No. 2) amendments*.⁹

“**access reform work**” means the program of work undertaken by a *service provider* necessary to complete:

- (a) the development and provision of *network constraints information*; and
- (b) preparation of the initial *whole of system plan*.¹⁰

“**access rights**” means all or part of a *user’s* rights under a *contract for services* to obtain a *covered service*.¹¹

“**additional revenue**”, when used in 6.41, has the meaning given to it in section 6.42.

¹²

“**AEMO**” or “**Australian Energy Market Operator**” means the Australian Energy Market Operator Limited (ACN 072 010 327).¹³

¹⁴

“**alternative option non-capital costs**” has the meaning given to it in section 6.41.¹⁵

“**alternative options**” means alternatives to part or all of a *major augmentation* or *new facilities investment*, including *stand-alone power systems*, *storage works*, demand-side management and *generation* solutions (such as distributed *generation*), either instead of or in combination with *network augmentation*.¹⁶

¹⁷

⁸ Section 1.3 amended by WAGG No 137, 29 June 2007; Section 1.3 amended by WAGG No 157, 18 September 2020

⁹ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁰ Section 1.3 amended by WAGG No 157, 18 September 2020

¹¹ Section 1.3 amended by WAGG No 180, 22 October 2008

¹² Section 1.3 amended by WAGG No 157, 18 September 2020

¹³ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁴ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁵ Section 1.3 amended by WAGG No 180, 22 October 2008

¹⁶ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁷ Section 1.3 amended by WAGG No 157, 18 September 2020

18

“**alternative options strategy**” has the meaning given in section 6A.3.¹⁹

“**annual price list**” has the meaning given to it in section 8.1(b).²⁰

“**anticipated incremental revenue**” for a *new facility* means:

(a) the present value (calculated at the *rate of return* over a reasonable period) of the increased income from *charges* (excluding any *contributions*)²¹ reasonably anticipated to arise from the increased sale of *covered services* on the network to one or more *users* (where “increased sale of *covered services*” means sale of *covered services* which would not have occurred had the *new facility* not been commissioned),

minus

(b) the present value (calculated at the *rate of return* over the same period) of the best reasonable forecast of the increase in *non-capital costs* directly attributable to the increased sale of the *covered services* (being the *covered services* referred to in the expression “increased sale of *covered services*” in paragraph (a) of this definition),

where the “**rate of return**” is a rate of return determined by the *Authority* in accordance with the *Code objective* and in a manner consistent with Chapter 6, which may (but does not have to) be the rate of return most recently approved by the *Authority* for use in the *price control* for the *covered network* under Chapter 6.

“**Appendix 8 work**” means *work* in connection with the *Western Power Network* of a type specified in clause A8.2 of Appendix 8.²²

“**applicant**” means—

(a) a person (who may be a *user*) who has lodged an *access application* under the *access arrangement* for a *covered network* to establish or modify a *contract for services*, and includes a prospective *applicant*; and

(b) a *prior applicant*.²³

²⁴“**applications and queuing policy**” means a policy in an *access arrangement* setting out the *access application* process under section 5.1(g).

¹⁸ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁹ Section 1.3 amended by WAGG No 157, 18 September 2020

²⁰ Section 1.3 amended by WAGG No 157, 18 September 2020

²¹ Section 1.3 amended by WAGG No 152, 1 September 2006; Section 1.3 amended by WAGG No 180, 22 October 2008

²² Section 1.3 amended by WAGG No 137, 29 June 2007; Section 1.3 amended by WAGG No 180, 22 October 2008

²³ Section 1.3 amended by WAGG No 137, 29 June 2007; Section 1.3 amended by WAGG No 180, 22 October 2008

²⁴ Section 1.3 amended by WAGG No 137, 29 June 2007

“**approval**” of a *proposed access arrangement* or *proposed revisions* means *approval* by the *Authority* under Chapter 4.

“**approved extension and expansion policy**” has the meaning given to “approved policy” in section 60 of the Act.

{Note: At the time this definition was inserted in this Code, the definition of “approved policy” in section 60 of the Act was—

“ ‘**approved policy**’ means an extension and expansion policy approved under section 62 as amended from time to time and includes any replacement for the policy approved under section 63”}”²⁵

“**approved price list**” means a *price list* approved by the *Authority*.²⁶

“**approved total costs**”, in relation to *covered services* provided by a *service provider* by means of a *covered network* for a period of time, means:

- (a) the *capital-related costs* determined in accordance with section 6.43; and
- (b) those *non-capital costs* which satisfy the test in (as applicable) section 6.40 or 6.41.²⁷

“**arbitrator**” has the meaning given to that term in section 61 of the *Gas Pipelines Access (Western Australia) Act 1998*.

“**associate**”, in relation to a person and subject to section 13.2, has the meaning it would have under Division 2 of Part 1.2 of the *Corporations Act 2001* of the Commonwealth if sections 13²⁸, 16(2) and 17 of that Act were repealed, except that a person will not be considered to be an *associate* of a *service provider* solely because that person proposes to enter, or has entered, into a contract, arrangement or understanding with the *service provider* for the provision of a *covered service*.

{Note: Reference must be made to the *Corporations Act 2001* (Cth) to determine whether one person is an associate of another person. At the *Code commencement date*, the following are examples of persons who are *associates* of a body corporate under the *Corporations Act 2001* (Cth):

- a director or secretary of the body corporate; and
- a *related body corporate* of the body corporate; and
- another body corporate that can control or influence the composition of the board or the conduct of the affairs of a body corporate.}

“**associate contract**” means any contract, arrangement or understanding by which a *service provider* provides *covered services* to an *associate* or a *related body corporate*.

²⁵ Section 1.3 amended by WAGG No 206, 8 December 2006

²⁶ Section 1.3 amended by WAGG No 157, 18 September 2020

²⁷ Section 1.3 amended by WAGG No 152, 1 September 2006; Section 1.3 amended by WAGG No 180, 22 October 2008

²⁸ Section 1.3 amended by WAGG No 207, 8 November 2005

“**augmentation**”, in relation to a *covered network*, means an increase in the capability of the *covered network* to provide *covered services*.²⁹

“**Authority**” means the Economic Regulation Authority established by the *Economic Regulation Authority Act 2003*.

“**average cost of service provision**”, in relation to a *customer* or group of *customers*, a *covered service* and a specified period of time, means that part of *approved total costs* that is associated with providing the *covered service* to the *customer* or group of *customers*, during the period of time.³⁰

31

“**bidirectional point**” means a point on a *covered network* identified as such in a *contract for services* at which, subject to the *contract for services*, electricity is expected to be, on a regular basis, both transferred into the *network* and transferred out of the *network*.³²

“**bidirectional service**” means a *covered service* provided by a *service provider* at a *bidirectional point* under which the *user* may transfer electricity into and out of the *network* at the *bidirectional point*.³³

“**business day**” means a day that is not a Saturday, Sunday or public holiday throughout Western Australia.

“**capital base**” for a *covered network* means the value of the *network assets* that are used to provide *covered services* on the *covered network* determined under sections 6.44 to 6.63.

“**capital contribution**” means a payment or *provision in kind* made, or to be made, by a *user* in respect of any *new facilities investment in required work*.³⁴

35

“**capital-related costs**”, in relation to *covered services* provided by a *service provider* by means of a *covered network* for a period of time, means:

- (a) a return on the *capital base* of the *covered network*; and
- (b) depreciation of the *capital base* of the *covered network*.

“**Chapter 9 objectives**” has the meaning given to it in section 9.1.

²⁹ Section 1.3 amended by WAGG No 180, 22 October 2008

³⁰ Section 1.3 amended by WAGG No 157, 18 September 2020

³¹ Section 1.3 amended by WAGG No 180, 22 October 2008; Section 1.3 amended by WAGG No 157, 18 September 2020

³² Section 1.3 amended by WAGG No 134, 30 July 2021

³³ Section 1.3 amended by WAGG No 134, 30 July 2021

³⁴ Section 1.3 amended by WAGG No 180, 22 October 2008

³⁵ Section 1.3 amended by WAGG No 180, 22 October 2008

“**charge**”, for a *user* for a *covered service*, means the amount that is payable by the *user* to the *service provider* for the *covered service*, calculated by applying the *tariff* for the *covered service*.

“**charging parameters**” means the constituent elements of a *reference tariff*.³⁶

“**Code change**” means an amendment to this Code after the start of an *access arrangement period*.³⁷

“**Code commencement date**” means the date on which this Code is *published* in the Gazette.

“**Code objective**” has the meaning given to it in section 2.1.

“**commercially sensitive information**” means all confidential or *commercially sensitive information* in relation to an *applicant*, *user* or *consumer* which is developed by or comes into the possession of a *service provider* including a *ringfenced business’s* past, present and future dealings with the *applicant*, *user* or *consumer*.

“**committed**”, in relation to a *proposed major augmentation*, has the meaning given to it in section 9.5 as limited by section 9.6.

“**common service**” means a *covered service* that is ancillary to the provision of one or more of *entry services*, *exit services* and network use of system *services* that ensures the reliability of a network or otherwise provides benefits to *users* of the network, the costs of which cannot reasonably be allocated to one or more particular *users* and so needs to be allocated across all *users*.

“**competing applications**”, subject to section 5.9A, exist where the provision of the *covered service* sought in one *access application* may impede the *service provider’s* ability to provide a *covered service* sought in one or more other *access applications*.³⁸

“**compliance report**” means a report submitted by a *service provider* to the *Authority* under section 6.32H.³⁹

“**confidential material**” means *relevant material* which the *disclosing person* advises the *recipient* is of a confidential or commercially sensitive nature.

“**connect**” means to form a physical link to or through a network.

“**connection assets**”, for a *connection point*, means all of the *network assets* that are used only in order to provide *covered services* at the *connection point*.

“**connection point**” means a point on a *covered network* identified in, or to be identified in, a *contract for services* as an *entry point*, *exit point* or *bidirectional point*.⁴⁰

³⁶ Section 1.3 amended by WAGG No 157, 18 September 2020

³⁷ Section 1.3 amended by WAGG No 180, 22 October 2008

³⁸ Section 1.3 amended by WAGG No 180, 22 October 2008

³⁹ Section 1.3 amended by WAGG No 157, 18 September 2020

⁴⁰ Section 1.3 amended by WAGG No 206, 8 December 2006; Section 1.3 amended by WAGG No 180, 22 October 2008; Section 1.3 amended by WAGG No 134, 30 July 2021

“connection service” means the right to *connect facilities and equipment* at a *connection point*.

{Note: A *connection service* is the right to physically *connect* to the network, and will regulate technical compliance etc. It is not the same thing as an *entry service* or *exit service*, which are the right to transfer electricity.}

“constraint” means a limitation on the capability of a *covered network* (including arising by reference to the technical limitations and configuration of the *covered network*) such that it is unsafe, inconsistent with the maintenance of the reliability and security of the *covered network* or otherwise unacceptable to transfer (including accept the transfer of electricity into or out of the *covered network* at a *connection point*) the level of electricity that would occur if the limitation was removed. Constraints affecting the *covered network* may change over time due to changes in *load* or generation connected to the *covered network*.⁴¹

“consume” means to consume electricity.

“consumer” means a person who consumes electricity.

{Note: A *consumer* may also be a *user*, if it acquires a *covered service* from a *service provider*.}

“contestable”, in relation to a *consumer*, means a *consumer* to whom the supply of electricity is not restricted under section 54 of the *Electricity Corporations Act 2005* or under another enactment dealing with the progressive introduction of *consumer contestability*.⁴²

“contract for services” means an agreement between a *service provider* and another person for the person to have access to *services*, and includes an *access contract*.

{Note: The expression **“contract for services”** is broader than *“access contract”*, because it catches all such contracts and not merely those entered into under this Code. Hence it includes contracts entered into under the *Electricity Transmission Regulations 1996* and the *Electricity Distribution Regulations 1997*.}⁴³

“contractual dispute” means a dispute between a *service provider* and a *user* that is not an *access dispute* and is referred to the *arbitrator* under a *contract for services*.⁴⁴

“contributing user” means a *user* that is or may be required to make a *contribution*.⁴⁵

“contribution” means a *capital contribution*, a *non-capital contribution* or a *headworks charge*.⁴⁶

⁴¹ Section 1.3 amended by WAGG No 157, 18 September 2020

⁴² Section 1.3 amended by WAGG No 207, 8 November 2005; Section 1.3 amended by WAGG No 59, 31 March 2006; Section 1.3 amended by WAGG No 134, 30 July 2021

⁴³ Section 1.3 amended by WAGG No 180, 22 October 2008

⁴⁴ Section 1.3 amended by WAGG No 180, 22 October 2008

⁴⁵ Section 1.3 amended by WAGG No 180, 22 October 2008

⁴⁶ Section 1.3 amended by WAGG No 180, 22 October 2008

“**contributions policy**” means a policy in an *access arrangement* under section 5.1(h) dealing with *contributions by users*.⁴⁷

“**Coordinator**” means the Coordinator of Energy referred to in section 4 of the *Energy Coordination Act 1994*.

“**coverage applicant**” means a person who lodges a *coverage application*.

“**coverage application**” means an application under section 3.8 requesting that the whole or part of a *network be covered*.

“**coverage decision**”, for a *coverage application for a network*, means either or both of the *draft coverage decision* under section 3.17 by the Minister and the *final coverage decision* under section 3.21 by the Minister.

“**covered**”, with regard to a *network*, means either:

- (a) that the *network* is referred to in section 3.1, and the coverage has not been revoked under Subchapter 3.4; or
- (b) that the Minister has made a *final coverage decision* that the *network* should be *covered*, and the coverage has not been revoked under Subchapter 3.4.

{Note: Among other things, coverage of a network means that the *service provider* must submit a *proposed access arrangement* under section 4.1.}⁴⁸

“**covered network**” means a *network* that is *covered*.

{Note: The term *covered network* is defined more narrowly in this Code than in the Act, and therefore the definitions of the term are not identical.}⁴⁹

“**covered Pilbara network**” has the meaning in the Act.

{Note: At the time this definition was inserted, the definition in section 3(1) of the Act was –

“**covered Pilbara network**” means a covered network that is located wholly or partly in the Pilbara region;”⁵⁰

“**covered service**” means a *service* provided by means of a *covered network*, including:⁵¹

- (a) a *connection service*; or
- (b) an *entry service*, *exit service* or *bidirectional service*; or
- (c) a *network use of system service*; or

⁴⁷ Section 1.3 amended by WAGG No 180, 22 October 2008

⁴⁸ Section 1.3 amended by WAGG No 180, 22 October 2008

⁴⁹ Section 1.3 amended by WAGG No 134, 30 July 2021

⁵⁰ Section 1.3 amended by WAGG No 118, 2 July 2021

⁵¹ Section 1.3 amended by WAGG No 180, 22 October 2008; Section 1.3 amended by WAGG No 134, 30 July 2021

- (d) a *common service*; or
- (e) a *service* ancillary to a service listed in paragraphs (a) to (d) above, but does not include an *excluded service*.

{Note: This Code uses the expression *covered service* to describe what is sometimes called a 'regulated service'. It can be distinguished from an *excluded service*.

Covered services subdivide into *reference services* and *non-reference services*.)

"CPI" means the Consumer Price Index (all groups) for the Weighted Average of Eight Capital Cities most recently *published* by the Australian Bureau of Statistics or, if the Consumer Price Index (all groups) for the Weighted Average of Eight Capital Cities ceases to be *published*, such alternative index as the *Authority* may reasonably determine, and in all cases the *CPI* figure is to be adjusted to correct for any effects of a change in the rate of *GST* as defined in the *A New Tax System (Goods and Services Tax) Act 1999* of the Commonwealth.

"CPI adjusted" has the meaning given to it in section 14.26.

"customer" means a:

- (a) *user*; or
- (b) *end-use customer* in the *end-use customer's* capacity as indirect customer for *covered services*.⁵²

"customer transfer code" means a code made under section 39(1) or section 39(2a) of the Act in respect of the matter referred to in section 39(2)(b) of the Act.

"deadlock", in Chapter 12, means circumstances in which the members of a *technical rules committee* cannot reach consensus on a matter on which the *technical rules committee* has been requested to, or one or more of its members wishes to, provide advice to the *Authority*.⁵³

"decision maker", in Appendix 7, means a person who, under this Code, is obliged or chooses to consult the public under Appendix 7 on a *matter for consultation*.

"deemed access contract" means the full terms and conditions of the arrangement by which a *network business* is to provide *covered services* to an *other business*.

"demand management innovation allowance guidelines" means the guidelines *published* by the *Authority* under section 6.32D.⁵⁴

⁵² Section 1.3 amended by WAGG No 157, 18 September 2020

⁵³ Section 1.3 amended by WAGG No 180, 22 October 2008; Section 1.3 amended by WAGG No 183, 21 November 2014

⁵⁴ Section 1.3 amended by WAGG No 157, 18 September 2020

“**demand management innovation allowance mechanism**” means the mechanism developed and *published* by the *Authority* in accordance with section 6.32D.⁵⁵

“**demand management innovation allowance objective**” has the meaning given to it in section 6.32C.⁵⁶

“**designated date**” means the date by which a *service provider* must submit *proposed revisions* to the *Authority* after a *trigger event* has occurred and is either:

- (a) specified in the *access arrangement*; or
- (b) able to be determined, after the *trigger event* has occurred, using a method specified in the *access arrangement*.

“**Director of Energy Safety**” means the Director of Energy Safety appointed under section 5 of the *Energy Coordination Act 1994*.

“**disclosing person**” means a person who provides *relevant material* to a *recipient* under the *Code*.

“**discount**” means a discount referred to in section 7.9 or 7.10, as the case may be.

“**distributed generating plant**” means a *generating plant* with an *entry point* to a *network* at a nominal voltage of less than 66 kV and no *entry point* to a *network* at a nominal voltage of 66 kV or higher.

“**distribution reference tariff**” means a *reference tariff* applicable to a *reference service* provided by way of, or in respect of a *connection point* on, a *distribution system*.⁵⁷

“**distribution system**” means any apparatus, equipment, plant or buildings used, or to be used, for, or in connection with, the transportation of electricity at nominal voltages of less than 66 kV.

“**distribution system target revenue**” for a *network* for an *access arrangement period* means either:

- (a) if the *access arrangement* or *access arrangement information* apportion part or all of the *target revenue* for the *access arrangement period* to the *distribution system* — the amount so apportioned; or
- (b) otherwise — a percentage of the *target revenue* for the *access arrangement period* calculated by determining the part of the *capital base* which is attributable to the *distribution system* and then dividing it by the *capital base*, with the quotient expressed as a percentage.⁵⁸

“**DORC**” has the meaning given to it in section 6.46.

⁵⁵ Section 1.3 amended by WAGG No 157, 18 September 2020

⁵⁶ Section 1.3 amended by WAGG No 157, 18 September 2020

⁵⁷ Section 1.3 amended by WAGG No 157, 18 September 2020

⁵⁸ Section 1.3 amended by WAGG No 180, 22 October 2008

“draft coverage decision”, for a *coverage application* for a *network*, means a draft decision under section 3.17 by the Minister on the *coverage application* that the *network* be covered or not be covered.

“draft decision” means a draft decision by the *Authority* under section 4.12 either to *approve a service provider’s proposed access arrangement* or to not *approve the proposed access arrangement*.

“draft revocation decision”, for a *revocation application* for a *network*, means a draft decision under section 3.17 (as modified under section 3.31) by the Minister on a *revocation application* that a *network* be covered or not be covered.

“efficiency and innovation benchmarks” means efficiency and innovation benchmarks in an *access arrangement* under section 5.1(j).

“efficiently minimising costs”, in relation to a *service provider*, means the *service provider* incurring no more costs than would be incurred by a prudent *service provider*, acting efficiently, in accordance with *good electricity industry practice*, seeking to achieve the lowest sustainable cost of delivering *covered services* and without reducing *service standards* below the *service standard benchmarks* set for each *covered service* in the *access arrangement* or *contract for services*.⁵⁹

“electronic form”, in relation to the *public register*, means that the *public register* is kept on an internet website which is accessible to the public and from which information may be downloaded.

“end-use customer” means a *consumer* who obtains the benefit of *covered services* through a *user*.⁶⁰

“entry point” means a point on a *covered network* identified as such in a *contract for services* at which, subject to the *contract for services*, electricity is more likely to be transferred into the *network* than transferred out of the *network*.⁶¹

“entry service” means a *covered service* provided by a *service provider* at an *entry point* under which the *user* may transfer electricity into the *network* at the *entry point*.

“entry service component” means the component of a *bidirectional service* relating to the transfer of electricity by the *user* into the *network* at the *bidirectional point*.⁶²

“excluded service” means a *service* provided by means of a *covered network*, including:⁶³

- (a) a *connection service*; or
- (b) an *entry service*, *-exit service* or *bidirectional service*; or
- (c) a network use of system service; or

⁵⁹ Section 1.3 amended by WAGG No 180, 22 October 2008

⁶⁰ Section 1.3 amended by WAGG No 157, 18 September 2020

⁶¹ Section 1.3 amended by WAGG No 180, 22 October 2008

⁶² Section 1.3 amended by WAGG No 134, 30 July 2021

⁶³ Section 1.3 amended by WAGG No 180, 22 October 2008; Section 1.3 amended by WAGG No 134, 30 July 2021

- (d) a *common service*, or
- (e) a *service* ancillary to the *services* listed in paragraphs (a) to (d) above,

which meets the following criteria:

- (f) the supply of the *service* is subject to effective competition; and
- (g) the cost of the *service* is able to be excluded from consideration for *price control* purposes without departing from the *Code objective*.

“exclusive license” means an exclusive license granted under regulations made under section 26(1) of the Act.

“exclusivity right” means a contractual right which by its terms either:

- (a) expressly prevents a *service provider* supplying *covered services* to persons who are not parties to the contract; or
- (b) expressly places a limitation on the *service provider’s* ability to supply *covered services* to persons who are not parties to the contract,

but does not include a *user’s* contractual right to obtain a certain volume of *covered services*.

“exit point” means a point on a *covered network* identified as such in a *contract for services* at which, subject to the *contract for services*, electricity is more likely to be transferred out of the *network* than transferred into the *network*.⁶⁴

“exit service” means a *covered service* provided by a *service provider* at an *exit point* under which the *user* may transfer electricity out of the *network* at the *exit point*.

“exit service component” means the component of a *bidirectional service* relating to the transfer of electricity by the *user* out of the *network* at the *bidirectional point*.⁶⁵

“facilities and equipment”, in relation to a *connection point*, means the apparatus, equipment, plant and buildings used for or in connection with *generating, consuming* and *transporting* electricity at the *connection point*.

“final coverage decision”, for a *coverage application* for a *network*, means a final decision under section 3.21 by the Minister on the *coverage application* that the *network* be *covered* or not be *covered*.

“final decision” means a final decision by the *Authority* under section 4.17 either to *approve* the *service provider’s proposed access arrangement* or to not *approve* the *service provider’s proposed access arrangement*.

“final report” means a final report provided by the Chair of the *technical rules committee* to the *Authority* under section 12.11(b)(ii) setting out the *technical rules committee’s* progress in performing its functions under section 12.23, and in the case of deadlock, advice in accordance with section 12.25.

⁶⁴ Section 1.3 amended by WAGG No 180, 22 October 2008

⁶⁵ Section 1.3 amended by WAGG No 134, 30 July 2021

“final revocation decision”, for a *revocation application* for a *network*, means a final decision by the Minister on a *revocation application* under section 3.21 (as modified under section 3.31 that a network be covered or not be covered).

“first access arrangement”, for a *covered network*, means the first *access arrangement* approved (or if no *access arrangement* has been approved, to be approved) for the *covered network* under this Code.

“first access arrangement period”, for a *covered network*, means the *access arrangement period* for the *first access arrangement*.

“force majeure”, operating on a person, means a fact or circumstance beyond the person’s control and which a *reasonable and prudent person* would not be able to prevent or overcome.

“forecast new facilities investment”, for a *covered network*, means the capital costs forecast to be incurred in developing, constructing and acquiring new *network assets* for the *covered network*.

66

“form of regulation decision” has the meaning in the *Pilbara Networks Access Code*.

{Note: At the time this definition was inserted, the definition in section 5 of the *PNAC* was—

“**form of regulation decision**” means a decision by the Minister as to whether a covered Pilbara network is to be fully regulated or lighted regulated.”⁶⁷

“framework and approach” means a document prepared and issued by the *Authority* under section 4.A1.⁶⁸

“fully regulated” has the meaning in the *Pilbara Networks Access Code*.

{Note: At the time this definition was inserted, the definition in section 5 of the *PNAC* was –

“**fully regulated**” in relation to a network, means that the work is a full regulation network.”⁶⁹

“gain sharing mechanism” is defined in section 6.19.

“generate” means to produce electricity.

“generating plant”, in relation to a *connection point*, means all equipment involved in *generating electricity*.

“generator” means a person who *generates* electricity.

⁶⁶ Section 1.3 amended by WAGG No 157, 18 September 2020

⁶⁷ Section 1.3 amended by WAGG No 118, 2 July 2021

⁶⁸ Section 1.3 amended by WAGG No 157, 18 September 2020

⁶⁹ Section 1.3 amended by WAGG No 118, 2 July 2021

“good electricity industry practice” means the exercise of that degree of skill, diligence, prudence and foresight that a skilled and experienced person would reasonably and ordinarily exercise under comparable conditions and circumstances consistent with applicable *written laws* and *statutory instruments* and applicable recognised codes, standards and guidelines.

“headworks”, in respect of a *headworks scheme*, means the class of *works* identified under section 5.17D(a) as the class in respect of which the *headworks scheme* applies.⁷⁰

“headworks charge”, in respect of a *headworks scheme*, means a payment made, or to be made, by a *user* under the *headworks scheme* in respect of a *connection point*.⁷¹

“headworks scheme” means a scheme under section 5.17C.⁷²

“Horizon Power coastal network” has the meaning in the *Pilbara Networks Access Code*.

{Note: At the time this definition was inserted, the definition in section 5 of the *PNAC* was –

“Horizon Power coastal network” means the *network* comprising—

- (a) the *network* which became a *covered network* as a result of the Minister’s final coverage decision of 2 February 2018 under the ENAC; and
- (b) any other *network* owned by Regional Power Corporation and *interconnected* as at the *code commencement date* with the *network* in paragraph (a); and
- (c) any *augmentation* as at the *code commencement date* of a *network* in paragraph (a) or (b); and
- (d) any *augmentation* of the *network* which forms part of the *network* under section 4(1).⁷³

“incoming user” has the meaning given to it in section 5.7(f).

“incremental cost of service provision”, in relation to a *user* or group of *users*, a *covered service* and a specified period of time, means that part of *approved total costs* that would be avoided by the *service provider* during the specified period of time if it were not to provide the *covered service* to the *user* or group of *users*.

“information package” means an information package established and *maintained* by a *service provider* in relation to *covered network* which complies with section 14.1.

“initial price list” has the meaning given in section 8.1(a).⁷⁴

⁷⁰ Section 1.3 amended by WAGG No 180, 22 October 2008

⁷¹ Section 1.3 amended by WAGG No 180, 22 October 2008

⁷² Section 1.3 amended by WAGG No 180, 22 October 2008

⁷³ Section 1.3 amended by WAGG No 118, 2 July 2021

⁷⁴ Section 1.3 amended by WAGG No 157, 18 September 2020

“integrated provider” means:

- (a) [deleted]⁷⁵
- (b) a *service provider* which, under section 13.31, has been given an exemption from section 13.11(a).

“interconnected” has the meaning in the *Pilbara Networks Access Code*.

{Note: At the time this definition was inserted, the definition in section 5 of the *PNAC* was—

“**interconnected**” means a state in which two *networks* are or become *connected*, such that electricity can be transferred between them.”⁷⁶

“interconnected network”, in relation to a *network*, means another *network* which is part of the same *interconnected system* as the first *network*.

“interconnected system” means an electricity system comprising two or more *networks* interconnected with each other, and in relation to a particular *network* means an *interconnected system* of which the *network* is a part.

“interested person”, for a *network*, means a person who is registered under section 14.8 in respect of that *network*.

“interim access arrangement”, for a *covered network*, means an *access arrangement* drafted and approved by the *Authority* under section 4.59.

“interim access arrangement period”, for an *interim access arrangement*, means the period from the date of *approval* of the *interim access arrangement* until the *access arrangement start date* for the *covered network*.

“investment adjustment mechanism” has the meaning given to it in section 6.13.

“investment difference” has the meaning given to it in section 6.13.

“judicial proceedings” has the meaning given to it in section 4.69.

“lightly regulated” has the meaning in the *Pilbara Networks Access Code*.

{Note: At the time this definition was inserted, the definition in section 5 of the *PNAC* was—

“**lightly regulated**” in relation to a *network*, means that the *network* is a light regulation *network*.”⁷⁷

“light regulation network” has the meaning in the *Pilbara Networks Access Code*.

{Note: At the time this definition was inserted, the definition in section 5 of the *PNAC* was—

⁷⁵ Section 1.3 amended by WAGG No 59, 31 March 2006

⁷⁶ Section 1.3 amended by WAGG No 118, 2 July 2021

⁷⁷ Section 1.3 amended by WAGG No 118, 2 July 2021

“**light regulation network**” means a covered Pilbara network which is regulated by Part 8A of the Act.⁷⁸

“**load**” means the amount of electrical power transferred out of a *network* at a *connection point* at a specified time.

“**maintain**” includes (as necessary and as applicable) renew, replace or update.

“**major augmentation**” means an *augmentation* for which the *new facilities investment* for the *shared assets*:

- (a) exceeds \$10 million (*CPI adjusted*), where the *network assets* comprising the *augmentation* are, or are to be, part of a *distribution system*; and
- (b) exceeds \$30 million (*CPI adjusted*), where the *network assets* comprising the *augmentation* are, or are to be, part of:
 - (i) a *transmission system*; or
 - (ii) both a *distribution system* and a *transmission system*.⁷⁹

“**major augmentation proposal**” means a proposal in respect of one or more *proposed major augmentations* submitted by a *service provider* under sections 9.10 and 9.11, or under sections 9.15 and 9.16, as applicable.

“**major augmentation report**” has the meaning given to it in section 10.41(b).

80

“**marketing staff**” means servants, consultants, independent contractors or agents directly involved in sales, sale provision or advertising (whether or not they are also involved in other functions) but does not include servants, consultants, independent contractors or agents:

- (a) who are *senior staff*; or
- (b) involved only in technical, administrative, accounting or service functions.

“**matter for consultation**” means a document, determination or decision that under this Code is required to be or may be the subject of public consultation under Appendix 7.

“**model alternative option service contract**” means the model alternative option service contract approved by the *Authority* under section 6A.7.⁸¹

“**model applications and queuing policy**” means the model *applications and queuing policy* in Appendix 2.

⁷⁸ Section 1.3 amended by WAGG No 118, 2 July 2021

⁷⁹ Section 1.3 amended by WAGG No 180, 22 October 2008

⁸⁰ Section 1.3 amended by WAGG No 157, 18 September 2020

⁸¹ Section 1.3 amended by WAGG No 157, 18 September 2020

82

“**model contributions policy**” means the model *contributions policy* in Appendix 4.⁸³

“**model standard access contract**” means the model *standard access contract* in Appendix 3.

84

“**modified test**” means one or more modified tests set out in an *access arrangement* for the purposes of section 6.52(b)(i)B in respect of *new facilities investment* below one or more *test application thresholds*.

“**multi-function asset**” has the meaning given in section 6.84.⁸⁵

“**multi-function asset guidelines**” means the guidelines *published* by the *Authority* under section 6.88.⁸⁶

“**multi-function asset policy**” means a policy in an *access arrangement* under section 5.1(m).⁸⁷

“**multi-function asset principles**” means the principles under section 6.86.⁸⁸

“**net benefit**” means a net benefit (measured in present value terms to the extent that it is possible to do so) to those who *generate, transport and consume* electricity in (as the case may be):

- (a) the *covered network*; or
- (b) the *covered network* and any *interconnected system*.

“**net benefit after considering alternative options**” is defined in section 9.4.

“**net incremental revenue**” means, in relation to a *multi-function asset*, the revenue from all payments received by a *service provider* in excess of the revenue it would receive if the asset only provided *covered services*, for a *pricing year*.⁸⁹

“**network**” has the meaning given to “network infrastructure facilities” in the Act.

{Note: As at the date of the 2020 (No. 2) amendments, the definition in section 103 of the Act was:

“network infrastructure facilities” –

⁸² Section 1.3 amended by WAGG No 180, 22 October 2008

⁸³ Section 1.3 amended by WAGG No 180, 22 October 2008

⁸⁴ Section 1.3 amended by WAGG No 180, 22 October 2008; Section 1.3 amended by WAGG No 183, 21 November 2014

⁸⁵ Section 1.3 amended by WAGG No 157, 18 September 2020

⁸⁶ Section 1.3 amended by WAGG No 157, 18 September 2020

⁸⁷ Section 1.3 amended by WAGG No 157, 18 September 2020

⁸⁸ Section 1.3 amended by WAGG No 157, 18 September 2020

⁸⁹ Section 1.3 amended by WAGG No 157, 18 September 2020

- (a) means electricity infrastructure used, or to be used, for the purpose of transporting electricity from generators of electricity to other electricity infrastructure or to end users of electricity; and
- (b) includes stand-alone power systems, or storage works, used, or to be used, as an adjunct to electricity infrastructure.⁹⁰

“network assets”, in relation to a *network*, means the apparatus, equipment, plant and buildings used to provide or in connection with providing *covered services* on the *network*, which assets are either *connection assets* or *shared assets*.

“network business” means the part of an *integrated provider’s* business and functions which are responsible for the operation and maintenance of a *covered network* and the provision of *covered services* by means of the *covered network*.

“network constraints information” means the information relating to limits of the *Western Power Network* to transfer and/or convey electricity that a *service provider* must establish, maintain and/or provide to *AEMO* in accordance with its functions under sections 1.32, 2.27A, 2.27B and 2.27C of the *WEM Rules*.⁹¹

“network modification”, when used in sections 3.36 to 3.37, means, in respect of a *covered network*, either:

- (a) the commissioning of an *augmentation* to the *covered network*; or
- (b) a disposal or decommissioning of *network assets* of the *covered network*.

“network persons”, means the *service provider*, *applicants*, *users* and controllers of a *covered network* where the *service provider* of the *covered network* has applied to the *Authority* for an exemption from one or more requirements of the *technical rules* applying to the *covered network*.

“new facilities investment”, for a *new facility*, means the capital costs incurred in developing, constructing and acquiring the *new facility*.

“new facilities investment test”, in respect of a *covered network*, means the test set out in section 6.52.

“new facility” means any capital asset developed, constructed or acquired to enable the *service provider* to provide *covered services* and to avoid doubt, including *stand-alone power systems*, *storage works* or other assets required for the purpose of facilitating competition in retail markets for electricity.⁹²

“non-capital contribution”, means a payment or *provision in kind* made, or to be made, by a *user* in respect of any *non-capital costs* of *required work*.⁹³

“non-capital costs”, in relation to *covered services* provided by a *service provider* by means of a *covered network* for a period of time, means all costs incurred in providing the *covered services* for the period of time which are not *new facilities investment* or

⁹⁰ Section 1.3 amended by WAGG No 157, 18 September 2020

⁹¹ Section 1.3 amended by WAGG No 157, 18 September 2020

⁹² Section 1.3 amended by WAGG No 157, 18 September 2020

⁹³ Section 1.3 amended by WAGG No 180, 22 October 2008

capital-related costs, including those operating, *maintenance* and administrative costs which are not *new facilities investment* or *capital-related costs*.⁹⁴

{Note: Because of the differences in how capital costs and non-capital costs can be treated in this Code, the expression “non-capital costs” is sometimes juxtaposed against “new facilities investment” (for example in Chapter 5) and sometimes against “*capital-related costs*” (for example in Chapter 6).}⁹⁵

“**non-covered network**” means a *network* that is not a *covered network*.

“**non-reference service**” means a *covered service* that is not a *reference service*.

“**notification threshold**” has the meaning given to it in section 3.37.

“**ODV**” has the meaning given to it in section 6.46.

“**other business**” means the part or parts of an *integrated provider’s* business which are not the *network business*, and includes any part or parts of the *integrated provider’s* business and functions which acquire *covered services* from the *network business*.

“**other service provider**”, in relation to a *service provider* that operates a *network* in an *interconnected system*, has the meaning given to it in section 12.59.

“**outgoing user**” has the meaning given to it in section 5.7(h).

“**participant**”, when used in sections 14.16 to 14.21, has the meaning given in section 4.17.

“**Pilbara network**” has the meaning in the Act.

{Note: At the time this definition was inserted, the definition in section 3(1) of the Act was—

“**Pilbara network**” means network infrastructure facilities that are located wholly or partly in the Pilbara region;”⁹⁶

“**Pilbara Network Access Code**” or “**PNAC**” means the *Pilbara Networks Access Code 2021*.⁹⁷

“**preliminary report**” means a preliminary report provided by the Chair of the *technical rules committee* to the *Authority* under section 12.11(b)(i) setting out the *technical rules committee’s* progress in performing its functions under section 12.23, and in the case of *deadlock*, advice in accordance with section 12.25.

“**previous regime**” means the *previous regulations* and sections 90 and 91 and Schedules 5 and 6 of the *Electricity Transmission and Distribution Systems (Access) Act 1994* as in effect immediately before 1 July 2007.⁹⁸

⁹⁴ Section 1.3 amended by WAGG No 180, 22 October 2008

⁹⁵ Section 1.3, note to definition of “non-capital costs” inserted by WAGG No 180, 22 October 2008

⁹⁶ Section 1.3 amended by WAGG No 118, 2 July 2021

⁹⁷ Section 1.3 amended by WAGG No 118, 2 July 2021

⁹⁸ Section 1.3 amended by WAGG No 137, 29 June 2007

“**previous regulations**” means the *Electricity Transmission Regulations 1996*, the *Electricity Distribution Regulations 1997* and the *Electricity Referee and Dispute Resolution Regulations 1997*, as in effect immediately before 1 July 2007.⁹⁹

“**price control**” means the provisions in an *access arrangement* under section 5.1(d) and Chapter 6 which determine *target revenue*.

{Note: *Price control* can consist of direct or indirect limits, and consists of a limit on the **level** of *tariffs* through the control of overall revenue. The **structure** of *tariffs* is dealt with by the *pricing methods* in Chapter 7.}

“**price control methodology**” means a methodology included in an *access arrangement* as part of *price control*.

{Examples of the things that might comprise *price control methodologies* are: the means for determining a suitable return on investment; the means of forecasting *load*; and calculation of the X factor if CPI-X is used.}

“**price list**” means the schedule of *reference tariffs* in effect in an *access arrangement* under Chapter 8 for a *covered network*.¹⁰⁰

101

“**pricing methods**” means the structure of *reference tariffs* in an *access arrangement* as defined in section 7.1.

“**pricing objective**” has the meaning given in section 7.3.¹⁰²

“**pricing principles**” means the requirements set out in sections 7.3D to 7.3J.¹⁰³

“**pricing years**” for an *access arrangement* are periods of no longer than one year, the start and end dates of which are set out in the *access arrangement*, which together account for the entire *access arrangement period* and in respect of which a *price list* must be submitted to the *Authority* under section 8.1.¹⁰⁴

105

106

“**priority**” means, in relation to—

- (a) an “access application” under the *PNAC*, the priority that the “applicant” has, as against any other “applicant” with a competing “access application” to

⁹⁹ Section 1.3 amended by WAGG No 137, 29 June 2007

¹⁰⁰ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁰¹ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁰² Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁰³ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁰⁴ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁰⁵ Section 1.3 amended by WAGG No 137, 29 June 2007; Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁰⁶ Section 1.3 amended by WAGG No 137, 29 June 2007; Section 1.3 amended by WAGG No 157, 18 September 2020

obtain “access” to “covered services” as determined in accordance with the “user access guide” (as each of those terms are defined in the *PNAC*); or

- (b) an *access application*, the priority that the *applicant* has, as against any other *applicant* with a competing *access application*, to obtain access to covered services as determined by the *applications and queuing policy* for the covered Pilbara network.¹⁰⁷

“**priority project**” means:

- (a) a project specified as a priority project in a *whole of system plan*; or¹⁰⁸
- (b) a project specified as a priority project in a *priority project determination*.¹⁰⁹

“**priority project determination**” means a determination made by the Minister under section 15.1A.¹¹⁰

“**proceedings**”, when used in Chapter 10 and Appendix 5, means any proceedings before the *arbitrator* under this Code whether final or interlocutory, and includes any application in connection with and at any stage of proceedings, and includes the making of an award.

“**processing**” an *access application* means the performance of all requirements under an *applications and queuing policy* necessary for the making of an *access offer* including engaging in discussions, preparing an *initial response* and carrying out a *preliminary assessment* and making an *access offer*.

“**proposed access arrangement**” means a proposed *access arrangement* that has been submitted by a *service provider* with the *Authority* for approval under this Code, but which has not been approved.

“**proposed award**”, in respect of an arbitration under Chapter 10 which is subject to Subchapter 10.3, means a document provided to the parties to the arbitration under section 10.40(a) which describes in reasonable detail the nature of the *major augmentation* that the *arbitrator* anticipates it will require the *service provider* to undertake in its award.

“**proposed generator performance standard**” has the meaning given to the term “Proposed Generator Performance Standard” in the *WEM Rules*.¹¹¹

“**proposed major augmentation**” means a *major augmentation* detailed in a *major augmentation* proposal under section 9.11(a) or 9.16(a), as applicable.

“**proposed revisions**” means *proposed revisions* to an *access arrangement* that, under section 4.37 or 4.48, have been submitted by a *service provider* to the *Authority* for approval under Chapter 4.

¹⁰⁷ Section 1.3 amended by WAGG No 118, 2 July 2021

¹⁰⁸ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁰⁹ Section 1.3 amended by WAGG [No], [date]

¹¹⁰ Section 1.3 amended by WAGG [No], [date]

¹¹¹ Section 1.3 amended by WAGG No 134, 30 July 2021

“**public register**” means the register established and *maintained* by the *Authority* under section 14.5.

“**publish**” means:

- (a) where the Minister is required to *publish* a thing — that the Minister must:
 - (i) provide the thing to the Coordinator; and
 - (ii) procure the Coordinator to place the thing on an internet website which is under the Coordinator’s control;
 - (b) where the *Authority* is required to *publish* a thing — that the *Authority* must:
 - (i) place the thing on its internet website; or
 - (ii) if relevant, place the thing on the *public register*,¹¹² and send a notice to each person listed on the *register of interested persons maintained* under section 14.8 in respect of the network to which the thing relates advising the person that the thing has been placed on the *public register*;
- and
- (c) where a *service provider* is required to *publish* a thing — that the *service provider* must place the thing on its internet website.¹¹²

“**queuing dispute**” has the meaning given to it in section 10.13.

“**reasonable and prudent person**” means a person acting in good faith and in accordance with *good electricity industry practice*.

“**reasons**”, in relation to a decision or other determination, means a statement of the decision-maker’s *reasons* for deciding including, as applicable:

- (a) findings on material questions of fact relied on by the decision-maker in reaching the decision;
- (b) reference to the evidence on which findings of fact are based; and
- (c) identification of the steps in the decision-making process, explanation of the link between the findings of fact and the final decision and a description of the role of policy or guidelines in the decision-making process.

“**recipient**” means, the *Authority* or a *service provider*, as applicable, when provided with *relevant material*.¹¹³

“**recoverable portion**”, for *new facilities investment* for a *covered network*, has the meaning given to it in section 6.57.

¹¹² Section 1.3 amended by WAGG No 157, 18 September 2020

¹¹³ Section 1.3 amended by WAGG No 180, 22 October 2008

“**redundant capital**”, for a *covered network*, means an amount determined under section 6.61 to be removed from the *capital base* of the *covered network*.

“**referee**” has the meaning given to it in the *Electricity Referee and Dispute Resolution Regulations 1997*, as in effect immediately before 1 July 2007.¹¹⁴

“**reference service**” means a *covered service* provided to a *user* and designated as a *reference service* in an *access arrangement* under section 5.1(a) for which there is a *reference tariff*, a *standard access contract* and *service standard benchmarks*.¹¹⁵

“**reference tariff**” means the *tariff* specified in a *price list* for a *reference service*.

{Note: Under section 10.20 an *arbitrator’s* award cannot require an *applicant* to pay more than the *reference tariff* for a *reference service*, or the *service provider* to accept less than the *reference tariff* for a *reference service*.}

“**reference tariff change forecast**” means, for a *service provider*, the forecast of price changes as referred to in section 7.1D.¹¹⁶

“**Regional Power Corporation**” means the body established by the *Electricity Corporations Act 2005* section 4(1)(d).¹¹⁷

“**register of interested persons**” means the register or registers *maintained* by the *Authority* under section 14.8.

“**registered generator performance standard**” has the meaning given to the term “Registered Generator Performance Standard” in the *WEM Rules*.¹¹⁸

“**regulatory test**” is defined in section 9.3.

“**related body corporate**” and “**related company**”, in relation to a body corporate, mean a body corporate that is related to the first-mentioned body corporate under the *Corporations Act 2001* of the Commonwealth.

“**related business**” means the business of generating, purchasing or selling electricity, but does not include generating, purchasing or selling electricity to the extent necessary:

- (a) for the safe and reliable operation of a *covered network*; or
- (b) to enable a *service provider* to provide balancing and ancillary *services* in connection with a *covered network*; or
- (c) to comply with an obligation under Part 9 of the Act.

{Note: Part 9 of the Act deals with the wholesale market.}

¹¹⁴ Section 1.3 amended by WAGG No 137, 29 June 2007

¹¹⁵ Section 1.3 amended by WAGG No 157, 18 September 2020

¹¹⁶ Section 1.3 amended by WAGG No 157, 18 September 2020

¹¹⁷ Section 1.3 amended by WAGG No 118, 2 July 2021

¹¹⁸ Section 1.3 amended by WAGG No 134, 30 July 2021

“relevant material” means information or a document provided to a *recipient* under the *Code*.

119

“required work” means *work* which is necessary in order to provide a *covered service* sought in an *access application*.¹²⁰

“review” of an *access arrangement* means the process set out in sections 4.46 to 4.52.

“revisions commencement date” means a date on which revisions to an *access arrangement* which have been approved by the *Authority* commence under section 4.46 (as modified under section 4.52).

“revisions submission date” is the date specified in an *access arrangement* under section 5.29(a) as the date by which the *service provider* must submit its *proposed revisions* to the *access arrangement* to the *Authority* under section 4.48.

“revocation applicant” means a person who applies to the Minister for the Minister to revoke coverage of a *covered network* as described in section 3.30.

“revocation application” means an application for revocation of coverage made under section 3.8¹²¹ (as modified under section 3.31).

“revocation decision”, for a *revocation application* for a network, means either or both of the draft *revocation decision* under section 3.17 (as modified under section 3.31) by the Minister and the final *revocation decision* under section 3.21 by the Minister.

“ringfenced business” is defined in section 13.3.

“ringfencing compliance procedures” means procedures established and *maintained* by a *service provider* as required by section 13.37(a) to ensure and monitor a *service providers* compliance with section 13.1.

“ringfencing objectives” means the objectives in section 13.11 (as added to under section 13.23 if applicable).

“ringfencing rules” means rules drafted and approved by the *Authority* under section 13.14 as varied from time to time under section 13.18.

“senior staff” means servants, consultants, independent contractors or agents involved strategic decision making, including directors and the executive officer or officers to whom marketing staff report either directly or indirectly.

122

¹¹⁹ Section 1.3 amended by WAGG No 180, 22 October 2008; Section 1.3 amended by WAGG No 157, 18 September 2020

¹²⁰ Section 1.3 amended by WAGG No 180, 22 October 2008

¹²¹ Section 1.3 amended by WAGG No 207, 8 November 2005

¹²² Section 1.3 amended by WAGG No 180, 22 October 2008

“service provider”, in relation to a *network*, means a person who owns or operates the *network*.

“services” has the meaning given to that term in Part 8 of the Act, and **“service”** has a corresponding meaning.

{Note: At the time the *Electricity Networks Access Code Amendments (No 2) 2008* were made, the definition in section 103 of the Act was:

“services” means –

- (a) the conveyance of electricity and other *services* provided by means of network infrastructure facilities; and
- (b) *services* ancillary to such *services*’.¹²³

“service standard benchmarks” means the benchmarks for *service standards* for a *reference service* in an *access arrangement* under section 5.1(c).

“service standard performance report” means a report provided by a *service provider* to the *Authority* under section 11.3.

“service standards” means either or both of the technical standard, and reliability, of delivered electricity.

“service standards adjustment mechanism” has the meaning given to it in section 6.29.

“shared assets” mean those *network assets* which are not *connection assets*.

“specific criterion” means an objective, requirement or factor specified in this Code in relation to a thing (including the making of any decision or the doing, or not doing, of any act), and **“specific criteria”** means any two or more such objectives, requirements or factors specified under this Code in relation to such a thing, whether or not all specified in one provision.

“speculative investment amount”, for a *new facility* (if any), is determined under section 6.58.

“stand-alone cost of service provision”, in relation to a *customer* or group of *customers*, a *covered service* and a specified period of time, means that part of *approved total costs* that the *service provider* would incur in providing the *covered service* to the *customer* or group of *customers*, for the period of time if the *covered service* was the sole *covered service* provided by the *service provider* and the *customer* or group of *customers* was the sole *customer* or group of *customers* supplied by the *service provider* during the specified period of time.¹²⁴

“stand-alone power system” has the meaning given to it in the Act.¹²⁵

¹²³ Section 1.3 amended by WAGG No 180, 22 October 2008

¹²⁴ Section 1.3 amended by WAGG No 157, 18 September 2020

¹²⁵ Section 1.3 amended by WAGG No 157, 18 September 2020

“**standard access contract**” means the terms and conditions for a *reference service* in an *access arrangement* under section 5.1(b).

“**standard tariff exit point**”, in section 7.7, means an *exit point* in respect of which the *contracted maximum demand* under a *contract for services* is less than 1 MVA.¹²⁶

“**standard tariff user**”, in section 7.7, means a *user* who transfers electricity out of a network at a *standard tariff exit point*.

“**statutory instruments**” means all relevant instruments made under a *written law* including all directions, notices, orders and other instruments given or made under a *written law* and includes, as existing from time to time:

- (a) orders made under section 8 of the Act; and
- (b) licences granted, renewed or transferred under section 19 of the Act; and
- (c) standard form contracts approved under section 51 of the Act; and
- (d) orders made under section 181(3) of the *Electricity Corporations Act 2005*;¹²⁷ and
- (e) approved policies as defined in section 60 of the Act¹²⁸; and
- (f) last resort supply plans approved under section 73 of the Act as amended under sections 74 and 75 of the Act; and
- (g) the *WEM Rules*.¹²⁹

“**storage works**” has the meaning given to it in the Act.¹³⁰

“**submission deadline**”, in relation to a *service provider’s* submission of a *proposed access arrangement* for a *covered network*, means the date which is six months after the network becomes *covered*.

“**supplementary matter**” has the meaning given to it in section 5.27 and *supplementary matters* must be dealt with in an *access arrangement* under section 5.1(k).

“**surplus**”, for a *covered network* for an *access arrangement period*, arises when the conditions described in section 6.23 are satisfied.¹³¹

¹³²

“**SWIS**” means the “South West interconnected system” as defined in the Act.

¹²⁶ Section 1.3 amended by WAGG No 180, 22 October 2008

¹²⁷ Section 1.3 amended by WAGG No 180, 22 October 2008

¹²⁸ Section 1.3 amended by WAGG No 180, 22 October 2008

¹²⁹ Section 1.3 amended by WAGG No 157, 18 September 2020

¹³⁰ Section 1.3 amended by WAGG No 157, 18 September 2020

¹³¹ Section 1.3 amended by WAGG No 137, 29 June 2007 and WAGG No 180, 22 October 2008

¹³² Section 1.3 amended by WAGG No 137, 29 June 2007 and WAGG No 180, 22 October 2008

{Note: Some parts of the SWIS are owned by the Western Power Corporation and some are privately owned.

As at the date of this Code the definition in the Act was:

‘ the interconnected transmission and distribution systems, generating works and associated works –

- (a) located in the South West of the State and extending generally between Kalbarri, Albany and Kalgoorlie; and
- (b) into which electricity is supplied by –
 - (i) one or more of the electricity generation plants at Kwinana, Muja, Collie and Pinjar; or
 - (ii) any prescribed electricity generation plant. ’}

“**target revenue**”, for a *covered network* for an *access arrangement period*, is determined in accordance with section 6.4(a).

“**target revisions commencement date**” is the date specified in an *access arrangement* under section 5.29(b) as the target date for the *revisions commencement date*.

“**tariff**”, for a *covered service*, means the criteria that determine the *charge* that is payable by a *user* to the *service provider*.

“**tariff structure statement**” means, for a *service provider*, the *tariff structure statement* referred to in section 7.1A that has been approved by the *Authority* for that *service provider*.¹³³

“**technical rules**”, for a *covered network*, means the *technical rules* (if any) approved for the *covered network* under Chapter 12.¹³⁴

“**technical rules committee**”, in relation to a *covered network* or *interconnected system*, means the current committee, if any, established under section 12.16 for the *covered network* or *interconnected system*.¹³⁵

“**technical rules start date**” for the *technical rules* for a *covered*¹³⁶ *network* is the date on which the *technical rules* take effect and is specified by the *Authority* under section 12.15.

“**test application threshold**”, for a modified test in an *access arrangement*, means the threshold for *new facilities investment* below which the modified test applies.

¹³³ Section 1.3 amended by WAGG No 157, 18 September 2020

¹³⁴ Section 1.3 amended by WAGG No 180, 22 October 2008; Section 1.3 amended by WAGG No 183, 21 November 2014

¹³⁵ Section 1.3 amended by WAGG No 183, 21 November 2014

¹³⁶ Section 1.3 amended by WAGG No 183, 21 November 2014

“**transfer**” refers to a novation of all or part of a *user’s* rights and obligations under an *access contract*.¹³⁷

“**transfer and relocation policy**” means the provisions of an *applications and queuing policy* that relate to a *user’s* rights to *transfer* its *access rights* to another person.¹³⁸

139

“**transmission connected generating system**” has the meaning given to the term “Transmission Connected Generating System” in the *WEM Rules*.¹⁴⁰

“**transmission system**” means any apparatus, equipment, plant or buildings used, or to be used, for, or in connection with, the transportation of electricity at nominal voltages of 66 kV or higher.

“**transport**” includes transmit and distribute.

“**trigger event**” is a set of one or more circumstances specified in an *access arrangement* under section 5.1(l)(ii), the occurrence of which requires a *service provider* to submit *proposed revisions* to the *Authority* under section 4.37.

“**user**” means a person, including a generator or a *consumer*, who is party to a *contract for services* with a *service provider*, and under section 13.4(e) includes an *other business* as a party to a deemed *access contract*.¹⁴¹

“**weighted average cost of capital**”, in relation to a *covered network*, is expressed as a percentage and means a weighted average of the cost of debt and the cost of equity as calculated under section 6.64.

“**WEM Rules**” means the market rules referred to in section 123(1) of the *Electricity Industry Act 2004 (WA)*.¹⁴²

“**Western Power Network**” means the *covered network* that is *covered* under section 3.1.

{Note:

- The SWIS is the South-West interconnected system including generation plant and *associated* equipment.
- The term “SWIN” is not used in this Code, but is commonly used to describe the network portion of the SWIS.

¹³⁷ Section 1.3 amended by WAGG No 157, 18 September 2020

¹³⁸ Section 1.3 amended by WAGG No 157, 18 September 2020

¹³⁹ Section 1.3 amended by WAGG No 137, 29 June 2007; Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁴⁰ Section 1.3 amended by WAGG No 134, 30 July 2021

¹⁴¹ Section 1.3 amended by WAGG No 180, 22 October 2008

¹⁴² Section 1.3 amended by WAGG No 157, 18 September 2020

- The “Western Power Network” is the portion of the SWIN that is owned by the Electricity Networks Corporation.¹⁴³

“**Western Power Network access arrangement**” means the *access arrangement* approved for the Western Power Network by the *Authority’s* Further Final Decision dated 26 April 2007.¹⁴⁴

“**Wholesale Electricity Market**” means the market referred to in section 122(1) of the *Electricity Industry Act 2004 (WA)*.¹⁴⁵

“**whole of system plan**” means the document *published* by the Minister from time to time as the Whole of System Plan for the efficient development of the *SWIS* over a 20 year period.¹⁴⁶

“**work**” means any activity or undertaking in connection with the *covered network*, whether of a capital or non-capital nature, including the planning, designing, development, *approval*, construction, acquisition and commissioning of *new facilities* and *new network assets* and the procurement or provision of any good or service.¹⁴⁷

“**workers**” of a person means the directors, officers, servants, employees, agents, sub-contractors and consultants of the person.

“**written law**” means:

- (a) all Western Australian Acts and all Western Australian subsidiary legislation for the time being in force; and
- (b) all Commonwealth Acts and all Commonwealth subsidiary legislation for the time being in force, where the term “subsidiary legislation” has the meaning given to it under the *Interpretation Act 1984*, if “Commonwealth Act” were substituted for “written law”.

Interpretation

1.4 This Code is a written law under the *Electricity Industry Act 2004*, and unless the contrary intention is apparent the *Interpretation Act 1984* applies to it.

1.5 In this Code, unless the contrary intention is apparent:

- (a) “**including**” and similar expressions are not words of limitation; and
- (b) where a word or expression is given a particular meaning, other parts of speech and grammatical forms of that word or expression have a corresponding meaning; and
- (c) a reference to a *law* includes any amendment or re-enactment of it that is for the time being in force, and includes all *laws* made under it from time to time; and

¹⁴³ Section 1.3 amended by WAGG No 180, 22 October 2008

¹⁴⁴ Section 1.3 amended by WAGG No 180, 22 October 2008

¹⁴⁵ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁴⁶ Section 1.3 amended by WAGG No 157, 18 September 2020

¹⁴⁷ Section 1.3 amended by WAGG No 180, 22 October 2008

- (d) where italic typeface has been applied to some words and expressions, it is solely to indicate that those words or expressions may be defined in section 1.3 or elsewhere, and in interpreting this Code the fact that italic typeface has or has not been applied to a word or expression is to be disregarded, to avoid doubt, nothing in this section 1.5(d) limits the application of section 1.3; and
- (e) where information in this Code (excluding the Appendices to this Code) ¹⁴⁸ is set out in braces (namely “{” and “}”), whether or not preceded by the expression “Note”, “Outline” or “Example”, the information:
 - (i) is provided for information only and does not form part of this Code; and
 - (ii) is to be disregarded in interpreting this Code; and
 - (iii) might not reflect amendments to this Code or other documents or *written laws*,and
- (ea) where information in the Appendices to this Code is set out in braces (namely “{” and “}”), whether or not preceded by the expression “Note”, “Outline” or “Example”, the information—
 - (i) is provided to assist readers; and
 - (ii) is to be regarded accordingly in interpreting this Code;and¹⁴⁹
- (f) a reference to:
 - (i) this Code includes any Appendix to this Code; and
 - (ii) a section, Chapter or Appendix is a reference to a section of, Chapter of or Appendix to this Code, and
 - (iii) a clause is a reference to a clause in an Appendix to this Code; and
- (g) without limiting section 1.4:
 - (i) where in this Code the word “may” is used in conferring a power, such word shall be interpreted to imply that the power may be exercised or not, at discretion¹⁵⁰;
 - (ii) where in this Code the word “must” is used in conferring a function, such word shall be interpreted to mean that the function so conferred must be performed.

¹⁴⁸ Section 1.5 amended by WAGG No 207, 8 November 2005

¹⁴⁹ Section 1.5 amended by WAGG No 207, 8 November 2005

¹⁵⁰ Section 1.5 amended by WAGG No 180, 22 October 2008

Chapter 2 – General Principles

Code objective

2.1 The objective of this Code (“**Code objective**”) is to promote efficient investment in, and efficient operation and use of, *services of networks* in Western Australia for the long-term interests of *consumers* in relation to:

- (a) price, quality, safety, reliability and security of supply of electricity;
- (b) the safety, reliability and security of *covered networks*; and
- (c) the environmental consequences of energy supply and consumption, including reducing greenhouse gas emissions, considering land use and biodiversity impacts, and encouraging energy efficiency and demand management.

{Note: *Consumers* in the context of the *Code objective* has the meaning in this Code being “a person who consumes electricity”.}¹⁵¹

2.2 The Minister, the *Authority* and the *arbitrator* must have regard to the *Code objective* when performing a function under this Code whether or not the provision refers expressly to the *Code objective*.

Code objective with other objectives, requirements and factors etc

2.3 Where this Code specifies one or more *specific criteria* in relation to a thing (including the making of any decision or the doing, or not doing, of any act), then:

- (a) subject to section 2.3(b), the *specific criteria* and the *Code objective* all apply in relation to the thing; and
- (b) subject to section 2.4, to the extent that a *specific criterion* and the *Code objective* conflict in relation to the thing, then:
 - (i) the *specific criterion* prevails over the *Code objective* in relation to the thing; and
 - (ii) to the extent that the *specific criterion* conflicts with one or more other *specific criteria* in relation to the thing, the *Code objective* applies in determining how the *specific criteria* can best be reconciled and which of them should prevail.

2.4 If the *Code objective* is specified in a provision of this Code as a *specific criterion*, then the *Code objective* is to be treated as being also a *specific criterion* for the purposes of section 2.3, but to the extent that the *Code objective* conflicts with one or more other *specific criteria* the *Code objective* prevails.

¹⁵¹ Section 2.1 amended by WAGG No 157, 18 September 2020

Freedom to contract

2.4A Subject to this Code (including without limitation section 2.4C) and to—

- (a) an *applications and queuing policy* in an *access arrangement*; and
- (b) the *ringfencing objectives* and any *ringfencing rules* approved for a network by the *Authority* under Chapter 13; and
- (c) any applicable *technical rules*,

a *service provider* (including Electricity Networks Corporation) and a *user* or *applicant* may negotiate regarding, and may make and implement, an *access contract* for access to any service (including a service which differs from a *reference service*) on any terms (including terms which differ from a *standard access contract*).

{Note: This provision confirms the Code's central emphasis on negotiated outcomes. The express reference to Electricity Networks Corporation confirms that such negotiation and agreement is within its functions under section 41(b) of the *Electricity Corporations Act 2005*.} ¹⁵²

2.4B Section 2.4A does not—

- (a) permit a *service provider*, *user* or *applicant* to do anything which a *written law* prohibits; or
- (b) by implication limit the rights, powers or obligations of a *service provider*, *user* or *applicant*. ¹⁵³

2.4C The *service provider* for the *Western Power Network* may not enter into an *access contract* which does not permit a *user's* export of electricity into the *Western Power Network* to be interrupted or curtailed in either of the following circumstances:

- (a) in circumstances where *constraints* are created by other *users* of the *Western Power Network* (including *users* that connected to the *Western Power Network* after the date of the relevant *access contract*); or
- (b) in connection with the operation of security constrained economic dispatch,

provided that this section 2.4C does not affect any agreements entered into by the *service provider* prior to the date of the *2020 (No. 2) amendments*.

{Note: The *2020 (No. 2) amendments* came into effect on 18 September 2020.} ¹⁵⁴

2.4D Nothing in section 2.4C prevents the inclusion of other interruption or curtailment rights in an *access contract* or the *standard access contract* including, without limitation, rights to curtail or interrupt for *force majeure*, maintenance, in emergencies, or as required by law. ¹⁵⁵

¹⁵² Section 2.4A inserted by WAGG No 176, 29 August 2007; Section 2.4A amended by WAGG No 157, 18 September 2020

¹⁵³ Section 2.4B inserted by WAGG No 176, 29 August 2007

¹⁵⁴ Section 2.4C inserted by WAGG No 157, 18 September 2020

¹⁵⁵ Section 2.4D inserted by WAGG No 157, 18 September 2020

- 2.4E The *Authority* must not make any determination or decision under this Code inconsistent with section 2.4C.¹⁵⁶
- 2.4F An *arbitrator* acting under this Code must not make any award, determination or decision inconsistent with section 2.4C.¹⁵⁷
- 2.5 Nothing in this Code except:
- (a) an *applications and queuing policy* in an *access arrangement*; and
 - (b) the *ringfencing objectives* and any *ringfencing rules* approved for a network by the *Authority* under Chapter 13; and
 - (ba) section 2.4C; and¹⁵⁸
 - (c) any applicable *technical rules*,
- limits:
- (d) the *services* a *service provider* may agree to provide to a *user* or *applicant*; or
 - (e) the terms for, or connected with, the provision of *services* which may be agreed between a *service provider* and a *user* or *applicant*; or
 - (f) the *covered services* which may be the subject of an *access dispute* or award under Chapter 10; or
 - (g) the terms for, or connected with, the provision of *covered services* which may be the subject of an *access dispute* or award under Chapter 10.
- 2.6 Nothing in this Code or an *access arrangement* prevails over or modifies the provisions of a *contract for services*, except for:¹⁵⁹
- (a) if an *access arrangement* is in effect for the network — the *applications and queuing policy*; and
 - (b) the *ringfencing objectives*, to the extent that they apply to the network, and any *ringfencing rules* in effect for the network; and
 - (c) any provisions of the *technical rules* which by this Code are expressed to prevail over such a contract; and
- {Note: See section 12.5.}
- (d) subject to section 10.32(a), an award by the *arbitrator*.

¹⁵⁶ Section 2.4E inserted by WAGG No 157, 18 September 2020

¹⁵⁷ Section 2.4F inserted by WAGG No 157, 18 September 2020

¹⁵⁸ Section 2.5 amended by WAGG No 157, 18 September 2020

¹⁵⁹ Section 2.6 amended by WAGG No 180, 22 October 2008

Service provider to use reasonable endeavours to provide access to covered services

- 2.7 Subject to section 2.4C, a *service provider* for a *covered network* must use all reasonable endeavours to accommodate an *applicant's*:¹⁶⁰
- (a) requirement to obtain *covered services*; and
 - (b) requirements in connection with the negotiation of an *access contract*.
- 2.8 Without limiting section 2.7, a *service provider* must:
- (a) comply with the *access arrangement* for its *covered network* and must expeditiously and diligently process *access applications*; and
 - (b) negotiate in good faith with an *applicant* regarding the terms for an *access contract*; and
 - (c) to the extent reasonably practicable in accordance with *good electricity industry practice*, permit an *applicant* to acquire a *covered service* containing only those elements of the *covered service* which the *applicant* wishes to acquire; and
 - (d) to the extent reasonably practicable, specify a separate *tariff* for an element of a *covered service* if requested by an *applicant*, which *tariff* must be determined in accordance with sections 10.23 and 10.24; and
 - (e) when forming a view as to whether all or part of any proposed *new facilities investment* meets the test in section 6.51A, form that view as a *reasonable and prudent person*.¹⁶¹
- 2.8A Nothing in section 2.7 affects the fact *registered generator performance standards* for a *transmission connected generating system* will be determined in accordance with the *WEM Rules* including that the *service provider's* obligation to accept *proposed generator performance standards* is determined in accordance with the provisions of the *WEM Rules* and not the procedures in this Code.¹⁶²
- 2.8B An *arbitrator* acting under this Code may not, as part of any award, decision or determination, determine *registered generator performance standards* for a *transmission connected generating system*.¹⁶³
- 2.9 [not used]¹⁶⁴
- 2.9A [not used]¹⁶⁵

¹⁶⁰ Section 2.7 amended by WAGG No 157, 18 September 2020

¹⁶¹ Section 2.8 amended by WAGG No 180, 22 October 2008

¹⁶² Section 2.8A inserted by WAGG No 134, 30 July 2021

¹⁶³ Section 2.8B inserted by WAGG No 134, 30 July 2021

¹⁶⁴ Section 2.9 amended by WAGG No 206, 8 December 2006; Section 2.9 amended by WAGG No 137, 29 June 2007; Section 2.9 deleted by WAGG No 180, 22 October 2008

¹⁶⁵ Section 2.9A inserted by WAGG No 206, 8 December 2006; Section 2.9A deleted by WAGG No 137, 29 June 2007

Requirement to undertake work and funding of work¹⁶⁶

- 2.10 Subject to section 2.11, the *service provider* must undertake and fund any *required work*.¹⁶⁷
- 2.11 If one or more *contributions* are required to be made under the *contributions policy* or under section 5.17A in respect of *required work*, then the *service provider* may refuse to undertake and fund any relevant *required work* under section 2.10 until either:
- (a) the *applicant* provides the *contributions*; or
 - (b) the *applicant* and the *service provider* reach agreement on, or the *arbitrator* determines, the terms on which the *applicant* will make the *contributions*.¹⁶⁸
- 2.12 If *work*:
- (a) is of a class which is or has been identified as *headworks* under any current or past *headworks scheme*; and
 - (b) is necessary in accordance with *good electricity industry practice*,
- then the *service provider* must undertake and fund the *work*, despite section 2.11 and whether or not the *work* is *required work*.¹⁶⁹

¹⁶⁶ Heading to section 2.10 inserted by WAGG No 180, 22 October 2008

¹⁶⁷ Section 2.10 inserted by WAGG No 180, 22 October 2008

¹⁶⁸ Section 2.11 inserted by WAGG No 180, 22 October 2008

¹⁶⁹ Section 2.12 inserted by WAGG No 180, 22 October 2008

Chapter 3 – Coverage

{Note: This Chapter 3 deals with the two ways by which networks located anywhere in Western Australia can become covered, namely—

- by prescription as in Subchapter 3.1; or
- by Ministerial decision under Subchapter 3.2.

For *Pilbara networks*, there are two other ways a network can become covered, namely—

- by prescription in the *PNAC* (see section 120B(a) of the Act and Subchapter 3.1 of the *PNAC*); or
- by a *service provider* opting under the *PNAC* for the *Pilbara network* to be regulated under Part 8A of the Act (see Subchapter 3.3 of the *PNAC*).

All four classes of *covered network* may apply under this Code for revocation of coverage under section 3.30 (see section 104A(1)(b) of the Act).

If the Minister makes a *final coverage decision* that a *Pilbara network* be covered, then the Minister must concurrently make a *form of regulation decision* under the *PNAC*.

Under section 104A(2) of the Act this Code applies to regulate only *covered networks* that are regulated under Part 8 of the Act. The *PNAC* applies to regulate only *covered Pilbara networks* that are regulated under Part 8A of the Act (that is, *light regulation networks*).¹⁷⁰

Subchapter 3.1 – Covered networks

Western Power Network is covered¹⁷¹

3.1 The portions of the *SWIS* which are owned by Electricity Networks Corporation are a *covered network* from the *Code commencement date*, unless coverage has subsequently been revoked under section 3.30.¹⁷²

When coverage starts for Horizon Power's Pilbara network¹⁷³

3.1A Despite the date specified for this purpose in the Minister's final coverage decision dated 2 February 2018 and entitled "Coverage of the Horizon Power electricity network in the North West Interconnected System", that decision will have effect on 1 July 2021.

{Note: The Minister's final coverage decision applies to those parts of the *Horizon Power coastal network* which were in existence on 2 February 2018. Section 17 of the *PNAC* then prescribes those parts, plus the balance of the *Horizon Power coastal network* as at 1 July 2021, to be *lightly regulated* under Part 8A of the Act. The combined effect is that the whole of the *Horizon Power coastal network* is a

¹⁷⁰ Note to Chapter 3 inserted by WAGG No 118, 2 July 2021

¹⁷¹ Heading to section 3.1 amended by WAGG No 180, 22 October 2008

¹⁷² Section 3.1 amended by WAGG No 180, 22 October 2008

¹⁷³ Heading to section 3.1A inserted by WAGG No 108, 26 June 2020

covered network from 1 July 2021. The Minister may make further decisions under section 3.1B of this Code extending the scope of that *covered network*.)¹⁷⁴

- 3.1B The Minister may decide under section 104A(1)(a) of the Act that any *network* owned by *Regional Power Corporation* and *interconnected* with the *Horizon Power coastal network* is to be part of that *covered network*.¹⁷⁵
- 3.1C The Minister must *publish* a decision made under section 3.1B but Subchapters 3.2 and 3.3 do not apply to the making of that decision.¹⁷⁶

Other networks may be covered

- 3.2 A network other than the Western Power Network may become *covered* after the *Code commencement date* where a person makes a *coverage application* in respect of the network and the Minister decides under section 3.21(a) that the *network* should be *covered*.¹⁷⁷
- 3.2A *Pilbara network* that is deemed to be a *light regulation network* under section 31(4) of the *PNAC* can only be the subject of a *coverage application* as provided for in section 31(5) of the *PNAC*.¹⁷⁸

Subchapter 3.2– Criteria for coverage

Minister’s decision on coverage

- 3.3 [not used]¹⁷⁹
- 3.4 If a *coverage decision* is that a network be *covered*, the *coverage decision* may cover the network to a greater or lesser extent than requested in the *coverage application* if, having regard to the part of the network that is necessary to provide *covered services* that *applicants* may seek, the Minister considers that doing so is consistent with the *Code objective*.

Coverage criteria

- 3.5 A *coverage decision* must be that a network be *covered* if the Minister determines an affirmative answer to each of the following questions:
- (a) Would *access* (or increased *access*) to *covered services* provided by means of the network promote a material increase in competition in at least one market (whether or not in Western Australia) other than the market for the *covered services* provided by means of the network?

¹⁷⁴ Section 3.1A inserted by WAGG No 108, 26 June 2020; note to section 3.1A amended by WAGG No 118, 2 July 2021

¹⁷⁵ Section 3.1B inserted by WAGG No 118, 2 July 2021

¹⁷⁶ Section 3.1C inserted by WAGG No 118, 2 July 2021

¹⁷⁷ Section 3.2 amended by WAGG No 180, 22 October 2008

¹⁷⁸ Section 3.2A inserted by WAGG No 118, 2 July 2021

¹⁷⁹ Section 3.3 deleted by WAGG No 180, 22 October 2008

- (b) Would it be uneconomic for anyone to develop another network to provide the *covered services* provided by means of the network?
- (c) Would *access* (or increased *access*) to the *covered services* provided by means of the network not be contrary to the public interest?

Factors the Minister must have regard to

- 3.6 The Minister must when exercising the Minister's functions under this Chapter 3 have regard to the geographical location of the network and the extent (if any) to which the network is interconnected with other networks.
- 3.7 Section 3.6 does not limit the factors to which the Minister may have regard.

Subchapter 3.3 – Coverage process

Applications for coverage

- 3.8 A *coverage applicant* may make a *coverage application* to the Minister requesting that the whole or any part of a network be *covered*.
- 3.9 A *coverage applicant* may withdraw its *coverage application* by notice to the Minister at any time before the Minister makes a *final coverage decision*.
- 3.10 A *coverage application* must be made in accordance with any guidelines which may be developed and *published* by the Minister concerning the form and content of *coverage applications* and specifying the amount of any fee to be paid on the making of a *coverage application*.
- 3.11 Within 10 *business days* after receipt of the *coverage application* inform the *service provider* and each other person known to the Minister whom the Minister believes has a sufficient interest in the matter that the Minister has received the *coverage application*.

Minister may dismiss a coverage application¹⁸⁰

- 3.12 If the Minister receives a *coverage application* which the Minister considers to have been made on trivial or vexatious grounds, then, without further consideration, the Minister may dismiss the *coverage application*, in which case sections 3.13 to 3.29 do not apply to the *coverage application*.¹⁸¹

Invitation for submissions and issues paper

- 3.13 The Minister must *publish*:¹⁸²
 - (a) a *coverage application*, stating how copies of the *coverage application* may be obtained; and

¹⁸⁰ New heading inserted by WAGG No 207, 8 November 2005

¹⁸¹ Section 3.12 amended by WAGG No 207, 8 November 2005; Section 3.12 amended by WAGG No 180, 22 October 2008

¹⁸² Section 3.13 amended by WAGG No 157, 18 September 2020

(b) an invitation for submissions on the *coverage application*,
as soon as practicable and in any event within 10 *business days* after the *coverage application* is received by the Minister.

3.14 The Minister may produce and *publish* an issues paper examining the issues raised in connection with a *coverage application* within 20 *business days* after the invitation for submissions on the *coverage application* is *published* under section 3.13(b).¹⁸³

3.15 The Minister must arrange to provide a copy of a *coverage application* to any person who requests a copy within 5 *business days* after the person makes the request and pays any reasonable fee required by the Minister.

First round public submissions

3.16 A person may make a submission to the Minister on a *coverage application* within the later of:

(a) 15 *business days* after an invitation for submissions on the *coverage application* is *published* under section 3.13(b); and¹⁸⁴

(b) 10 *business days* after an issues paper is *published* in respect of the *coverage application* under section 3.14.

Draft coverage decision by the Minister

3.17 Subject to section 3.24, the Minister must consider any submissions made under section 3.16 on a *coverage application* and must make a *draft coverage decision* either:

(a) that the *network* be *covered*; or

(b) that the *network* not be *covered*.

3.18 The Minister must, within 15 *business days* (but not earlier than 10 *business days*) after the due date for submissions under section 3.16, *publish* the *draft coverage decision* and provide a copy of the *draft coverage decision* and *reasons* to the *coverage applicant* and the *service provider*.¹⁸⁵

3.19 The Minister must *publish* an invitation for submissions on a *draft coverage decision* at the same time as the Minister *publishes* the *draft coverage decision*.¹⁸⁶

Second round public submissions

3.20 A person may make a submission to the Minister on a *draft coverage decision* within 15 *business days* after the invitation for submissions on the *draft coverage decision* is *published* under section 3.19.¹⁸⁷

¹⁸³ Section 3.14 amended by WAGG No 157, 18 September 2020

¹⁸⁴ Section 3.16 amended by WAGG No 157, 18 September 2020

¹⁸⁵ Section 3.18 amended by WAGG No 157, 18 September 2020

¹⁸⁶ Section 3.19 amended by WAGG No 157, 18 September 2020

¹⁸⁷ Section 3.20 amended by WAGG No 157, 18 September 2020

Final coverage decision by Minister

- 3.21 Subject to section 3.24, the Minister must consider any submissions made under section 3.20 on a *draft coverage decision* and must make a *final coverage decision* either:
- (a) that the *network* be *covered*; or
 - (b) that the *network* not be *covered*.
- 3.22 The Minister must, within 15 *business days* (but not earlier than 10 *business days*) after the due date for submissions under section 3.20, *publish* the *final coverage decision* and provide a copy of the *final coverage decision* and *reasons* to the *coverage applicant* and the *service provider*.¹⁸⁸

Final coverage decision has effect

- 3.23 The Minister must specify a date in the *final coverage decision* on which the *final coverage decision* will have effect, which date must not be earlier than 10 *business days* after the day the *final coverage decision* is made.

Late submissions

- 3.24 The Minister may consider any submission received pursuant to an invitation for submissions after the time for making the submission has expired.

Reasons

- 3.25 At the time of *publishing* a *coverage decision* the Minister must also *publish* the *reasons* for the *coverage decision*.¹⁸⁹

Service provider agrees to network coverage

- 3.26 At any time prior to the Minister making a *final coverage decision* for a network, the *service provider* may notify the Minister that it agrees to coverage of the network to the same extent as specified in the *coverage application*, in which case the Minister may then make a *final coverage decision* that the *network* be *covered* to the same extent as specified in the *coverage application* and if the Minister does so:
- (a) the Minister is not required to consider the matters set out in sections 3.5 to 3.6; and
 - (b) the Minister is not required to comply with the process in sections 3.13 to 3.22.

Extensions of time under this Chapter

- 3.27 Subject to section 3.28, the Minister may extend any deadline, or provide for stages in the making of a *coverage decision* in addition to those provided for, in this Chapter 3, but only if, and only to the extent that, the Minister first determines that:

¹⁸⁸ Section 3.22 amended by WAGG No 157, 18 September 2020

¹⁸⁹ Section 3.25 amended by WAGG No 157, 18 September 2020

- (a) a longer period of time is essential for due consideration of all the matters under consideration or satisfactory performance of the relevant obligation, or both; and
- (b) the Minister has taken all reasonable steps to fully utilise the times and processes provided for in this Chapter 3.

3.28 The Minister:

- (a) must not exercise the power in section 3.27 to extend any deadline unless, before the day on which the time would otherwise have expired, the Minister *publishes* the Minister's decision to extend the deadline; and¹⁹⁰
- (b) may (subject to section 3.29) exercise the power in section 3.27 to extend a deadline on more than one occasion but the total time for the extension of a deadline cannot exceed the period originally specified in this Chapter 3 for the relevant deadline.

3.29 The Minister must not extend the deadline specified in section 3.15.

Subchapter 3.4 – Revocation of coverage

Revocation of coverage

3.30 A *covered network* ceases to be *covered* if a *revocation applicant* makes a *revocation application* to the Minister for coverage of the *covered network* to be revoked and the Minister makes a final *revocation decision* that the network not be *covered*.

3.31 The process for the Minister to decide on revocation of coverage is the same as the process for a decision on coverage outlined in sections 3.4¹⁹¹ to 3.29, with appropriate modifications including replacing a reference to:

- (a) “*coverage application*” with a reference to “*revocation application*”; and
- (b) “*coverage decision*” with a reference to “*revocation decision*”; and
- (c) “*draft coverage decision*” with a reference to *draft revocation decision*; and
- (d) “*final coverage decision*” with a reference to “*final revocation decision*”; and
- (e) “*coverage*” with a reference to “*revocation of coverage*”; and
- (f) “*coverage applicant*” with a reference to “*revocation applicant*”.

¹⁹⁰ Section 3.28 amended by WAGG No 157, 18 September 2020

¹⁹¹ Section 3.31 amended by WAGG No 180, 22 October 2008

Subchapter 3.5 – Miscellaneous

Advertising

3.32 Where the Minister is required to *publish* a thing under this Chapter 3, the thing *published* must contain a description of the network the subject of the *publication*.¹⁹²

Publishing

3.33 The Minister must *publish* all submissions made in connection with a *coverage application* or *revocation application*.¹⁹³

Automatic coverage¹⁹⁴

3.34 An *augmentation* of a *covered network* is part of the *covered network* from the time the *augmentation* is commissioned.

3.34A A *stand-alone power system* provided by a *service provider* is treated as part of the *covered network* to which it is an adjunct if it:

- (a) replaces part of the *covered network*; or
- (b) is required to be provided by the *service provider* pursuant to a *written law* or *statutory instrument*.¹⁹⁵

3.35 Sections 3.34 and 3.34A do not limit section 3.30.¹⁹⁶

Notification of network modification

3.36 A *service provider* must:

- (a) as soon as practicable after a network modification which meets the notification threshold has occurred, notify the *Authority* of the details of the network modification; and
- (b) within 30 *business days* after receiving a request from the *Authority*, and within 30 *business days* after the end of a year, provide the *Authority* with an updated description of the *covered network*, identifying all significant network modifications (whether or not they meet the notification threshold) that have occurred since the last description,

and the *Authority* must promptly after notification amend the description of the *covered network* on the *public register* to reflect the network modification or network modifications.

{Note: The *Authority* is required to establish and *maintain* a *public register* under section 14.15.}

¹⁹² Section 3.32 amended by WAGG No 157, 18 September 2020

¹⁹³ Note to section 3.33 deleted by WAGG No 180, 22 October 2008

¹⁹⁴ Heading to section 3.34 amended by WAGG No 157, 18 September 2020

¹⁹⁵ Section 3.34A inserted by WAGG No WAGG No 157, 18 September 2020

¹⁹⁶ Section 3.35 amended by WAGG No 157, 18 September 2020

- 3.37 For the purposes of section 3.36, the notification threshold for a network modification is:
- (a) for an *augmentation* — an *augmentation* requiring *new facilities investment* of more than \$15 million (*CPI adjusted*); or
 - (b) for a disposal or decommissioning — a disposal or decommissioning involving *network assets* that are valued by the *service provider* as a *reasonable and prudent person* at more than \$15 million (*CPI adjusted*).

Subchapter 3.6 – Transitional matters relating to form of regulation decision¹⁹⁷

Contracts preserved

- 3.38 If the Minister makes a *form of regulation decision* under the *PNAC* that a *Pilbara network* which was previously *fully regulated* is to be *lightly regulated*, then any existing *contracts for services* in respect of the *Pilbara network* will continue in accordance with their terms, including for the duration of any option periods provided for in any such contracts (subject to any variations the parties may agree from time to time).
- 3.39 If a contract which is continued under section 3.38 depends upon a regulated outcome under this Code (for example, because it adopts a regulated tariff from time to time) then the arbitrator under the *PNAC* has jurisdiction to hear an access dispute in respect of the relevant contract and the provisions of Chapter 7 of the *PNAC* will apply to such dispute.
- 3.40 Section 3.39 applies in addition to any other dispute resolution mechanism included in a contract, and the arbitrator under the *PNAC* has jurisdiction to determine the effect of section 3.39.
- 3.41 If the Minister makes a *form of regulation decision* under the *PNAC* that a *Pilbara network* which was previously *lightly regulated* is to be *fully regulated*, then any existing “contracts for services” (as defined in the *PNAC*) in respect of the *Pilbara network* will continue in accordance with their terms, including for the duration of any option periods provided for in any such contracts (subject to any variations the parties may agree from time to time).

How applications and disputes in progress are managed

- 3.42 Following a form of regulation decision under the *PNAC* that a *Pilbara network* be lightly regulated—
- (a) any *access application* made before the date of the *form of regulation decision* is to be transitioned to being *lightly regulated* under the *PNAC*; and
 - (b) the *access application’s priority* will remain the same under the *PNAC* as its *priority* under this Code;

¹⁹⁷ Subchapter 3.6 inserted by WAGG No 118, 2 July 2021

- (c) the *applicant* and the *service provider* must meet expeditiously and negotiate in good faith with a view to agreeing any amendments or additional information needed in respect of the *access application* as a result of the transition, and failing agreement the question may be the subject of an access dispute under the *PNAC* but not an *access dispute* under this Code; and
- (d) any *access dispute* notified in the *Authority* before the date of the *form of regulation decision* is to be transitioned to be determined by arbitration under the *PNAC*, in which case the *arbitrator* may make such orders as the *arbitrator* deems necessary in respect of the transition.

{Note: This gives the *arbitrator* the power to make orders to deal with the transition of an *access dispute* to be determined by arbitration under the *PNAC*. Similar powers also exist under the *PNAC*. The combined effect is that the arbitrators under both this Code and the *PNAC* can make the necessary orders to transition an *access dispute*.}

- 3.43 If the Minister makes a *form of regulation decision* under the *PNAC* that a *Pilbara network* which was previously *lightly regulated* is to be *fully regulated*, the *service provider* must submit to the *Authority*, as applicable, either—
- (a) if the *Pilbara network* has not previously had an *access arrangement*—a proposed *access arrangement* and *access arrangement information* under section 4.1; or
 - (b) if the *Pilbara network* has previously had an *access arrangement*—proposed revisions to the *access arrangement* and proposed revised *access arrangement information* under section 4.48.
- 3.44 The *form of regulation decision* that a *Pilbara network* is *fully regulated* does not take effect until, as applicable, the *access arrangement start date* or *revisions commencement date* in respect of the submission referred to in section 3.43.
- 3.45 Following a *form of regulation decision* that a *Pilbara network* which was previously *lightly regulated* is to be *fully regulated*—
- (a) any access application made under the *PNAC* before the date of the *form of regulation decision*, is to be transitioned to be determined under this Code; and
 - (b) the access application has effect for the purposes of this Code as though it was an *access application* lodged under the *service provider's access arrangement*; and
 - (c) the *access application's priority* will remain the same under this Code as its *priority* under the *PNAC*; and
 - (d) the *applicant* and the *service provider* must meet expeditiously and negotiate in good faith with a view to agreeing any amendments or additional information needed in respect of the *access application* as a result of the transition, and failing agreement the question may be the subject of an *access dispute* under this Code but not an access dispute under the *PNAC*; and

- (e) any access dispute under the *PNAC* notified to the *Authority* before the date of the *form of regulation decision*, is to be transitioned to be determined as an *access dispute* under this Code, in which case the *arbitrator* may make such orders as the *arbitrator* deems necessary in respect of the transition.

{Note: This gives the *arbitrator* the power to make orders to deal with the transition of an access dispute under the *PNAC* to be determined as an *access dispute* under this Code. Similar powers also exist under the *PNAC*. The combined effect is that the arbitrators under both this Code and the *PNAC* can make the necessary orders to transition an *access dispute* under the *PNAC*.}

Chapter 4 – Access Arrangements: Approvals and Review

Subchapter 4.A – Framework and approach¹⁹⁸

- 4.A1 The *Authority* must make and *publish* a document (“**framework and approach**”) that is consistent with the *Code objective*, and applies to the *service provider* in respect of a *proposed access arrangement* for a matter listed in section 4.A2 in accordance with this section.¹⁹⁹
- 4.A2 The *framework and approach* must set out the *Authority’s* decision (including its *reasons* for the decision) for the purposes of the next *access arrangement review*, on the following matters:
- (a) the *investment adjustment mechanism* that will apply to the *service provider*; and
 - (b) the *gain sharing mechanism* that will apply to the *service provider*; and
 - (c) the *service standards adjustment mechanism* that will apply to the *service provider*; and
 - (d) the *demand management innovation allowance mechanism* that will apply to the *service provider*; and
 - (e) the form of *price control*, having regard to the objectives in section 6.4; and
 - (f) a list of and classification of *services* including whether *services* are *reference services* or *non-reference services*, the eligibility criteria for each *reference service*, the structure and *charging parameters* for each *distribution reference tariff* and a description of the approach to setting each *distribution reference tariff* in accordance with sections 7.2 to 7.12; and
 - (g) the method for setting the *service standard benchmarks* for each *reference service*.²⁰⁰
- 4.A3 If there is no *access arrangement* that applies in respect of a *service provider*, the *Authority* must *publish* the *framework and approach* that will apply to the first *access arrangement* by no later than 3 months prior to the *submission deadline*.²⁰¹
- 4.A4 By no later than 31 months prior to the *target revisions commencement date*, the *Authority* must *publish*:

¹⁹⁸ Heading inserted by WAGG No 157, 18 September 2020

¹⁹⁹ Section 4.A1 inserted by WAGG No 157, 18 September 2020

²⁰⁰ Section 4.A2 inserted by WAGG No 157, 18 September 2020

²⁰¹ Section 4.A3 inserted by WAGG No 157, 18 September 2020

- (a) an issues paper on:
 - (i) if there is a *framework and approach* that applies in respect of the *service provider*, whether it is necessary or desirable to amend or replace the *framework and approach*; or
 - (ii) if there is no *framework and approach* that applies in respect of the *service provider*, the *framework and approach* that will apply to the next *access arrangement*;
- (b) an invitation for submissions on the issues paper referred to in section 4.A3(a); and
- (c) an indicative timetable setting out the *Authority's* proposed timeline with respect to the milestones for the *framework and approach* and *access arrangement* revision process to apply to the next *access arrangement review*.²⁰²

4A.5 A person may make a submission to the *Authority* on the issues paper within 20 *business days* (or such longer period as specified by the *Authority*) after the invitation for submissions on the *framework and approach* is *published* under section 4.A3.

{Note: Under section 14.5(d)(iii), the *Authority* must place each submission made under section 4.A5 on the *public register*.}

{Note: A person may state that a submission or part of a submission is confidential in which case sections 14.12 to 14.15 apply.}²⁰³

4.A6 The *Authority* must consider any submissions made under section 4.A5 (and information provided pursuant to section 4.A14, if applicable) and must make and *publish*:

- (a) the *Authority's* decision (including its *reasons* for the decision) for making, amending or replacing the *framework and approach*;
- (b) the draft *framework and approach* (as amended or replaced, if applicable); and
- (c) an invitation for submissions on the draft *framework and approach*.²⁰⁴

4.A7 A person may make a submission to the *Authority* on a draft *framework and approach* within 20 *business days* (or such longer period as specified by the *Authority*) after the invitation for submissions on the draft *framework and approach* is *published* under section 4.A3.

{Note: Under section 14.5(d)(iii), the *Authority* must place each submission made under section 4.A7 on the *public register*.}

²⁰² Section 4.A4 inserted by WAGG No 157, 18 September 2020

²⁰³ Section 4.A5 inserted by WAGG No 157, 18 September 2020

²⁰⁴ Section 4.A6 inserted by WAGG No 157, 18 September 2020

{Note: A person may state that a submission or part of a submission is confidential in which case sections 14.12 to 14.15 apply.}²⁰⁵

4.A8 The *service provider* may, within 15 *business days* after the due date for submissions under section 4.A7, make a submission on the draft *framework and approach*.

{Note: Under section 14.5(d)(iii), the *Authority* must place each submission made under section 4.A8 on the *public register*.}

{Note: A person may state that a submission or part of a submission is confidential in which case sections 14.12 to 14.15 apply.}²⁰⁶

4.A9 By no later than 23 months prior to the *target revisions commencement date*, the *Authority* must:

- (a) consider any submissions made under sections 4.A7 and 4.A8 (and information provided pursuant to section 4.A14, if applicable) on the draft *framework and approach*; and
- (b) make and *publish* a final *framework and approach* (including its *reasons* for the final *framework and approach*).²⁰⁷

4.A10 The *framework and approach* is not binding on the *Authority* and the *service provider*.²⁰⁸

4.A11 Any *proposed access arrangement* or *proposed revisions* submitted by a *service provider* to the *Authority* must be consistent with the *framework and approach* that applies to it. The *service provider* may propose departures from the *framework and approach* if there has been a material change in circumstances in which case it must provide reasons for the departure.²⁰⁹

4.A12 The *Authority* must not *approve* a *proposed access arrangement* or *proposed revisions* that departs from the *framework and approach* unless there has been a material change in circumstances, in which case it must provide *reasons* for the departure.²¹⁰

4.A13 The *Authority* may make and *publish* a *framework and approach* that applies in respect of an *access arrangement* for a matter that is not listed in section 4.A2 and, if it does so, sections 4.A1 to 4.A12 apply as if that matter were listed in section 4.A2.²¹¹

4.A14 A submission made under section 4.A5, 4.A7 or 4.A8 that proposes the introduction of a new *reference service* must include information which justifies and supports the basis on which the party making the submission considers the relevant *reference service* is likely to be sought by either or both of:

²⁰⁵ Section 4.A7 inserted by WAGG No 157, 18 September 2020

²⁰⁶ Section 4.A8 inserted by WAGG No 157, 18 September 2020

²⁰⁷ Section 4.A9 inserted by WAGG No 157, 18 September 2020

²⁰⁸ Section 4.A10 inserted by WAGG No 157, 18 September 2020

²⁰⁹ Section 4.A11 inserted by WAGG No 157, 18 September 2020

²¹⁰ Section 4.A12 inserted by WAGG No 157, 18 September 2020

²¹¹ Section 4.A13 inserted by WAGG No 157, 18 September 2020

- (a) a significant number of *customers* and *applicants*; or
- (b) a substantial proportion of the market for *services* in the *covered network*.²¹²

Subchapter 4.1— Approval process

{Note: Appendix 1 contains a flowchart which provides an outline of the *access arrangement approval* process.}

Submission of first access arrangement

4.1 The *service provider* of a *covered network* must submit a *proposed access arrangement* and *access arrangement information* to the *Authority* by the *submission deadline*.

{Note: Sections 4.16 to 4.21 apply where there are two *service providers* for a *covered network*, for example because one person owns it and another operates it.}

{Note: If a *service provider* does not submit a *proposed access arrangement* for the *first access arrangement period* by the *submission deadline* sections 4.55 to 4.58 will apply.}

{Note: Section 4.48 requires a *service provider* who has an existing *access arrangement* to submit *proposed revisions* by no later than 17 months prior to the *target revisions commencement date* in the *access arrangement*.²¹³}

{Note: A *service provider* that submits an *access arrangement* and *access arrangement information* under section 4.1 must also submit proposed *technical rules* under Chapter 12 to be processed in parallel with the *access arrangement*.}

Access arrangement information

4.2 *Access arrangement information* must enable the *Authority*, *users* and *applicants* to:

- (a) understand how the *service provider* derived the elements of the *proposed access arrangement*; and
- (b) form an opinion as to whether the *proposed access arrangement* complies with the *Code*.

4.3 *Access arrangement information* must include:

- (a) information detailing and supporting the *price control* in the *access arrangement*; and
- (b) information detailing and supporting the *pricing methods* in the *access arrangement*, including:

²¹² Section 4.A14 inserted by WAGG No 157, 18 September 2020

²¹³ Note to section 4.1 inserted by WAGG No 157, 18 September 2020

- (i) a description (with supporting materials) of how the proposed *tariff structure statement* complies with the *pricing principles* including:
 - A. a description of where there has been any departure from the pricing principles set out in sections 7.3D to 7.3H; and
 - B. an explanation of how that departure complies with section 7.3B; and
 - (ii) a description of how the *service provider* has engaged with *users* and *end-use customers* in developing the proposed *tariff structure statement* and has sought to address any relevant concerns identified as a result of that engagement; and
 - (c) if applicable, information detailing and supporting the measurement of the components of *approved total costs* in the *access arrangement*; and
 - (d) information detailing and supporting the *service provider's* system capacity and volume assumptions; and
 - (e) any other information specified in the guidelines made under section 4.5.²¹⁴
- 4.4 If a *service provider* submits a revised *proposed access arrangement* under section 4.16, the *service provider* must at the same time submit appropriately amended *access arrangement information*.²¹⁵
- 4.5 The *Authority* may from time to time *publish* guidelines setting out in further detail what information must be included in *access arrangement information* in order for the *access arrangement information* to comply with sections 4.2 and 4.3, either generally or in relation to a particular matter or circumstance.
- 4.6 Subject to sections 4.2 and 4.3, *access arrangement information* submitted more than six months after guidelines are *published* under section 4.5²¹⁶ must comply with the guidelines.
- 4.7 [Not used]²¹⁷
- 4.8 The *Authority* may, to the extent necessary to make *access arrangement information* comply with sections 4.2 and 4.3, require the *service provider* to amend and resubmit *access arrangement information* to the *Authority* within a reasonable time specified by the *Authority*, which time must not exceed 5 *business days*.

Invitation for submissions and issues paper

- 4.9 As soon as practicable after the *proposed access arrangement* is submitted to the *Authority*, the *Authority* must *publish*:

²¹⁴ Section 4.3 amended by WAGG No 157, 18 September 2020

²¹⁵ Section 4.4 amended by WAGG No 157, 18 September 2020

²¹⁶ Section 4.6 amended by WAGG No 207, 8 November 2005; Section 4.6 amended by WAGG No 157, 18 September 2020

²¹⁷ Section 4.7 deleted by WAGG No 157, 18 September 2020

- (a) a *proposed access arrangement* and the *access arrangement information* submitted to it; and
- (b) an invitation for submissions on the *proposed access arrangement*; and
- (c) an invitation to attend a public forum on the issues paper referred to in section 4.10.²¹⁸

4.10 The *Authority* must:

- (a) produce and *publish* an issues paper examining the issues raised in connection with the *proposed access arrangement* after the invitation for submissions on the *proposed access arrangement* is *published* under section 4.9(b); and
- (b) hold a public forum on the issues paper.²¹⁹

First round public submissions

4.11 A person may make a submission to the *Authority* on the *proposed access arrangement* within 30 *business days* (or such longer period as specified by the *Authority*) after the publication of the issues paper under section 4.10(a).²²⁰

{Note: Under section 14.5(d)(iii), the *Authority* must place each submission made under section 4.11 on the *public register*.}

{Note: A person may state that a submission or part of a submission is confidential in which case sections 14.12 to 14.15 apply.}

4.11A The *service provider* may submit further *access arrangement information* on the *proposed access arrangement* to the *Authority* within 20 *business days* after the due date for submissions under section 4.11.²²¹

Draft decision by Authority

4.12 The *Authority* must consider any submissions made under section 4.11 and any further *access arrangement information* submitted under section 4.11A on a *proposed access arrangement* and must make a *draft decision* either:²²²

- (a) to *approve* the *proposed access arrangement*; or
- (b) to not *approve* the *proposed access arrangement*, in which case the *Authority* must in its *reasons* provide details of the amendments required to the *proposed access arrangement* before the *Authority* will approve it.

4.13 The *Authority* must, as soon as practicable after the due date for submission of further *access arrangement information* under section 4.11A, *publish*:

²¹⁸ Section 4.9 amended by WAGG No 157, 18 September 2020

²¹⁹ Section 4.10 amended by WAGG No 157, 18 September 2020

²²⁰ Section 4.11 amended by WAGG No 157, 18 September 2020

²²¹ Section 4.11A inserted by WAGG No 157, 18 September 2020

²²² Section 4.12 amended by WAGG No 157, 18 September 2020

- (a) the *draft decision*;
- (b) *reasons* for the *draft decision*;
- (c) an invitation for submissions on a *draft decision*; and
- (d) notice of a predetermination conference, which must include the time, date and place of the predetermination conference.²²³

4.14 The *Authority* must hold the predetermination conference at the time, date and place specified in the notice under section 4.13 and in any event, within 15 *business days* of the notice for the purpose of explaining the *draft decision*.²²⁴

Second round public submissions

4.15 A person may make a submission to the *Authority* on a *draft decision* within 45 *business days* (or such longer period as specified by the *Authority*) after the invitation for submissions on the *draft decision* is *published* under section 4.13.²²⁵

{Note: Under section 14.5(d)(iii), the *Authority* must place each submission made under section 4.15 on the *public register*.}

{Note: A person may state that a submission or part of a submission is confidential in which case sections 14.12 to 14.15 apply.}

Revised proposed access arrangement

4.16 The *service provider* must, within 45 *business days* after the *draft decision* is *published* under section 4.13, submit a revised *proposed access arrangement*, and if so, a reference in this Code to a “*proposed access arrangement*” is to be read as though it was a reference to a “*revised proposed access arrangement*”.²²⁶

4.16A The *service provider* may submit further *access arrangement information* on the revised *proposed access arrangement* to the *Authority* within 20 *business days* after the due date for submissions under section 4.15.²²⁷

Final decision by Authority

4.17 The *Authority* must consider any submissions made under sections 4.15 to 4.16A on the *draft decision* and must:

- (a) make a *final decision* either:
 - (i) to approve the proposed access arrangement; or
 - (ii) to not approve the *proposed access arrangement*; and
- (b) *publish* the *final decision*; and

²²³ Section 4.13 amended by WAGG No 157, 18 September 2020

²²⁴ Section 4.14 amended by WAGG No 157, 18 September 2020

²²⁵ Section 4.15 amended by WAGG No 157, 18 September 2020

²²⁶ Section 4.16 amended by WAGG No 157, 18 September 2020

²²⁷ Section 4.16A inserted by WAGG No 157, 18 September 2020

(c) provide and *publish reasons* for the *final decision*.²²⁸

4.18 If the *Authority's final decision* is not to approve a *service provider's proposed access arrangement*, then the *Authority* must draft, approve and *publish* its own *access arrangement*, which must be:

(a) based on the *proposed access arrangement*; and

(b) amended from the basis in section 4.18(a) only to the extent necessary to satisfy the criteria for *approval* in section 4.28.²²⁹

4.18A The *Authority* must comply with sections 4.17 and 4.18 as soon as practicable after the due date for submission of further *access arrangement information* under section 4.16A and in any event by no later than 3 months prior to the *target revisions commencement date*.²³⁰

[Heading not used]²³¹

4.19 [Not used]²³²

4.20 [Not used]²³³

[Heading not used]²³⁴

4.21 [Not used]²³⁵

4.22 [Not used]²³⁶

4.23 [Not used]²³⁷

[Heading not used]²³⁸

4.24 [Not used]²³⁹

4.25 [Not used]²⁴⁰

Access arrangement start date

4.26 When the *Authority*:

²²⁸ Section 4.17 amended by WAGG No 157, 18 September 2020

²²⁹ Section 4.18 amended by WAGG No 157, 18 September 2020

²³⁰ Section 4.18A inserted by WAGG No 157, 18 September 2020

²³¹ Heading to section 4.19 deleted by WAGG No 157, 18 September 2020

²³² Section 4.19 deleted by WAGG No 157, 18 September 2020

²³³ Section 4.20 deleted by WAGG No 157, 18 September 2020

²³⁴ Heading to section 4.21 deleted by WAGG No 157, 18 September 2020

²³⁵ Section 4.21 deleted by WAGG No 157, 18 September 2020

²³⁶ Section 4.22 deleted by WAGG No 157, 18 September 2020

²³⁷ Section 4.23 deleted by WAGG No 157, 18 September 2020

²³⁸ Heading to section 4.24 deleted by WAGG No 157, 18 September 2020

²³⁹ Section 4.24 deleted by WAGG No 157, 18 September 2020

²⁴⁰ Section 4.25 deleted by WAGG No 157, 18 September 2020

- (a) makes a *final decision to approve a proposed access arrangement*; or
 - (b) *approves* its own *access arrangement* under section 4.18,
- the *Authority* must specify an *access arrangement start date* which must:
- (c) be consistent with the *Code objective*; and
 - (d) be at least 2 months after the later of the *final decision* or the *Authority's* own *access arrangement* under section 4.18 being *published*.²⁴¹

Subchapter 4.2 – Criteria for approval

[Heading not used]²⁴²

4.27 [Not used]²⁴³

Criteria for approval of a proposed access arrangement

4.28 Subject to section 4.32, when making a *draft decision* or *final decision*, the *Authority* must determine whether a *proposed access arrangement* meets the *Code objective* and the requirements set out in Chapter 5 (and Chapter 9, if applicable) and:²⁴⁴

- (a) if the *Authority* considers that:
 - (i) the *Code objective* and the requirements set out in Chapter 5 (and Chapter 9, if applicable) are satisfied — it must approve the *proposed access arrangement*; and
 - (ii) the *Code objective* or a requirement set out in Chapter 5 (or Chapter 9, if applicable) is not satisfied — it must not approve the *proposed access arrangement*;

and

- (b) to avoid doubt, if the *Authority* considers that the *Code objective* and the requirements set out in Chapter 5 (and Chapter 9, if applicable) are satisfied, it must not refuse to approve the *proposed access arrangement* on the ground that another form of *access arrangement* might better or more effectively satisfy the *Code objective* and the requirements set out in Chapter 5 (and Chapter 9, if applicable).

{Note: The effect of section 4.28 is to make the *Authority's* decision in relation to a *proposed access arrangement* a “pass or fail” assessment. The intention is that, if a *proposed access arrangement* meets the *Code objective* and the requirements set out in Chapter 5 (and Chapter 9, if applicable), the *Authority* should not refuse to approve it simply because the *Authority* considers that some other form of *access arrangement* might be even better, or more effective,

²⁴¹ Section 4.26 amended by WAGG No 157, 18 September 2020

²⁴² Heading to section 4.27 deleted by WAGG No 157, 18 September 2020

²⁴³ Section 4.27 deleted by WAGG No 157, 18 September 2020

²⁴⁴ Section 4.28 amended by WAGG No 157, 18 September 2020

at meeting the *Code objective* and the requirements set out in Chapter 5 (and Chapter 9, if applicable).}

4.29 The *Authority*:

- (a) must not approve a *proposed access arrangement* which omits something listed in section 5.1; and
- (b) may in its discretion approve a *proposed access arrangement* containing something not listed in section 5.1; and
- (c) must not refuse to approve a *proposed access arrangement* on the ground that it omits something not listed in section 5.1.

Factors the Authority must have regard to

4.30 In determining whether to approve a *proposed access arrangement*, the *Authority* must have regard to following:

- (a) the geographical location of the network and the extent (if any) to which the network is interconnected with other networks; and
- (b) contractual obligations of the *service provider* or other persons (or both) already using the network; and
- (c) the operational and technical requirements necessary for the safe and reliable operation of the network; and
- (d) to the extent relevant — *written laws* and *statutory instruments*.

4.31 Section 4.30 does not limit the factors the *Authority* may have regard to.

4.32 The *Authority* must not approve a *proposed access arrangement* which would, if approved, require the *service provider* or another person to engage in an act or omit to engage in an act which would contravene a *written law* or a *statutory instrument*.

[Heading not used]²⁴⁵

4.33 [Not used]²⁴⁶

Access arrangement must not override prior contractual rights

4.34 Subject to section 4.35, the *Authority* must not approve a *proposed access arrangement* which would, if approved, have the effect of depriving a person of a contractual right that existed prior to the earlier of the *submission deadline* for the *proposed access arrangement* and the date on which the *proposed access arrangement* was submitted.

4.35 Section 4.34 does not apply to protect:

- (a) an exclusivity right which arose on or after 30 March 1995; or

²⁴⁵ Heading to section 4.33 deleted by WAGG No 157, 18 September 2020

²⁴⁶ Section 4.33 deleted by WAGG No 157, 18 September 2020

- (b) contractual rights that arose before the date of the 2020 (No. 2) amendments and that are inconsistent with provisions of a *proposed access arrangement* that have been implemented to reflect the introduction or operation of security constrained economic dispatch in the *Wholesale Electricity Market*.²⁴⁷

Conditional approval – price lists

- 4.36 The *Authority* must, as a condition of *approval* of a *proposed access arrangement*, require a *service provider* to submit each *price list* under the *access arrangement* to the *Authority* under section 8.1 for *approval*, if:
- (a) the *service provider* requests such a condition; or
 - (b) the *Authority* considers that the submission of *price lists* under the *access arrangement* to the *Authority* under section 8.1 for *approval* would improve the operation of the *access arrangement*.

Subchapter 4.3 – Revision and review

Trigger events

- 4.37 If an *access arrangement*:
- (a) specifies one or more *trigger events*; and
 - (b) the conditions of a *trigger event* are satisfied, then:
 - (c) as soon as practicable, the *service provider* must notify the *Authority* that the conditions of the *trigger event* are satisfied; and
 - (d) the *service provider* must submit *proposed revisions* to the *Authority* by the *designated date*; and
 - (e) the *Authority* must consider the *proposed revisions* in accordance with sections 4.46 to 4.52.

Revision of price control or pricing methods during an access arrangement period²⁴⁸

- 4.38 The *Authority* may by notice to a *service provider* vary the *price control* or *pricing methods* in an *access arrangement* before the next *revisions commencement date*, but only if the *Authority* determines that:
- (a) its *approval* of the *access arrangement* was based on materially false, misleading or deceptive information provided to it by the *service provider*, and the *Authority* considers that the impact of the materially false, misleading or deceptive information is of a sufficient magnitude to warrant making the variation before the end of the *access arrangement period*; or

²⁴⁷ Section 4.35 amended by WAGG No 157, 18 September 2020

²⁴⁸ Heading to section 4.38 amended by WAGG No 180, 22 October 2008

- (b) either:
 - (i) its *approval* of the *access arrangement* contains a material error or was based on materially false, misleading or deceptive information provided to it by a person other than the *service provider*; or
 - (ii) significant unforeseen developments have occurred that are:
 - A. outside the control of the *service provider*; and
 - B. not something that the *service provider*, acting in accordance with *good electricity industry practice*, should have been able to prevent or overcome,

and the impact of the error, materially false, misleading or deceptive information or unforeseen developments is so substantial that the *Authority* considers that the advantages of making the variation before the end of the *access arrangement period* outweigh the disadvantages, having regard to the impact of the variation on regulatory certainty.

4.39 Before giving a notice under section 4.38, the *Authority* must consult the public in accordance with Appendix 7.

4.40 The *Authority* must *publish* a notice given under section 4.38.

Revision of access arrangement if Code is amended²⁴⁹

4.41 Subject to section 4.42, if there is a *Code change*, the *Authority* may by notice to a *service provider* vary its *access arrangement* in one or more of the following ways:

- (a) if the *access arrangement* incorporates some or all of the terms of the *model applications and queuing policy* — to incorporate any relevant amendments to Appendix 2 made by the *Code change*; and
- (b) if the *access arrangement* incorporates some or all of the terms of the *model standard access contract* — to incorporate any relevant amendments to Appendix 3 made by the *Code change*; and
- (c) if the *access arrangement* incorporates some or all of the terms of the *model contributions policy* — to incorporate any relevant amendments to Appendix 4 made by the *Code change*; and
- (d) otherwise — as a consequence of any other relevant amendments to this Code made by the *Code change*.²⁵⁰

Other revisions during an access arrangement period²⁵¹

4.41A Subject to section 4.42, if the *service provider* proposes revisions other than when it is required to do so under this Code and in circumstances where sections 4.38 and

²⁴⁹ Heading to section 4.41 amended by WAGG No 180, 22 October 2008

²⁵⁰ Section 4.41 amended by WAGG No 180, 22 October 2008

²⁵¹ Heading to section 4.41A inserted by WAGG No 180, 22 October 2008

4.41 do not apply, the *Authority* may by notice to a *service provider* vary its *access arrangement* in accordance with the *proposed revisions*.²⁵²

Mid-period revisions do not necessarily involve full review²⁵³

4.41B In considering and implementing revisions under sections 4.38, 4.41 or 4.41A, the *Authority* is not obliged to undertake a complete *review* of the proposed revised *access arrangement* such as would occur under section 4.52.²⁵⁴

Procedure for amendments under sections 4.41 and 4.41A²⁵⁵

4.42 Before giving a notice under section 4.41 or 4.41A, the *Authority* must determine whether the advantages of varying the *access arrangement* under section 4.41 or 4.41A (as applicable) outweigh the disadvantages, in particular the disadvantages associated with decreased regulatory certainty and increased regulatory cost and delay.²⁵⁶

4.43 Before giving a notice under section 4.41 or 4.41A, the *Authority*:

(a) must consult the public under Appendix 7, unless, in the *Authority's* opinion, the proposed variations are not material and will not result in a material change to a *reference tariff*, a *reference service*, a *standard access contract* or the rights of any *applicant*, in which case the *Authority* may consult the public under Appendix 7; and

(b) must consult the *service provider*.²⁵⁷

4.44 The *Authority* must *publish* a notice given under section 4.41 or 4.41A.²⁵⁸

4.45 Nothing in section 4.41 or 4.41A limits the matters which may be specified as *trigger events* in an *access arrangement*.²⁵⁹

Review of access arrangement

4.46 An *access arrangement* continues in effect from the *access arrangement start date* until the network ceases to be a *covered network*.

{Note: The revision of an *access arrangement* does not create a new *access arrangement* but operates as an amendment to the *access arrangement*. Accordingly, in a subsequent *access arrangement period* the original *access arrangement* continues to have effect, but in a revised form.}

4.47 An *access arrangement* may only be amended in accordance with this Chapter 4.

²⁵² Section 4.41A inserted by WAGG No 180, 22 October 2008

²⁵³ Heading to section 4.41B inserted by WAGG No 180, 22 October 2008

²⁵⁴ Section 4.41B inserted by WAGG No 180, 22 October 2008

²⁵⁵ Heading to section 4.42 inserted by WAGG No 180, 22 October 2008

²⁵⁶ Section 4.42 amended by WAGG No 180, 22 October 2008

²⁵⁷ Section 4.43 amended by WAGG No 180, 22 October 2008

²⁵⁸ Section 4.44 amended by WAGG No 180, 22 October 2008

²⁵⁹ Section 4.45 amended by WAGG No 180, 22 October 2008

- 4.48 The *service provider* of a *covered network* must submit *proposed revisions* and revised *access arrangement information* to the *Authority* by no later than 17 months prior to the *target revisions commencement date*.²⁶⁰
- 4.49 If a *service provider* has failed to submit *proposed revisions* to the *Authority* by the *revisions submissions date* then the *Authority* may *publish* a notice stating that if, by a specified time, the *service provider* has not submitted *proposed revisions* to the *Authority*, the *Authority* will draft, approve and *publish* its own *proposed revisions* for the *covered network*.²⁶¹
- 4.50 If a *service provider* has not submitted *proposed revisions* to the *Authority* by the time specified in a notice under section 4.49, the *Authority* may draft, approve and *publish* its own *proposed revisions* for the *covered network*.²⁶²
- 4.51 The *Authority* must consult the public under Appendix 7 before approving its own *proposed revisions* under section 4.50.
- 4.52 Sections 4.2 to 4.36 apply to the *Authority's* consideration of *proposed revisions* submitted by a *service provider* under sections 4.37 and 4.48 with appropriate modifications including replacing a reference to:²⁶³
- (a) "*proposed access arrangement*" with a reference to "*proposed revisions*"; and
 - (b) [not used]²⁶⁴
 - (b) "*access arrangement start date*" with a reference to "*revisions commencement date*".

Subchapter 4.4– Miscellaneous

Late submissions

- 4.53 The *Authority* may consider any submission made pursuant to an invitation for submissions after the time for making the submission has expired.

No confidentiality for certain documents

- 4.54 Where this Code requires the *Authority* to *publish*:
- (a) a *proposed access arrangement*, a revised *proposed access arrangement*, an *approved access arrangement* or an *access arrangement*; or
 - (b) *proposed revisions*; or
 - (c) *access arrangement information*,

²⁶⁰ Section 4.48 amended by WAGG No 157, 18 September 2020

²⁶¹ Section 4.49 amended by WAGG No 157, 18 September 2020

²⁶² Section 4.50 amended by WAGG No 157, 18 September 2020

²⁶³ Section 4.52 amended by WAGG No 180, 22 October 2008

²⁶⁴ Section 4.52 amended by WAGG No 157, 18 September 2020

(each of which is a “**relevant document**”) then the *Authority* must *publish a relevant document* despite any claim of confidentiality made to the *Authority* in respect of the *relevant document*.²⁶⁵

Authority drafting and approving own access arrangement if no access arrangement submitted

- 4.55 If, for the *first access arrangement period*, a *service provider* has failed to submit a *proposed access arrangement* to the *Authority* by the *submission deadline* then the *Authority* must *publish* a notice stating that if, within 20 *business days* the *service provider* has not submitted a *proposed access arrangement* to the *Authority*, the *Authority* will draft, approve and *publish* its own *access arrangement* for the *covered network*.²⁶⁶
- 4.56 If a *service provider* has not submitted a *proposed access arrangement* to the *Authority* within 20 *business days* of the *publishing* of a notice under section 4.55, the *Authority* must, within 12 months after the *submission deadline*, draft, approve and *publish* its own *access arrangement* for the *covered network*.²⁶⁷
- 4.57 The *Authority* must consult the public under Appendix 7 before drafting, approving and *publishing* its own *access arrangement* under section 4.56.²⁶⁸
- 4.58 If the *Authority* drafts, approves and *publishes* its own *access arrangement* for a *covered network* under section 4.56, it must also draft, approve and *publish access arrangement information* for the *covered network*.²⁶⁹

Interim access arrangement in the event of delay

- 4.59 If, for the *first access arrangement period*:
- (a) a *service provider* has submitted a *proposed access arrangement*; but
 - (b) by 12 months after the *submission deadline* no *access arrangement* has been approved under this Chapter 4,
- then, as soon as practicable and in any event within 18 months after the *submission deadline*, the *Authority* must draft, approve and *publish* an “**interim access arrangement**” to take effect for the *interim access arrangement period*.²⁷⁰
- 4.60 Unless a *user* requests otherwise, an *access contract* entered into under an *interim access arrangement* is deemed to provide that at the end of the *interim access arrangement period*:
- (a) the *tariff* payable under the *access contract* is varied from the end of the *interim access arrangement period* to be the *tariff* payable for an equivalent service under the *access arrangement*; and

²⁶⁵ Section 4.54 amended by WAGG No 157, 18 September 2020

²⁶⁶ Section 4.55 amended by WAGG No 157, 18 September 2020

²⁶⁷ Section 4.56 amended by WAGG No 157, 18 September 2020

²⁶⁸ Section 4.57 amended by WAGG No 157, 18 September 2020

²⁶⁹ Section 4.58 amended by WAGG No 157, 18 September 2020

²⁷⁰ Section 4.59 amended by WAGG No 157, 18 September 2020

- (b) the difference between:
 - (i) the *charges* paid between the commencement date of the *access contract* and the end of the *interim access arrangement period* based on the *access contract tariffs*; and
 - (ii) the *charges* that would have been payable under the *access contract* had the *access arrangement* been in effect during the *interim access arrangement period* and the *access arrangement tariffs* had applied to the *access contract* (which are to be calculated using the *user's* actual use of *services* during the period, without allowing for any possible variation in the *user's* use of *services* arising from the different *tariffs*),

must be treated as an underpayment or overpayment, as appropriate, under the *access contract* and must be paid by or paid to, as applicable, the *user*.

4.61 For the purposes of section 4.60:

- (a) the date of underpayment or overpayment, as appropriate, is deemed to be the *approval* date of the subsequent *access arrangement*; and
- (b) either party may give notice to the other of an underpayment or overpayment under the *access contract* and section 4.60.

4.62 To assist with the determination of:

- (a) the underpayment or overpayment amount under section 4.60(b); and
- (b) the *access contract* variation under section 4.60(a),

the *Authority* must not approve an *access arrangement* which does not:

- (c) designate, for each *reference service* under the *interim access arrangement*, an equivalent *covered service* in the *access arrangement*; and
- (d) specify a *tariff* for each equivalent *covered service* designated under section 4.62(c); and
- (e) provide for suitable provisions to deal with the underpayment or overpayment, as appropriate, under section 4.60.

4.63 Nothing in section 4.62 obliges a *service provider* to, after the end of the *interim access arrangement period*, enter into an *access contract* to provide, or to provide at a particular *tariff*, a *covered service* which was a *reference service* under an *interim access arrangement* but is not a *reference service* under the *access arrangement*.

Extensions of time under this Chapter 4

4.64 Subject to section 4.65, the *Authority* may extend any deadline specified in this Chapter 4 but only if, and only to the extent that, the *Authority* first determines as a *reasonable and prudent person* that:

- (a) a longer period of time is essential for due consideration of all the matters under consideration or satisfactory performance of the relevant obligation, or both; and
 - (b) the *Authority* or the *service provider*, as applicable, has taken all reasonable steps to fully utilise the times and processes provided for in this Chapter 4.²⁷¹
- 4.65 The *Authority* must not exercise the power in section 4.64 to extend any deadline unless, before the day on which the time would otherwise have expired, it *publishes* notice of, and *reasons* for, its decision to extend the deadline.²⁷²
- 4.66 A decision (however described) made by the *Authority* under this Code after the expiry of the period of time specified in this Code for the making of that decision is not to be taken to be an invalid decision only because the decision is not made within the specified period of time.²⁷³
- 4.67 [Not used]²⁷⁴

Suspension of deadlines when Authority obtains information

- 4.68 Despite anything else in this Code, if the *Authority* exercises its power to obtain information and documents under section 51 of the *Economic Regulation Authority Act 2003* in respect of an *access arrangement*, then:
- (a) the *Authority* may, by *publishing* a notice, suspend the operation of the deadline for the issue of a *draft decision* under section 4.12, a *final decision* under section 4.17 or an *interim access arrangement* under section 4.59, if the *Authority* considers that such a suspension is essential for due consideration of all the matters relevant to the decision; and
 - (b) if the *Authority* suspends a deadline under section 4.68(a) — time ceases to run in respect of the relevant deadline until the suspension is ended by the *Authority publishing* a notice, which it must *publish* no later than 10 *business days* after it receives the information or documents but may *publish* at any earlier time.

Suspension of deadlines for judicial proceedings

- 4.69 Despite anything else in this Code, if judicial proceedings commence with respect to an *access arrangement* or a matter of interpretation or *application* of this Code which is likely to affect the *approval* of an *access arrangement* (“**judicial proceedings**”), then:
- (a) the *Authority* may, by *publishing* a notice, suspend the operation of the deadline for the issue of a *draft decision* under section 4.12 or a *final decision* under section 4.17, if the *Authority* considers that it is essential that the *judicial proceedings* be resolved in order for the *Authority* in its *draft decision*

²⁷¹ Section 4.64 amended by WAGG No 157, 18 September 2020

²⁷² Section 4.65 amended by WAGG No 157, 18 September 2020

²⁷³ Section 4.66 amended by WAGG No 157, 18 September 2020

²⁷⁴ Section 4.67 deleted by WAGG No 157, 18 September 2020

or *final decision*, as applicable, to give due consideration to the matters raised in the *judicial proceedings*; and²⁷⁵

- (b) if the *Authority* suspends a deadline under section 4.69(a) — time ceases to run in respect of the relevant deadline until the suspension is ended by the *Authority publishing* a notice, which it must *publish* no later than 10 *business days* after the *judicial proceedings* have been determined or discontinued but may *publish* at any earlier time.

Suspension of deadlines for Code amendment

4.70 In section 4.71, “notice of proposed amendment” means a written notice, expressed to be given under this section 4.70, from the Coordinator to the *Authority* in respect of a proposed amendment to, or repeal and replacement of, this Code.

4.71 Despite anything else in this Code, if the Coordinator gives the *Authority* a notice of proposed amendment, then—

- (a) the *Authority* may, by *publishing* a notice, suspend the operation of the deadline for the issue of a *draft decision* under section 4.12, a *final decision* under section 4.17 or an *interim access arrangement* under section 4.59, if the *Authority* reasonably considers that the proposed amendment, or repeal and replacement, would, if made, materially affect the *Authority’s* determination of the *draft decision*, *final decision* or *interim access arrangement*; and
- (b) if the *Authority* suspends a deadline under section 4.71(a) — time ceases to run in respect of the relevant deadline until the suspension is ended by the *Authority publishing* a notice, which it must *publish* no later than 10 *business days* after the earlier of—
 - (i) the date the amendment, or repeal and replacement, takes effect; and
 - (ii) the date the Coordinator gives the *Authority* written notice withdrawing the notice of proposed amendment.²⁷⁶

[Heading not used]²⁷⁷

4.72 [Not used]²⁷⁸

4.73 [Not used]²⁷⁹

4.74 [Not used]²⁸⁰

²⁷⁵ Section 4.69 amended by WAGG No 157, 18 September 2020

²⁷⁶ Sections 4.70 and 4.71 inserted by WAGG No 152, 1 September 2006

²⁷⁷ Heading to section 4.72 deleted by WAGG No 157, 18 September 2020

²⁷⁸ Section 4.72 deleted by WAGG No 157, 18 September 2020

²⁷⁹ Section 4.73 deleted by WAGG No 157, 18 September 2020

²⁸⁰ Section 4.74 deleted by WAGG No 157, 18 September 2020

4.75 [Not used]²⁸¹

4.76 [Not used]²⁸²

[Heading not used]²⁸³

4.77 [Not used]²⁸⁴

4.78 [Not used]²⁸⁵

4.79 [Not used]²⁸⁶

“Review of access arrangement for the Western Power Network after first 2020 Code change²⁸⁷

4.80 Sections 4.81 to 4.82 apply only in respect of the *application* of the next *review* of the *access arrangement* for the Western Power Network after the 2020 (No. 1) amendments and not any subsequent reviews.²⁸⁸

4.81 In sections 4.80 to 4.82—

“**2020 (No. 1) amendments**” means the amendments to this Code made by the *Electricity Networks Access Code Amendments (No.1) 2020*.

{Note: The *Electricity Networks Access Code Amendments (No.1) 2020* were Gazetted on 26 June 2020.}²⁸⁹

4.82 Despite anything else in this Code or the *access arrangement* for the Western Power Network, the *revisions submission date* by which the Electricity Networks Corporation must submit its *proposed revisions* to the *access arrangement* for the *Western Power Network* and revised *access arrangement information* to the *Authority* is deemed to be 1 February 2022.²⁹⁰

Amendments of model documents for Western Power Network²⁹¹

4.83 Section 4.84 to 4.85 apply only in respect of the *access arrangement* for the *Western Power Network* in force as at the time the 2021 amendments come into force, and not to any subsequent *reviews* of that *access arrangement*.²⁹²

4.84 In sections 4.83 to 4.85—

²⁸¹ Section 4.75 deleted by WAGG No 157, 18 September 2020

²⁸² Section 4.76 deleted by WAGG No 157, 18 September 2020

²⁸³ Heading to section 4.77 deleted by WAGG No 157, 18 September 2020

²⁸⁴ Section 4.77 deleted by WAGG No 157, 18 September 2020

²⁸⁵ Section 4.78 deleted by WAGG No 157, 18 September 2020

²⁸⁶ Section 4.79 deleted by WAGG No 157, 18 September 2020

²⁸⁷ Heading to section 4.80 inserted by WAGG No 108, 26 June 2020

²⁸⁸ Section 4.80 inserted by WAGG No 108, 26 June 2020

²⁸⁹ Section 4.81 inserted by WAGG No 108, 26 June 2020

²⁹⁰ Section 4.82 inserted by WAGG No 108, 26 June 2020

²⁹¹ Heading to section 4.83 inserted by WAGG No 134, 30 July 2021

²⁹² Section 4.83 inserted by WAGG No 134, 30 July 2021

“2021 amendments” means the amendments to this Code made by the *Electricity Networks Access Code Amendments 2021*.

{Note: The *Electricity Networks Access Code Amendments 2021* were Gazetted on 30 July 2021.}²⁹³

- 4.85 Notwithstanding anything else in this Code or the *access arrangement* for the Western Power Network:
- (a) the *applications and queuing policy* and *transfer and relocation policy* applicable under the *access arrangement* for the *Western Power Network* are deemed to be in the form set out in Appendix 2A;
 - (b) the *standard access contract* applicable under the *access arrangement* for the *Western Power Network* is deemed to be in the form set out in Appendix 3A; and
 - (c) the *contributions policy* applicable under the *access arrangement* for the *Western Power Network* is deemed to be in the form set out in Appendix 4A.²⁹⁴

²⁹³ Section 4.84 inserted by WAGG No 134, 30 July 2021

²⁹⁴ Section 4.85 inserted by WAGG No 134, 30 July 2021

Chapter 5 – Access Arrangement: Content

Required contents of an access arrangement

5.1 An *access arrangement* must:

- (a) specify one or more *reference services* under section 5.2; and
- (b) include a *standard access contract* under sections 5.3 to 5.5 for each *reference service*; and

{Note: An *access arrangement* may contain a single *standard access contract* in which the majority of terms and conditions apply to all *reference services* and the other terms and conditions apply only to specified *reference services*.}

- (c) include *service standard benchmarks* under section 5.6 for each *reference service*; and
- (d) include *price control* under Chapter 6; and
- (e) include a *tariff structure statement* and *reference tariff change forecast* under Chapter 7; and
- (f) include²⁹⁵ a description of the *pricing years* for the *access arrangement*; and
- (g) include an *applications and queuing policy* under sections 5.7 to 5.11; and
- (h) include a *contributions policy* under sections 5.12 to 5.17D;²⁹⁶ and
- (i) [not used]
- (j) if required under section 5.25, include *efficiency and innovation benchmarks* under section 5.26; and
- (k) include provisions dealing with *supplementary matters* under sections 5.27 and 5.28; and
- (l) include provisions dealing with:
 - (i) the submission of *proposed revisions* under sections 5.29 to 5.33; and
 - (ii) *trigger events* under sections 5.34 to 5.36; and

{Note: At the same time as an *access arrangement* is submitted, *access arrangement information* must be submitted under section 4.1 and *technical rules* must be submitted under

²⁹⁵ Section 5.1 amended by WAGG No 207, 8 November 2005

²⁹⁶ Section 5.1 amended by WAGG No 180, 22 October 2008

section 12.10. Neither the *access arrangement information* nor the *technical rules* are part of the *access arrangement*.)

- (m) include a *multi-function asset policy* under section 5.37.²⁹⁷

Reference services

5.2 An *access arrangement* must:

- (a) specify at least one *reference service*; and
- (b) specify a *reference service* for each *covered service* that is likely to be sought by (or the benefit of which is likely to be sought by) either or both of:
 - (i) a significant number of *customers* and *applicants*; or
 - (ii) a substantial proportion of the market for *services* in the *covered network*;and²⁹⁸
- (c) to the extent reasonably practicable, specify *reference services* in such a manner that a *user* or *applicant* is able to acquire by way of one or more *reference services* only those elements of a *covered service* that the *user* or *applicant* wishes to acquire; and
- (d) for the *Western Power Network*²⁹⁹— specify one or more *reference services* such that there is both:
 - (i) a *reference service* which enables a *user* or *applicant* to acquire an *entry service* at a *connection point* without a need to acquire a corresponding *exit service* at another *connection point*; and
 - (ii) a *reference service* which enables a *user* or *applicant* to acquire an *exit service* at a *connection point* without a need to acquire a corresponding *entry service* at another *connection point*.

5.2A In determining whether an *access arrangement* complies with section 5.2(b), the *Authority* must have regard to any information provided by a person pursuant to section 4.A14.³⁰⁰

Standard access contract for each reference service

5.3 A *standard access contract* must be:

- (a) reasonable; and
- (b) sufficiently detailed and complete to:

²⁹⁷ Section 5.1 amended by WAGG No 157, 18 September 2020

²⁹⁸ Section 5.2 amended by WAGG No 157, 18 September 2020

²⁹⁹ Section 5.2 amended by WAGG No 180, 22 October 2008

³⁰⁰ Section 5.2A inserted by WAGG No 157, 18 September 2020

- (i) form the basis of a commercially workable *access contract*; and
- (ii) enable a *user* or *applicant* to determine the value represented by the *reference service* at the *reference tariff*.

5.4 A *standard access contract* may:

- (a) be based in whole or in part upon the *model standard access contract*, in which case, to the extent that it is based on the *model standard access contract*, any matter which in the *model standard access contract* is left to be completed in the *access arrangement*, must be completed in a manner consistent with:
 - (i) any instructions in relation to the matter contained in the *model standard access contract*; and
 - (ii) section 5.3;
 - (iii) the *Code objective*; and
- (b) be formulated without any reference to the *model standard access contract* and is not required to reproduce, in whole or in part, the *model standard access contract*.

{Note: The intention of this section 5.4(b) is to ensure that the *service provider* is free to formulate its own *standard access contract* which complies with section 5.3 but is not based on the *model standard access contract*.}

5.5 The *Authority*:

- (a) must determine that a *standard access contract* is consistent with section 5.3 and the *Code objective* to the extent that it reproduces without material omission or variation the *model standard access contract*; and
- (b) subject to section 5.38, otherwise must have regard to the *model standard access contract* in determining whether the *standard access contract* is consistent with section 5.3 and the *Code objective*.³⁰¹

Service standards for each reference service

5.6 A *service standard benchmark* for a *reference service* must be:

- (a) reasonable; and
- (b) sufficiently detailed and complete to enable a *user* or *applicant* to determine the value represented by the *reference service* at the *reference tariff*.

³⁰¹ Section 5.5 amended by WAGG No 134, 30 July 2021

Applications and queuing policy

5.7 An *applications and queuing policy* must:

- (a) to the extent reasonably practicable, accommodate the interests of the *service provider* and of *users* and *applicants*; and
- (b) be sufficiently detailed to enable *users* and *applicants* to understand in advance how the *applications and queuing policy* will operate; and
- (c) set out a reasonable timeline for the commencement, progressing and finalisation of *access contract* negotiations between the *service provider* and an *applicant*, and oblige the *service provider* and *applicants* to use reasonable endeavours to adhere to the timeline; and
- (d) oblige the *service provider*, subject to any reasonable confidentiality requirements in respect of *competing applications*, to provide to an *applicant* all commercial and technical information reasonably requested by the *applicant* to enable the *applicant* to apply for, and engage in effective negotiation with the *service provider* regarding, the terms for an *access contract* for a *covered service* including:
 - (i) information in respect of the availability of *covered services* on the *covered network*; and
 - (ii) if there is any *required work*:³⁰²
 - A. operational and technical details of the *required work*³⁰³; and
 - B. commercial information regarding the likely cost of the *required work*³⁰⁴;and
- (e) set out the procedure for determining the *priority* that an *applicant* has, as against another *applicant*, to obtain *access to covered services*, where the *applicants' access applications* are *competing applications*; and
- (f) to the extent that *contestable consumers* are connected at *exit points* on the *covered network*, contain provisions dealing with the *transfer* of capacity associated with a *contestable consumer* from the *user* currently supplying the *contestable consumer* (“**outgoing user**”) to another *user* or an *applicant* (“**incoming user**”) which, to the extent that it is applicable, are consistent with and facilitate the operation of any *customer transfer code*; and
- (g) establish arrangements to enable a *user* who is:
 - (i) a ‘supplier of last resort’ as defined in section 67 of the Act to comply with its obligations under Part 5 of the Act; and

³⁰² Section 5.7 amended by WAGG No 180, 22 October 2008

³⁰³ Section 5.7 amended by WAGG No 180, 22 October 2008

³⁰⁴ Section 5.7 amended by WAGG No 180, 22 October 2008

- (ii) a 'default supplier' under regulations made in respect of section 59 of the Act to comply with its obligations under section 59 of the Act and the regulations; and
- (h) facilitate the operation of Part 9 of the Act, any enactment under Part 9 of the Act and the *WEM Rules*; and
- (i) if applicable, contain provisions setting out how *access applications* (or other requests for *access* to the *covered network*) lodged before the start of the relevant *access arrangement period* are to be dealt with; and
- (j) set out the *transfer and relocation policy*, which policy will set out the circumstances in which the *service provider* is obliged to agree to a *user transferring* all of its rights and obligations under an *access contract* to another person or part of its rights and obligations under an *access contract* to another person.³⁰⁵

{Note: For the *first access arrangement period* section 5.7(i) would apply in respect of *access applications* or requests for *access* lodged under any prior *access* regime such as the regimes established under the *Electricity Transmission Regulations 1996 (WA)* and *Electricity Distribution Regulations 1997 (WA)*. For subsequent *access arrangement periods* it would apply in respect of *access applications* lodged in a prior *access arrangement period*.}

5.8 The paragraphs of section 5.7 do not limit each other.

5.8A The *transfer and relocation policy* must:

- (a) require the *service provider* not to unreasonably withhold its consent to a *transfer* by a *user* of all of its rights and obligations under an *access contract*; and
- (b) require the *service provider* not to unreasonably withhold its consent to a *transfer* by a *user* of parts of its rights or obligations under an *access contract* provided the rights and obligations being *transferred* are of a nature such that they can be meaningfully severed from the remainder of the *access contract*.³⁰⁶

5.9 Under section 5.7(e), the *applications and queuing policy* may:

- (a) provide that if there are *competing applications*, then *priority* between the *access applications* is to be determined by reference to the time at which the *access applications* were lodged with the *service provider*, but if so the *applications and queuing policy* must:
 - (i) provide for departures from that principle where necessary to achieve the *Code objective*; and

³⁰⁵ Section 5.7 amended by WAGG No 157, 18 September 2020

³⁰⁶ Section 5.8A inserted by WAGG No 157, 18 September 2020

- (ii) contain provisions entitling an *applicant*, subject to compliance with any reasonable conditions, to:
 - A. current information regarding its position in the *queue*; and
 - B. information in reasonable detail regarding the aggregated capacity requirements sought in *competing applications* ahead of its *access application* in the *queue*; and
 - C. information in reasonable detail regarding the likely time at which the *access application* will be satisfied;

and

- (b) oblige the *service provider*, if it is of the opinion that an *access application* relates to a particular project or development:
 - (i) which is the subject of an invitation to tender; and
 - (ii) in respect of which other *access applications* have been lodged with the *service provider*,

(“**project applications**”) to, treat the *project applications*, for the purposes of determining their *priority*, as if each of them had been lodged on the date that the *service provider* becomes aware that the invitation to tender was announced.

5.9A If:

- (a) an *access application* (the “**first application**”) seeks modifications to a *contract for services*; and
- (b) the modifications, if implemented, would not materially impede the *service provider’s* ability to provide a *covered service* sought in one or more other *access applications* (each an “**other application**”) compared with what the position would be if the modifications were not implemented,

then the *first application* is not, by reason only of seeking the modifications, a *competing application* with the *other applications*.³⁰⁷

5.10 An *applications and queuing policy* may:

- (a) be based in whole or in part upon the *model applications and queuing policy*, in which case, to the extent that it is based on the *model applications and queuing policy*, any matter which in the *model applications and queuing policy* is left to be completed in the *access arrangement*, must be completed in a manner consistent with:
 - (i) any instructions in relation to the matter contained in the *model applications and queuing policy*; and
 - (ii) sections 5.7 to 5.9;

³⁰⁷ Section 5.9A inserted by WAGG No 180, 22 October 2008

- (iii) the *Code objective*; and
- (b) be formulated without any reference to the *model applications and queuing policy* and is not required to reproduce, in whole or in part, the *model applications and queuing policy*.

{Note: The intention of this section 5.10(b) is to ensure that the *service provider* is free to formulate its own *applications and queuing policy* which complies with sections 5.7 to 5.9 but is not based on the *model applications and queuing policy*.}

5.11 The *Authority*:

- (a) must determine that an *applications and queuing policy* is consistent with sections 5.7 to 5.9 and the *Code objective* to the extent that it reproduces without material omission or variation the *model applications and queuing policy*; and
- (b) subject to section 5.38, otherwise must have regard to the *model applications and queuing policy* in determining whether the *applications and queuing policy* is consistent with sections 5.7 to 5.9 and the *Code objective*.³⁰⁸

Contributions policy³⁰⁹

5.12 The objectives for a *contributions policy* must be that:

- (a) it strikes a balance between the interests of:
 - (i) *contributing users*; and
 - (ii) *other users*; and
 - (iii) *consumers*; and
- (b) it does not constitute an inappropriate barrier to entry.³¹⁰

5.13 A *contributions policy* must facilitate the operation of this Code, including:

- (a) sections 2.10 to 2.12; and
- (b) the test in section 6.51A; and
- (a) sections 5.14 and 5.17D; and
- (c) the *regulatory test*.³¹¹

³⁰⁸ Section 5.11 amended by WAGG No 134, 30 July 2021

³⁰⁹ Heading to section 5.12 amended by WAGG No 180, 22 October 2008

³¹⁰ Section 5.12 amended by WAGG No 180, 22 October 2008

³¹¹ Section 5.13 amended by WAGG No 180, 22 October 2008

- 5.14 Subject to section 5.17A and a *headworks scheme*, a *contributions policy*:
- (a) must not require a *user* to make a *contribution* in respect of any part of *new facilities investment* which meets the *new facilities investment test*; and
 - (b) must not require a *user* to make a *contribution* in respect of any part of *non-capital costs* which would not be incurred by a *service provider efficiently minimising costs*; and
 - (c) may only require a *user* to make a *contribution* in respect of *required work*; and
 - (d) without limiting sections 5.14(a) and 5.14(b), must contain a mechanism designed to ensure that there is no double recovery of *new facilities investment* or *non-capital costs*.³¹²
- 5.14A [not used]³¹³
- 5.15 A *contributions policy* must set out:
- (a) the circumstances in which a *contributing user* may be required to make a *contribution*; and
 - (b) the method for calculating any *contribution* a *contributing user* may be required to make; and
 - (c) for any *contribution*:
 - (i) the terms on which a *contributing user* must make the *contribution*; or
 - (ii) a description of how the terms on which a *contributing user* must make the *contribution* are to be determined.³¹⁴
- 5.16 A *contributions policy* may:
- (a) be based in whole or in part upon the *model contributions policy*, in which case, to the extent that it is based on the *model contributions policy*, any matter which in the *model contributions policy* is left to be completed in the *access arrangement*, must be completed in a manner consistent with:
 - (i) any instructions in relation to the matter contained in the *model contributions policy*; and
 - (ii) sections 5.12 to 5.15; and
 - (iii) the *Code objective*; and

³¹² Section 5.14 amended by WAGG No 137, 29 June 2007; Section 5.14 amended by WAGG No 206, 8 December 2006; Section 5.14 amended by WAGG No 180, 22 October 2008

³¹³ Section 5.14A inserted by WAGG No 206, 8 December 2006; Section 5.14A deleted by WAGG No 137, 29 June 2007

³¹⁴ Section 5.15 amended by WAGG No 180, 22 October 2008

- (b) be formulated without any reference to the model *contributions policy* and is not required to reproduce, in whole or in part, the model *contributions policy*.³¹⁵

{Note: The intention of this section 5.16(b) is to ensure that the *service provider* is free to formulate its own *contributions policy* which complies with sections 5.12 to 5.15 but is not based on the model *contributions policy*.}³¹⁶

5.17 The *Authority*:

- (a) must determine that a *contributions policy* is consistent with sections 5.12 to 5.15 and the *Code objective* to the extent that it reproduces without material omission or variation the *model contributions policy*; and
- (b) subject to section 5.38, otherwise must have regard to the *model contributions policy* in determining whether the *contributions policy* is consistent with sections 5.12 to 5.15 and the *Code objective*.³¹⁷

Contributions for certain Western Power Network work³¹⁸

5.17A Despite section 5.14, Electricity Networks Corporation may require a *contribution* for Appendix 8 work of up to the maximum amount determined under Appendix 8 for the relevant type of Appendix 8 work.³¹⁹

5.17B From 1 July 2007 until the first *revisions commencement date* for the Western Power Network *access arrangement*, section 5.17A prevails over any inconsistent provision of the Western Power Network *access arrangement*.³²⁰

Headworks scheme³²¹

5.17C Despite section 5.14, the *Authority* may approve a *contributions policy* that includes a “**headworks scheme**” which requires a *user* to make a payment to the *service provider* in respect of the *user’s* capacity at a *connection point* on a distribution system because the *user* is a member of a class, whether or not there is any *required work* in respect of the *user*.

{Example: In 2008 Electricity Networks Corporation adopted a headworks scheme under which new *users* in certain rural parts of the SWIS who *connect* more than 25 km along the wires from a zone substation, were required to pay a headworks *charge* in respect of reinforcement of the 3 phase HV distribution

³¹⁵ Section 5.16 amended by WAGG No 180, 22 October 2008

³¹⁶ Note to section 5.16 amended by WAGG No 180, 22 October 2008

³¹⁷ Section 5.17 amended by WAGG No 180, 22 October 2008; Section 5.17 amended by WAGG No 134, 30 July 2021

³¹⁸ Heading to section 5.17A amended by WAGG No 180, 22 October 2008

³¹⁹ Section 5.17A inserted by WAGG No 137, 29 June 2007; Section 5.17A amended by WAGG No 180, 22 October 2008

³²⁰ Section 5.17B inserted by WAGG No 137, 29 June 2007; Section 5.17B amended by WAGG No 180, 22 October 2008

³²¹ Heading to section 5.17C inserted by WAGG No 180, 22 October 2008

network, whether or not the *user's* connection made any such reinforcement necessary.)³²²

5.17D A headworks scheme must:

- (a) identify the class of *works* in respect of which the scheme applies, which must not include any *works* on a *transmission system* or any *works* which effect a geographic extension of a *network*; and
- (b) not seek to recover *headworks charges* in an *access arrangement period* which in aggregate exceed 4% of the *distribution system target revenue* for the *access arrangement period*; and
- (c) identify the class of *users* who must make a payment under the scheme; and
- (d) set out the method for calculating the *headworks charge*, which method:
 - (i) must have the objective that *headworks charges* under the *headworks scheme* will, in the long term, and when applied across all *users* in the class referred to in section 5.17D(c), recover no more than the *service provider's* costs (such as would be incurred by a *service provider efficiently minimising costs*) of any *headworks*; and
 - (ii) must have the objective that the *headworks charge* payable by one *user* will differ from that payable by another *user* as a result of material differences in the *users' capacities* and the locations of their *connection points*, unless the *Authority* considers that a different approach would better achieve the *Code objective*; and
 - (iii) may use estimates and forecasts (including long term estimates and forecasts) of loads and costs; and
 - (iv) must contain a mechanism designed to ensure that there is no double recovery of costs in all the circumstances, including the manner of calculation of other *contributions* and *tariffs*; and
 - (v) may exclude a rebate mechanism (of the type contemplated by clauses A4.13(d) or A4.14(c)(ii) of Appendix 4) and may exclude a mechanism for retrospective adjustments to account for the

[Heading not used]³²³

³²² Section 5.17C and example inserted by WAGG No 180, 22 October 2008

³²³ Heading to section 5.18 deleted by WAGG No 157, 18 September 2020

5.18 [Not used]³²⁴

5.19 [Not used]³²⁵

5.20 [Not used]³²⁶

5.21 [Not used]³²⁷

5.22 [Not used]³²⁸

5.23 [Not used]³²⁹

5.24 [Not used]³³⁰

Efficiency and innovation benchmarks

5.25 An *access arrangement* which contains a *gain sharing mechanism* must, and an *access arrangement* which does not contain a *gain sharing mechanism* may, contain *efficiency and innovation benchmarks*.

5.26 *Efficiency and innovation benchmarks* must:

- (a) if the *access arrangement* contains a *gain sharing mechanism*, be sufficiently detailed and complete to permit the *Authority* to make a determination under section 6.25 at the next *access arrangement review*; and
- (b) provide an objective standard for assessing the *service provider's* efficiency and innovation during the *access arrangement period*; and
- (c) be reasonable.

Supplementary matters

5.27 Each of the following matters is a “**supplementary matter**”:

- (a) balancing; and
- (b) line losses; and
- (c) metering; and
- (d) ancillary *services*; and
- (e) stand-by; and
- (f) trading; and

³²⁴ Section 5.18 deleted by WAGG No 157, 18 September 2020

³²⁵ Section 5.19 deleted by WAGG No 157, 18 September 2020

³²⁶ Section 5.20 deleted by WAGG No 157, 18 September 2020

³²⁷ Section 5.21 deleted by WAGG No 157, 18 September 2020

³²⁸ Section 5.22 deleted by WAGG No 157, 18 September 2020

³²⁹ Section 5.23 deleted by WAGG No 157, 18 September 2020

³³⁰ Section 5.24 deleted by WAGG No 157, 18 September 2020

- (g) settlement; and
- (h) any other matter in respect of which arrangements must exist between a *user* and a *service provider* to enable the efficient operation of the *covered network* and to facilitate access to *services*, in accordance with the *Code objective*.

5.28 An *access arrangement* must deal with a *supplementary matter* in a manner which:

- (a) to the extent that the *supplementary matter* is dealt with in:
 - (i) an enactment under Part 9 of the Act; or
 - (ii) the *WEM Rules*,
applying to the *covered network* — is consistent with and facilitates the treatment of the *supplementary matter* in the enactment or *WEM Rules*; and³³¹
- (b) to the extent that the *supplementary matter* is dealt with:
 - (i) in a *written law* other than as contemplated under section 5.28(a); and
 - (ii) in a manner which is not inconsistent with the requirement under section 5.28(a) to the extent that it applies to the *covered network*,
is consistent with and facilitates the treatment of the *supplementary matter* in the *written law*; and
- (c) otherwise — in accordance with the *technical rules* applying to the *covered network* and the *Code objective*.

Revisions submission

5.29 An *access arrangement* must specify:

- (a) a *revisions submission date*; and
- (b) a *target revisions commencement date*.

5.30 For the *first access arrangement*:

- (a) the *revisions submission date* must be at least 6 months before the *target revisions commencement date* under section 5.30(b); and
- (b) the *target revisions commencement date* must be no more than 3 years after the *access arrangement start date*.

5.31 Subject to section 5.32, for *access arrangements* other than the *first access arrangement*:

³³¹ Section 5.28 amended by WAGG No 157, 18 September 2020

- (a) the *revisions submission date* must be at least 17 months before the *target revisions commencement date*; and³³²
- (b) the *target revisions commencement date* must be 5 years after the start of the *access arrangement period*, unless a different date is proposed by the *service provider* and the different date is consistent with the *Code objective*.

5.32 The *Authority*:

- (a) in determining whether an *access arrangement period* of longer than 5 years is consistent with the *Code objective* must have regard to:
 - (i) the likely advantages of the *approval* (including by way of reduced regulatory costs); and
 - (ii) the likely disadvantages of the *approval*; and
- (b) if it determines that an *access arrangement period* of longer than 5 years is consistent with the *Code objective*, must consider whether to require under section 5.34 that the *access arrangement* include one or more *trigger events*.

5.33 Section 5.32(a) does not limit the matters to which the *Authority* may have regard.

Trigger events

5.34 If it is consistent with the *Code objective* an *access arrangement* may specify one or more *trigger events*.

5.35 To avoid doubt, under section 5.34, an *access arrangement* may specify a *trigger event* which was not proposed by the *service provider*.

5.36 Before determining whether a *trigger event* is consistent with the *Code objective* the *Authority* must consider:

- (a) whether the advantages of including the *trigger event* outweigh the disadvantages of doing so, in particular the disadvantages associated with decreased regulatory certainty; and
- (b) whether the *trigger event* should be balanced by one or more other *trigger events*.

{Example: The *service provider* may wish to include a *trigger event* allowing it to reopen the *access arrangement* if actual *covered service* consumption is more than x% below forecast. However, if the *Authority* were minded to allow such a *trigger event*, it may also require the inclusion of a complementary *trigger event* requiring the *service provider* to reopen the *access arrangement* if *covered service* consumption is more than y% above forecast.}

Multi-function asset policy

5.37 A *multi-function asset policy* must:

³³² Section 5.31 amended by WAGG No 157, 18 September 2020

- (a) to the extent reasonably practicable, accommodate the interests of the *service provider* and of *users* and *applicants*; and
- (b) be sufficiently detailed to enable *users* and *applicants* to understand in advance how the *multi-function asset policy* will operate; and
- (c) set out the method for determining *net incremental revenue*; and
- (d) be consistent with the *multi-function asset guidelines*.³³³

Assessment of model documents³³⁴

5.38 Notwithstanding sections 5.5(b), 5.11(b) and 5.17(b), when determining whether the *standard access contract, applications and queuing policy* or *contributions policy* (as applicable) included in an *access arrangement* is consistent with the *Code objective* and sections 5.3, 5.7 to 5.9, or 5.12 to 5.15 (as applicable), the *Authority* must not have regard to any provisions of the *model standard access contract, model applications and queuing policy* or *model contributions policy* (as applicable) that are inconsistent with section 2.4C or otherwise inconsistent with the operation of security constrained economic dispatch in the *Wholesale Electricity Market*.³³⁵

³³³ Section 5.37 inserted by WAGG No 157, 18 September 2020

³³⁴ Heading to section 5.38 inserted by WAGG No 134, 30 July 2021

³³⁵ Section 5.38 inserted by WAGG No 134, 30 July 2021

Chapter 6 – Price Control

Subchapter 6.1 – Target revenue

Form of price control

- 6.1 Subject to section 6.3, an *access arrangement* may contain any form of *price control* provided it meets the objectives set out in section 6.4 and otherwise complies with this Chapter 6.
- 6.2 Without limiting the forms of *price control* that may be adopted, *price control* may set *target revenue*:
- (a) by reference to the *service provider's approved total costs*; or

{Note: This includes “revenue cap” *price controls* based on controlling total revenue, average revenue or revenue yield and “price cap” *price controls* based on cost of service.}
 - (b) by setting *tariffs* with reference to:
 - (i) *tariffs* in previous *access arrangement periods*; and
 - (ii) changes to costs and productivity growth in the electricity industry;

{Note: This includes “price cap” *price controls* based on controlling the weighted average of *tariffs* or individual *tariffs*.}
- or
- (c) using a combination of the methods described in sections 6.2(a) and 6.2(b).

Form of price control for first access arrangement

- 6.3 The *first access arrangement* must contain the form of *price control* described in section 6.2(a).

Price control objectives

- 6.4 The *price control* in an *access arrangement* must have the objectives of:
- (a) giving the *service provider* an opportunity to earn revenue (“**target revenue**”) for the *access arrangement period* from the provision of *covered services* as follows:
 - (i) an amount that meets the forward-looking and efficient costs of providing *covered services*, including a return on investment commensurate with the commercial risks involved;

plus:

- (ii) for *access arrangements* other than the *first access arrangement*, an amount in excess of the revenue referred to in section 6.4(a)(i), to the extent necessary to reward the *service provider* for efficiency gains and innovation beyond the *efficiency and innovation benchmarks* in a previous *access arrangement* or to penalise the *service provider* for efficiency losses derived from a failure to meet the *efficiency and innovation benchmarks* in a previous *access arrangement*;

{Note: The presence of section 6.4(a)(ii) provides incentive to a *service provider* during an *access arrangement period* to pursue efficiency gains and innovation beyond the *efficiency and innovation benchmarks* in the *access arrangement*, because the *service provider* may be rewarded in the calculation of the *target revenue* for subsequent *access arrangement periods*.}

plus:

- (iiA) an amount (if any) determined under sections 6.5A to 6.5E; plus: ³³⁶
- (iiB) an amount (if any) determined under sections 6.5F to 6.5J; plus
- (iii) an amount (if any) determined under section 6.6; plus:
- (iv) an amount (if any) determined under section 6.9; plus:
- (v) an amount (if any) determined under an *investment adjustment mechanism* (see sections 6.13 to 6.18);

plus:

- (vi) an amount (if any) determined under a *service standards adjustment mechanism* (see sections 6.29 to 6.32);

plus —

- (vii) an amount (if any) determined under section 6.37A; ³³⁷

and

- (b) enabling a *user* to predict the likely annual changes in *target revenue* during the *access arrangement period*; and
- (c) minimising, as far as reasonably possible, variance between expected revenue for the last *pricing year* in the *access arrangement period* and the *target revenue* for that last *pricing year*. ³³⁸

³³⁶ Section 6.4 amended by WAGG No 182, 30 September 2011

³³⁷ Section 6.4(a)(vii) inserted by WAGG No 207, 8 November 2005

³³⁸ Section 6.4 amended by WAGG No 157, 18 September 2020

6.5 The amount determined in seeking to achieve the objective specified in section 6.4(a)(i) is a target, not a ceiling or a floor.

Recovery of deferred revenue

6.5A In this Chapter, “deferred revenue” means the amounts referred to in paragraphs 5.37A and 5.48A of the Amended *Proposed revisions* dated 24 December 2009 to the Western Power Network *access arrangement*, as approved by the *Authority’s* further final decision dated 19 January 2010, expressed in present value terms as at 30 June 2009 and in real dollar values as at 30 June 2009, being respectively:

- (a) \$64.5 million; and
- (b) \$484.2 million.³³⁹

6.5B An amount in respect of deferred revenue must be added to the *target revenue* for the Western Power Network for one or more *access arrangement periods* until the aggregate amount referred to in section 6.5A has been added.³⁴⁰

6.5C An amount added to the *target revenue* under section 6.5B must include an adjustment so that the deferral of the deferred revenue is financially neutral for the Electricity Networks Corporation, taking into account:

- (a) the time value of money; and
- (b) inflation.³⁴¹

6.5D The *Authority* must determine the amount to be added under section 6.5B in a given *access arrangement period*, provided that the *Authority* must approve an amount proposed to be added by the *Electricity Networks Corporation* in its *proposed revisions* if the amount to be recovered will not result in the forecast weighted average annual price change across all *reference tariffs* (as determined based on the *reference tariff change forecast* included in the *proposed revisions*, in nominal terms) being greater than zero for any *pricing year* of the *access arrangement period*.³⁴²

6.5E The total of all amounts added under section 6.5B (aggregated over all *access arrangement periods* for which such amounts are added) must equal:

- (a) the total amount of the deferred revenue; plus:
- (b) the sum of all adjustments under section 6.5C.³⁴³

Recovery of advanced metering communications infrastructure expenditure³⁴⁴

6.5F In this Chapter:

³³⁹ Section 6.5A inserted by WAGG No 182, 30 September 2011

³⁴⁰ Section 6.5B inserted by WAGG No 182, 30 September 2011

³⁴¹ Section 6.5C inserted by WAGG No 182, 30 September 2011

³⁴² Section 6.5D inserted by WAGG No 182, 30 September 2011; Section 6.5D amended by WAGG No 134, 30 July 2021

³⁴³ Section 6.5E inserted by WAGG No 182, 30 September 2011

³⁴⁴ Heading to section 6.5F inserted by WAGG No 157, 18 September 2020

- (a) “AMI communications expenditure” means all expenditure incurred prior to 30 June 2022 on and in relation to communications equipment (such as communication access points, modems and network interface cards), information technology systems and supporting equipment and services that are required to enable advanced metering functionality. For the purposes of this section, AMI communications expenditure is \$115.36 million (expressed in real dollar values as at 30 June 2017); and
- (b) “AMI recovery period” means a period of 10 years commencing on the next *revisions commencement date* following the date of the 2020 (No. 2) amendments.

{Note: The 2020 (No. 2) amendments came into effect on 18 September 2020.}³⁴⁵

6.5G An amount in respect of AMI communications expenditure must be added to the *target revenue* for the *Western Power Network* for each *access arrangement period* in the AMI recovery period until the full amount referred to in section 6.5F(a) (subject to any adjustments under section 6.5H) has been added.³⁴⁶

6.5H An amount added to the *target revenue* under section 6.5G must include an adjustment so that the deferral of the recovery of the AMI communications expenditure is financially neutral for the Electricity Networks Corporation, taking into account:

- (a) the time value of money; and
- (b) inflation.³⁴⁷

6.5I Subject to section 6.5J, the *Authority* must determine the amount to be added under section 6.5G in a given *access arrangement period* in the AMI recovery period.³⁴⁸

6.5J The total of all amounts added under section 6.5G over the AMI recovery period must equal:

- (a) the total amount of the AMI communications expenditure; plus:
- (b) the sum of all adjustments under section 6.5H.³⁴⁹

Target revenue may be adjusted for unforeseen events

6.6 If:

- (a) during the previous *access arrangement period*, a *service provider* incurred *capital-related costs* or *non-capital costs* as a result of a *force majeure event*; and
- (b) the *service provider* was unable to, or is unlikely to be able to, recover some or all of the costs (“**unrecovered costs**”) under its insurance policies; and

³⁴⁵ Section 6.5F inserted by WAGG No 157, 18 September 2020

³⁴⁶ Section 6.5G inserted by WAGG No 157, 18 September 2020

³⁴⁷ Section 6.5H inserted by WAGG No 157, 18 September 2020

³⁴⁸ Section 6.5I inserted by WAGG No 157, 18 September 2020

³⁴⁹ Section 6.5J inserted by WAGG No 157, 18 September 2020

- (c) at the time of the *force majeure event* the *service provider* had insurance to the standard of a *reasonable and prudent person* (as to the insurers and the type and level of insurance),

then subject to section 6.8 an amount may be added to the *target revenue* for the *covered network* for the next *access arrangement period* in respect of the unrecovered costs.

- 6.7 Nothing in section 6.6 requires the amount added under section 6.6 in respect of unrecovered costs to be equal to the amount of unrecovered costs.
- 6.8 An amount must not be added under section 6.6 in respect of *capital-related costs* or *non-capital costs*, to the extent that they exceed the costs which would have been incurred by a *service provider efficiently minimising costs*.

Target revenue may be adjusted for technical rule changes

- 6.9 If, during the previous *access arrangement period*, the *technical rules* for the *covered network* were amended under section 12.53 with the result that the *service provider*, in complying with the amended *technical rules*:

- (a) incurred *capital-related costs* or *non-capital costs*:
 - (i) for which no allowance was made in the *access arrangement*; and
 - (ii) which the *service provider* could not have reasonably foreseen at the time of the *approval* of the previous *access arrangement*;

and

- (b) did not incur *capital-related costs* or *non-capital costs* for which allowance was made in the *access arrangement*,

then subject to sections 6.10 to 6.12 an amount may be added to the *target revenue* for the *covered network* for the next *access arrangement period* in respect of the costs.

- 6.10 The amount (if any) to be added under section 6.9(a) must be positive, and the amount (if any) to be added under section 6.9(b) must be negative.
- 6.11 A positive amount must not be added under section 6.9(a) in respect of capital-related costs or *non-capital costs*, to the extent that they exceed the costs which would have been incurred by a *service provider efficiently minimising costs*.
- 6.12 A negative amount added under section 6.9(b) must have regard to the savings that would have been made by a *service provider efficiently minimising costs* even if the *service provider* did not actually achieve that level of savings.

'Investment adjustment mechanism' defined

- 6.13 An "**investment adjustment mechanism**" is a mechanism in an *access arrangement* detailing how any investment difference for the *access arrangement period* is to be treated by the *Authority* at the next *access arrangement review*.
- 6.14 In sections 6.13 and 6.16, "**investment difference**" for an *access arrangement period* is to be determined at the end of the *access arrangement period* by comparing:

- (a) the nature (including amount and timing) of actual *new facilities investment* which occurred during the *access arrangement period*;
- with
- (b) the nature (including amount and timing) of *forecast new facilities investment* which at the start of the *access arrangement period* was forecast to occur during the *access arrangement period*.

Requirement for an investment adjustment mechanism

- 6.15 If an *access arrangement* uses the form of *price control* described in section 6.2(a), then the *access arrangement* must contain an *investment adjustment mechanism*.
- 6.16 Without limiting the types of *investment adjustment mechanism* which may be contained in an *access arrangement*, an *investment adjustment mechanism* may provide that:
- (a) adjustments are to be made to the *target revenue* for the next *access arrangement* in respect of the full extent of any investment difference; or
 - (b) no adjustment is to be made to the *target revenue* for the next *access arrangement* in respect of any investment difference.
- 6.17 An *investment adjustment mechanism* must be:
- (a) sufficiently detailed and complete to enable the *Authority* to apply the *investment adjustment mechanism* at the next *access arrangement review*; and
 - (b) without limiting this Code, consistent with the *gain sharing mechanism* (if any) in the *access arrangement*;
 - (c) consistent with the *Code objective*.
- 6.18 An *investment adjustment mechanism* in an *access arrangement* applies at the next *access arrangement review*.

'Gain sharing mechanism' defined

- 6.19 A "gain sharing mechanism" is a mechanism:
- (a) in an *access arrangement* which the *Authority* must apply at the next *access arrangement review* to determine an amount to be included in the *target revenue* for one or more of the following *access arrangement periods*; and
 - (b) which operates as set out in sections 6.20 to 6.28.

Requirement for a gain sharing mechanism

- 6.20 An *access arrangement* must contain a *gain sharing mechanism* unless the *Authority* determines that a *gain sharing mechanism* is not necessary to achieve the objective in section 6.4(a)(ii).

Objectives for gain sharing mechanism

6.21 A *gain sharing mechanism* must have the objective of:

- (a) achieving an equitable allocation over time between *users* and the *service provider* of innovation and efficiency gains or losses relative to *efficiency and innovation benchmarks*; and
- (b) being objective, transparent, easy to administer and replicable from one *access arrangement* to the next; and
- (c) giving the *service provider* an incentive to reduce costs or otherwise improve productivity in a way that is neutral in its effect on the timing of such initiatives-; and

{For example, a *service provider* should not have an artificial incentive to defer an innovation until after an *access arrangement review*.}

- (d) minimising the effects of the mechanism on incentives for the implementation of *alternative options*.³⁵⁰

6.22 A *gain sharing mechanism* must be sufficiently detailed and complete to enable the *Authority* to apply the *gain sharing mechanism* at the next *access arrangement review*, including by prescribing the basis on which returns are to be determined for the purposes of section 6.23 and the basis on which losses are to be determined for the purposes of section 6.23A.³⁵¹

'Surplus' defined

6.23 A "**surplus**" has arisen to the extent that:

- (a) returns actually achieved by the *service provider* from the sale of *covered services* during the previous *access arrangement period*;
exceeded:
- (b) the level of returns from the sale of *covered services* which at the start of the *access arrangement period* was forecast to occur during the *access arrangement period*.³⁵²

'Deficit' defined³⁵³

6.23A A "**deficit**" has arisen to the extent that:

- (a) returns actually achieved by the *service provider* from the sale of *covered services* during the previous *access arrangement period*;
are less than:

³⁵⁰ Section 6.21 amended by WAGG No 157, 18 September 2020

³⁵¹ Section 6.22 amended by WAGG No 157, 18 September 2020

³⁵² Section 6.23 amended by WAGG No 157, 18 September 2020

³⁵³ Heading to section 6.23A inserted by WAGG No 157, 18 September 2020

- (b) the level of returns from the sale of *covered services* which at the start of the *access arrangement period* was forecast to occur during the *access arrangement period*.³⁵⁴

Prior surpluses may be retained

- 6.24 Subject to the provisions of any *investment adjustment mechanism*, the *service provider* may retain all of the *surplus* achieved in the previous *access arrangement period*, and accordingly, the *Authority* must not make an adjustment in order to recover the *surplus* achieved in the previous *access arrangement period* when approving the *price control* in a subsequent *access arrangement*.

Determining the above-benchmark surplus or below-benchmark deficit³⁵⁵

- 6.25 The *Authority* must determine how much (if any) of the *surplus* results from efficiency gains or innovation by the *service provider* in excess of the *efficiency and innovation benchmarks* in the previous *access arrangement* (“**above-benchmark surplus**”) or how much of the *deficit* results from a failure of the *service provider* to meet the *efficiency and innovation benchmarks* in the previous *access arrangement* (“**below-benchmark deficit**”).³⁵⁶
- 6.26 [Not used]³⁵⁷

Determining the increase or decrease to the target revenue³⁵⁸

- 6.27 The *Authority* must apply the *gain sharing mechanism* to determine how much (if anything) is to be added to or removed from the *target revenue* for one or more coming *access arrangement periods* under section 6.4(a)(ii) in order to enable the *service provider* to continue to share in the benefits of the efficiency gains or innovations which gave rise to the *above-benchmark surplus* or to penalise the *service provider* for the failure to meet the *efficiency and innovation benchmarks* which gave rise to the *below-benchmark deficit*.³⁵⁹
- 6.28 If the *Authority* makes a determination under section 6.27 to add or remove an amount to the *target revenue* in more than one *access arrangement period*, that determination binds the *Authority* when undertaking the *access arrangement review* at the beginning of each such *access arrangement period*.³⁶⁰

‘Service standards adjustment mechanism’ defined

- 6.29 A “*service standards adjustment mechanism*” is a mechanism in an *access arrangement* detailing how the *service provider’s* performance during the *access arrangement period* against the *service standard benchmarks* is to be treated by the *Authority* at the next *access arrangement review*.

³⁵⁴ Section 6.23A inserted by WAGG No 157, 18 September 2020

³⁵⁵ Heading to section 6.25 amended by WAGG No 157, 18 September 2020

³⁵⁶ Section 6.25 amended by WAGG No 157, 18 September 2020

³⁵⁷ Section 6.26 deleted by WAGG No 157, 18 September 2020

³⁵⁸ Heading to section 6.27 amended by WAGG No 157, 18 September 2020

³⁵⁹ Section 6.27 amended by WAGG No 157, 18 September 2020

³⁶⁰ Section 6.28 amended by WAGG No 157, 18 September 2020

Requirement for service standards adjustment mechanism

- 6.30 An *access arrangement* must contain a *service standards adjustment mechanism*.
- 6.31 A *service standards adjustment mechanism* must be:
- (a) sufficiently detailed and complete to enable the *Authority* to apply the *service standards adjustment mechanism* at the next *access arrangement review*; and
 - (b) consistent with the *Code objective*.
- 6.32 A *service standards adjustment mechanism* in an *access arrangement* applies at the next *access arrangement review*.

Demand management innovation allowance mechanism³⁶¹

- 6.32A An *access arrangement* must contain a *demand management innovation allowance mechanism*.³⁶²
- 6.32B The demand management innovation allowance is an annual, ex-ante allowance provided to *service providers* in the form of a fixed amount of additional revenue at the commencement of each *pricing year* of an *access arrangement period*.³⁶³
- 6.32C The objective of the *demand management innovation allowance mechanism* is to provide *service providers* with funding for research and development in demand management projects that have the potential to reduce long term network costs (“**demand management innovation allowance objective**”).³⁶⁴
- 6.32D The *Authority* must make and *publish* guidelines which must include a *demand management innovation allowance mechanism* consistent with the *demand management innovation allowance objective* and the information specified in section 6.32J.³⁶⁵
- 6.32E The *Authority* must determine the maximum amount of the allowance under the *demand management innovation allowance mechanism* for an *access arrangement period*, which must be calculated for each *pricing year in the access arrangement period*.³⁶⁶
- 6.32F Any amount of allowance not used by the *service provider* or not approved by the *Authority* over the *access arrangement period* must not be carried over into the subsequent *access arrangement period* or reduce the amount of the allowance for the subsequent *access arrangement period*.³⁶⁷

³⁶¹ Heading to section 6.32A inserted by WAGG No 157, 18 September 2020

³⁶² Section 6.32A inserted by WAGG No 157, 18 September 2020

³⁶³ Section 6.32B inserted by WAGG No 157, 18 September 2020

³⁶⁴ Section 6.32C inserted by WAGG No 157, 18 September 2020

³⁶⁵ Section 6.32D inserted by WAGG No 157, 18 September 2020

³⁶⁶ Section 6.32E inserted by WAGG No 157, 18 September 2020

³⁶⁷ Section 6.32F inserted by WAGG No 157, 18 September 2020

- 6.32G In developing and applying any *demand management innovation allowance mechanism*, the *Authority* must take into account the following:
- (a) the mechanism should be applied in a manner that contributes to the achievement of the *demand management innovation allowance objective*;
 - (b) projects the subject of the allowance should:
 - (i) have the potential to reduce long term network costs; and
 - (ii) be innovative and not otherwise efficient and prudent *alternative options* that a *service provider* should have provided for in its *proposed access arrangement*; and
 - (iii) comply with the *demand management innovation allowance guidelines*
 - (c) the level of the allowance:
 - (i) should be reasonable, considering the long term benefit to *consumers*; and
 - (ii) should only provide funding that is not available from any other source; and
 - (iii) may vary over time; and
 - (d) the allowance may fund projects which occur over a period longer than an *access arrangement period*.³⁶⁸
- 6.32H A *service provider* must submit a *compliance report* to the *Authority* in accordance with the *demand management innovation allowance guidelines*.³⁶⁹
- 6.32I The *Authority* must *publish* the *compliance report*.³⁷⁰
- 6.32J The *demand management innovation allowance guidelines* must include the following:
- (a) the eligibility criteria to be applied by the *Authority* in determining whether a project is entitled to receive the allowance;
 - (b) the process, manner and form by which a *service provider* may apply to the *Authority* for up-front consideration of a project;
 - (c) the information required to be included in a *compliance report* which must include:
 - (i) the amount of the allowance:
 - A. incurred by the *service provider* to date as at the end of that *pricing year*;

³⁶⁸ Section 6.32G inserted by WAGG No 157, 18 September 2020

³⁶⁹ Section 6.32H inserted by WAGG No 157, 18 September 2020

³⁷⁰ Section 6.32I inserted by WAGG No 157, 18 September 2020

- B. incurred by the *service provider* in that *pricing year*; and
- C. expected to be incurred by the *service provider* in total over the duration of the eligible project;
- (ii) a list and description of each project on which the allowance was spent;
- (iii) a summary of how and why each project complies with the eligibility criteria;
- (iv) the results of each project; and
- (d) any requirements for the preparation, lodgement and form of a *compliance report*.³⁷¹

6.32K The *Authority* must consult the public in accordance with Appendix 7 before making and *publishing* the *demand management innovation allowance guidelines*.³⁷²

Authority may make a determination of excluded services for a covered network

6.33 The *Authority* may from time to time make and *publish* a determination (which subject to section 6.37 has effect for a specified *covered network*) of which *services* being provided by means of the *covered network* are *excluded services*.

6.34 If a determination has effect under section 6.33, then despite any existing *framework and approach*, the determination is binding in respect of the *approval* or *review* of *price control* in an *access arrangement* for the *covered network*.³⁷³

6.35 Without limiting section 6.33, a *service provider* or a *user* may at any time request the *Authority* to determine under section 6.33 that one or more *services* provided by means of the *service provider's covered network* are *excluded services*.³⁷⁴

6.36 Before making a determination under section 6.33, the *Authority* must consult the public in accordance with Appendix 7.

6.37 A determination under section 6.33:

- (a) may be revoked or amended by a further determination under section 6.33; and
- (b) has effect until revoked by a further determination; and
- (c) does not have effect in relation to the *approval* or *review*, as applicable, of an *access arrangement* if the determination is *published* less than 3 months before the *submission deadline* or *revisions submission date*, as applicable.³⁷⁵

³⁷¹ Section 6.32J inserted by WAGG No 157, 18 September 2020

³⁷² Section 6.32K inserted by WAGG No 157, 18 September 2020

³⁷³ Section 6.34 amended by WAGG No 157, 18 September 2020

³⁷⁴ Section 6.35 amended by WAGG No 157, 18 September 2020

³⁷⁵ Section 6.37 amended by WAGG No 157, 18 September 2020

{Note: The intention of section 6.37(c) is to ensure that the goalposts are not set or shifted too late in the process.}

Tariff equalisation contributions may be added to target revenue³⁷⁶

6.37A If the *service provider* for the *Western Power Network* is or will be required, by a notice made under section 129D(2) of the Act, to pay a tariff equalization contribution into the Tariff Equalization Fund during an *access arrangement period*, then an amount may be added to the *target revenue* for the *covered network* for the *access arrangement period*, which amount—

- (a) must not exceed the total of the tariff equalisation contributions which are or will be required to be paid under the notice, including any amount that was payable or paid before the commencement of the *access arrangement period*; and
- (b) must be separately identified as being under this section 6.37A.³⁷⁷

{Note: Section 7.12 deals with how the amount added under this section 6.37A is to be allocated as *tariff* components.}³⁷⁸

Subchapter 6.2 – Calculation of Service provider’s Costs

When this Subchapter 6.2 applies

6.38 The following provisions, namely:

- (a) sections 6.40 to 6.42 (*non-capital costs*); and
- (b) sections 6.43 to 6.70 (*capital-related costs*),

apply in relation to an *access arrangement* only to the extent that, in determining *target revenue*, it is necessary to calculate part or all of the relevant component of the *service provider’s approved total costs*.

6.39 Nothing in section 6.38:

- (a) limits the operation of a section of this Code or a provision of an *access arrangement* which refers to a provision of this Subchapter 6.2 for a purpose other than calculating the *service provider’s approved total costs*; or
- (b) requires an *access arrangement* to determine *target revenue* in a manner which requires the calculation of, or of any component of, the *service provider’s approved total costs*.

{Note: Each element of the *price control*, as with each other component of an *access arrangement*, must be proposed by a

³⁷⁶ Heading to section 6.37A inserted by WAGG No 207, 8 November 2005

³⁷⁷ Section 6.37A amended by WAGG No 206, 8 December 2006; Section 6.37A amended by WAGG No 180, 22 October 2008; Section 6.37A amended by WAGG No 206, 8 December 2006; Section 6.37A amended by WAGG No 180, 22 October 2008

³⁷⁸ Note to section 6.37A inserted by WAGG No 207, 8 November 2005

service provider in its *proposed access arrangement* submitted under section 4.1. Under section 4.28, the *Authority* must approve the *access arrangement*, including the *price control*, if the *Authority* considers that it meets the applicable objectives.}

Non-capital costs

6.40 Subject to section 6.41, the *non-capital costs* component of *approved total costs* for a *covered network* must include only those *non-capital costs* which would be incurred by a *service provider* *efficiently minimising costs*.

6.41 Where, in order to maximise the *net benefit after considering alternative options*, a *service provider* pursues an *alternative option* in order to provide *covered services*, the *non-capital costs* component of *approved total costs* for a *covered network* may include *non-capital costs* incurred in relation to the *alternative option* (“**alternative option non-capital costs**”) if:

- (a) the *alternative option non-capital costs* do not exceed the amount of *alternative option non-capital costs* that would be incurred by a *service provider* *efficiently minimising costs*; and
- (b) at least one of the following conditions is satisfied:
 - (i) the *additional revenue* for the *alternative option* is expected to at least recover the *alternative option non-capital costs*; or
 - (ii) the *alternative option* provides a *net benefit* in the *covered network* over a reasonable period of time that justifies higher *reference tariffs*; or
 - (iii) the *alternative option* is necessary to maintain the safety or reliability of the *covered network* or its ability to provide contracted *covered services*.³⁷⁹

{Note: The *service provider* may adopt an *alternative option* either due to the operation of the *regulatory test*, or due to the *service provider*'s own processes in advance of the *regulatory test*.}

6.42 For the purposes of section 6.41(b)(i) “**additional revenue**” for an *alternative option* means:

- (a) the present value (calculated at the *rate of return* over a reasonable period) of the increased *tariff* income reasonably anticipated to arise from the increased sale of *covered services* on the network to one or more *users* (where “increased sale of *covered services*” means sale of *covered services* which would not have occurred had the *alternative option* not been undertaken);

minus

- (b) the present value (calculated at the *rate of return* over the same period) of the best reasonable forecast of the increase in *non-capital costs* (other than

³⁷⁹ Section 6.41 amended by WAGG No 180, 22 October 2008

alternative option non-capital costs) directly attributable to the increased sale of the *covered services* (being the *covered services* referred to in the expression “increased sale of *covered services*” in section 6.42(a)),³⁸⁰

where the “**rate of return**” is a rate of return determined by the *Authority* in accordance with the *Code objective* and in a manner consistent with this Chapter 6, which may be the rate of return most recently approved by the *Authority* for use in the *price control* for the *covered network* under this Chapter 6.

Capital-related costs

- 6.43 The *capital-related costs* component of *approved total costs* for a *covered network* must be calculated by:
- (a) determining a *capital base* under sections 6.44 to 6.63; and
 - (b) calculating a return on the *capital base* of the *covered network* by applying the *weighted average cost of capital* calculated under section 6.64 to the *capital base*; and
 - (c) calculating the depreciation of the *capital base* under section 6.70.

Determining the capital base

- 6.44 The *capital base* for the *covered network*:
- (a) must be determined at the start of each *access arrangement period*; and
 - (b) may be determined from time to time by the *service provider* during an *access arrangement period*.
- 6.45 If the *service provider* determines the *capital base* under section 6.44(b) during an *access arrangement period*, then:
- (a) the determination does not affect a subsequent determination under section 6.44(a); and
 - (b) the determination does not affect the *target revenue* or the determination of *tariffs* for the *access arrangement period*.

Capital base for the start of the first access arrangement period

- 6.46 For the start of the *first access arrangement period*, the *capital base* for a *covered network* must be determined using one of the following asset valuation methodologies:
- (a) depreciated optimised replacement cost (“**DORC**”); or
 - (b) optimised deprival value (“**ODV**”).
- 6.47 If under section 6.46 the ODV asset valuation methodology is used to determine the *capital base* at the start of the *first access arrangement period* for the *Western Power Network*, the valuation must utilise, to the extent possible, any ministerial valuation

³⁸⁰ Section 6.42 amended by WAGG No 180, 22 October 2008

under section 119 of the Act of the *network assets* which comprise the *covered network*.³⁸¹

{Note: Under section 119 of the Act the Minister may commission a DORC valuation of existing network facilities, and if the Minister does so, in certain circumstances, the valuation provided to the Minister is taken to be the DORC valuation of the facilities.}

Capital base for the start of subsequent access arrangement periods

6.48 For the start of each *access arrangement period* other than the *first access arrangement period*, the *capital base* for a *covered network* must be determined in a manner which is consistent with the *Code objective*.

{Note: A number of options are available in relation to the determination of the *capital base* at the start of an *access arrangement period*, including:

- rolling forward the *capital base* from the previous *access arrangement period* applying benchmark indexation such as the *consumer price index* or an asset specific index, plus *new facilities investment* incurred during the previous *access arrangement period*, less depreciation and *redundant capital* etc; and
- valuation or revaluation of the *capital base* using an appropriate methodology such as the Depreciated Optimised Replacement Cost or Optimised Deprival Value methodology.}

Capital base must not include forecast new facilities investment

6.49 Subject to section 6.50, the *capital base* for a *covered network* must not include any amount in respect of *forecast new facilities investment*.

6.50 For the start of each *access arrangement period*, the *capital base* for a *covered network* may include *forecast new facilities investment* which:

- (a) has not yet occurred but is forecast to occur before the *access arrangement start date*; and
- (b) at the time of inclusion is reasonably expected to satisfy the test in section 6.51A when made.³⁸²

{Note: *Forecast new facilities investment* in a *proposed access arrangement* may actually have occurred by the time of the *access arrangement start date*. Under section 6.50, such *new facilities investment* may be included in the *capital base* for a *covered network*.}

6.51 For the purposes of section 6.4(a)(i) and subject to section 6.49, the forward-looking and efficient costs of providing *covered services* may include costs in relation to *forecast new facilities investment* for the *access arrangement period* which at the time

³⁸¹ Section 6.47 amended by WAGG No 180, 22 October 2008

³⁸² Section 6.50 amended by WAGG No 152, 1 September 2006; Section 6.50 amended by WAGG No 180, 22 October 2008

of inclusion is reasonably expected to satisfy the test in section 6.51A when the *forecast new facilities investment* is forecast to be made.³⁸³

Test for adding new facilities investment to the capital base³⁸⁴

6.51A *New facilities investment* may be added to the *capital base* if:

- (a) it satisfies the *new facilities investment test*; or
- (b) the *Authority* otherwise approves it being added to the *capital base* if:
 - (i) it has been, or is expected to be, the subject of a *contribution*; and
 - (ii) it meets the requirements of section 6.52(a); and
 - (iii) the *access arrangement* contains a mechanism designed to ensure that there is no double recovery of costs as a result of the addition.³⁸⁵

New facilities investment test

[not used]³⁸⁶

6.52 *New facilities investment* satisfies the *new facilities investment test* if:³⁸⁷

- (a) the *new facilities investment* does not exceed the amount that would be invested by a *service provider efficiently minimising costs*, having regard, without limitation, to:
 - (i) whether the *new facility* exhibits economies of scale or scope and the increments in which capacity can be added; and
 - (ii) whether the lowest sustainable cost of providing the *covered services* forecast to be sold over a reasonable period may require the installation of a *new facility* with capacity sufficient to meet the forecast sales; and
 - (iii) if it is not a *priority project*, *alternative options* to the *new facility* (including the capital costs and *non-capital costs* that would be incurred in respect of that *alternative option*);

and

- (b) one or more of the following conditions is satisfied:
 - (i) either:

³⁸³ Section 6.51 amended by WAGG No 152, 1 September 2006; Section 6.51 amended by WAGG No 180, 22 October 2008

³⁸⁴ Heading to section 6.51A inserted by WAGG No 180, 22 October 2008

³⁸⁵ Section 6.51A inserted by WAGG No 180, 22 October 2008

³⁸⁶ Note before section 6.52 inserted by WAGG No 152, 1 September 2006; Note before section 6.52 deleted by WAGG No 180, 22 October 2008

³⁸⁷ Section 6.52 amended by WAGG No 180, 22 October 2008

- A. the *anticipated incremental revenue* for the *new facility* is expected to at least recover the *new facilities investment*; or
 - B. if a *modified test* has been approved under section 6.53 and the *new facilities investment* is below the *test application threshold* – the *modified test* is satisfied;
- or
- (ii) the *new facility* provides a *net benefit* in the *covered network* over a reasonable period of time that justifies the *approval* of higher *reference tariffs*; or
 - (iii) the *new facility* is necessary to maintain the safety or reliability of the *covered network* or its ability to provide contracted *covered services*; or
 - (iv) the *new facility* is in respect of a *priority project*.³⁸⁸
- 6.53 The *Authority* may, in an *access arrangement*, approve a “**modified test**” for the purposes of section 6.52(b)(i)B to apply to a *covered network* in respect of *new facilities investment* below the *test application threshold* where:
- (a) the *service provider* has proposed a *modified test* to apply in respect of new facilities investment below a proposed *test application threshold*; and
 - (b) the *Authority* determines that approving the *access arrangement* with the proposed *modified test*:
 - (i) would be efficient in that the advantages of approving the proposed *modified test* would outweigh the disadvantages; and
 - (ii) would promote the achievement of the *Code objective*.
- 6.54 In making a determination under section 6.52 the *Authority* must have regard to:
- (a) if the *new facilities investment* is in respect of a *priority project*, for the purposes of considering the amount invested or recovered under section 6.52(a), the unit costs of the *service provider’s actual new facilities investment* only; and³⁸⁹
 - (b) whether the *new facilities investment* was required by a *written law* or a *statutory instrument*.
- 6.55 Section 6.54 does not limit the matters to which regard must or may be had in making a determination under section 6.52.
- 6.55A If the *Authority* makes a determination under section 6.52, it must provide *reasons* for its determination in its *draft decision* and *final decision*, and such *reasons* must

³⁸⁸ Section 6.52 amended by WAGG No 157, 18 September 2020

³⁸⁹ Section 6.54 amended by WAGG No 157, 18 September 2020

provide detail on how the *Authority* applied the guidelines referred to in section 6.56 in making its determination.³⁹⁰

Authority must make guidelines³⁹¹

6.56 The *Authority* must make and *publish* guidelines that provide guidance as to the factors the *Authority* proposes to consider in making a determination under section 6.52 and must consult the public in accordance with Appendix 7 before making and *publishing* any guidelines under this section.³⁹²

Recoverable portion

6.57 If only part of any *new facilities investment* satisfies the *new facilities investment test*, that part ("**recoverable portion**") may be added to the *capital base*.

Speculative investment

6.58 The "**speculative investment amount**" (if any) for a *new facility* at any time is equal to:

- (a) the *new facilities investment*; minus
- (b) any *recoverable portion*; minus:
- (c) any amount for which a *contribution* has been, or is to be, provided to the *service provider*;³⁹³

minus:

- (d) any part of the *speculative investment amount* for the *new facility* previously added to the *capital base* under section 6.60.

6.59 If the calculation in section 6.58 produces a negative result, the *speculative investment amount* is zero.

6.60 If:

- (a) a *speculative investment amount* was created for a *new facility* at a time; and
- (b) a determination is being made under section 6.44 at a later time,

then any part of the *speculative investment amount* which satisfies the *new facilities investment test* at the later time may be added to the *capital base*.

{Note: *Reasons* for the investment satisfying the *new facilities investment test* at the later time could include a change in the type or volume of *covered*

³⁹⁰ Section 6.55A inserted by WAGG No 157, 18 September 2020

³⁹¹ Heading to section 6.56 deleted by WAGG No 207, 8 November 2005; Heading to section 6.56 inserted by WAGG No 152, 1 September 2006; Heading to section 6.56 deleted by WAGG No 180, 22 October 2008; Heading to section 6.56 inserted by WAGG No 157, 18 September 2020

³⁹² Section 6.56 deleted by WAGG No 207, 8 November 2005; Section 6.56 inserted by WAGG No 152, 1 September 2006; Section 6.56 deleted by WAGG No 180, 22 October 2008; Section 6.56 inserted by WAGG No 157, 18 September 2020

³⁹³ Section 6.58 amended by WAGG No 180, 22 October 2008

services provided using the new facility from the circumstances prevailing at the original time.}

Redundant capital

6.61 Subject to section 6.62, the *Authority* may in relation to a determination under section 6.44(a) require an amount (“**redundant capital**”) to be removed from the *capital base* to the extent (if any) necessary to ensure that *network assets* which have ceased to contribute in any material way to the provision of *covered services* are not included in the *capital base*.

6.62 Before requiring a removal under section 6.61, the *Authority* must have regard to:

- (a) whether the *service provider* was *efficiently minimising costs* when it developed, constructed or acquired the *network assets*; and
- (b) the uncertainty such a removal may cause and the effect which any such uncertainty may have on the *service provider, users and applicants*; and
- (c) whether the cause of the *network assets* ceasing to contribute in any material way to the provision of *covered services* was the *application of a written law or a statutory instrument*; and
- (d) whether the *service provider* was compelled to develop, construct or acquire the *network assets*:
 - (i) by an award by the *arbitrator*, or
 - (ii) because of the *application of a written law or a statutory instrument*; and
- (e) whether the depreciation of the *network assets* should be accelerated instead of or in addition to a *redundant capital* amount being removed from the *capital base* under section 6.61.

6.63 If the *Authority* requires a removal under section 6.61, then when making other determinations under this Chapter 6 the *Authority* may have regard to the removal.

{Examples of such other determinations include approving a *weighted average cost of capital* and assessing the economic life of assets.}

Calculating weighted average cost of capital

6.64 An *access arrangement* must set out the *weighted average cost of capital* for a *covered network*, which:

- (a) if a determination has effect under section 6.65:
 - (i) for the *first access arrangement* for the *Western Power Network*³⁹⁴— may use any methodology (which may be formulated without any reference to the determination under section 6.65) but, in determining whether the methodology used is consistent with this

³⁹⁴ Section 6.64 amended by WAGG No 180, 22 October 2008

Chapter 6 and the *Code objective*, regard must be had to the determination under section 6.65; and

- (ii) otherwise — must use the methodology in the determination under section 6.65 unless the *service provider* can demonstrate that an *access arrangement* containing an alternative methodology would better achieve the objectives set out in section 6.64 and the *Code objective*,

and

- (b) if a determination does not have effect under section 6.65 – must be calculated in a manner consistent with section 6.66.

Authority may make a determination of a methodology for calculation of weighted average cost of capital

6.65 The *Authority* may from time to time make and *publish* a determination (which subject to section 6.68 has effect for all *covered networks* under this Code) of the preferred methodology for calculating the *weighted average cost of capital* in *access arrangements*.

6.66 A determination under section 6.65:

- (a) must represent an effective means of achieving the *Code objective* and the objectives in section 6.4; and
- (b) must be based on an accepted financial model such as the Capital Asset Pricing Model.

6.67 Before making a determination under section 6.65, the *Authority* must consult the public in accordance with Appendix 7.

6.68 A determination under section 6.65:

- (a) may be revoked or amended by a further determination under section 6.65; and
- (b) has effect for the period specified in the determination, which must not be more than 5 years, unless earlier revoked by a further determination; and
- (c) subject to section 6.69, does not have effect in relation to the *approval* or *review*, as applicable, of an *access arrangement* if the determination is *published* less than 6 months before the *submission deadline* or *revisions submission date*, as applicable.³⁹⁵

{Note: The intention of section 6.68(c) is to ensure that the goalposts are not set or shifted too late in the process.}

³⁹⁵ Section 6.68 amended by WAGG No 157, 18 September 2020

- 6.69 For the *Western Power Network*, a determination under section 6.65 has effect in relation to the *approval* of the *first access arrangement* if it is *published* at least 3 months before the *submission deadline*.³⁹⁶

Depreciation

- 6.70 An *access arrangement* must provide for the depreciation of the *network assets* comprising the *capital base*, including the economic lives of each *network asset* or group of *network assets*, the depreciation method to be applied to each *network asset* or group of *network assets* and the circumstances in which the depreciation of a *network asset* may be accelerated.

Consultation with AEMO³⁹⁷

- 6.70A Where a *service provider* is required under this Code to consider changes in costs and benefits for participants in the *Wholesale Electricity Market* (including where required to do so pursuant to the *guidelines* published under section 6A.6(a)), the *service provider* must consult with AEMO in good faith in respect of such changes in costs and benefits.³⁹⁸
- 6.70B Clause 6.70A only applies in respect of the *SWIS*.³⁹⁹

Subchapter 6.3 – Service provider may seek approval for costs

Approval for new facilities investment

- 6.71 A *service provider* may at any time apply to the *Authority* for the *Authority* to determine whether:
- (a) actual *new facilities investment* made by the *service provider* meets the test in section 6.51A; or
 - (b) *forecast new facilities investment* proposed by the *service provider* is forecast to meet the test in section 6.51A.⁴⁰⁰
- 6.72 If an *application* is made to the *Authority* under section 6.71, then subject to section 6.75 the *Authority* must make and *publish* a determination (subject to such conditions as the *Authority* may consider appropriate) within a reasonable time.
- 6.73 Before making a determination under section 6.72, the *Authority* must consult the public in accordance with Appendix 7.
- 6.74 The effect of a determination under section 6.72 is to bind the *Authority* when it approves *proposed revisions*, but in the case of *forecast new facilities investment* under section 6.71(b) the *Authority* is only bound if the *new facilities investment* has proceeded as proposed.

³⁹⁶ Section 6.69 amended by WAGG No 180, 22 October 2008

³⁹⁷ Heading to section 6.70A inserted by WAGG No 157, 18 September 2020

³⁹⁸ Section 6.70A inserted by WAGG No 157, 18 September 2020

³⁹⁹ Section 6.70B inserted by WAGG No 157, 18 September 2020

⁴⁰⁰ Section 6.71 amended by WAGG No 180, 22 October 2008

- 6.75 The *Authority*:
- (a) must make a determination under section 6.72 if the actual or *forecast new facilities investment* is equal to or greater than the amount of \$15 million (*CPI adjusted*); and
 - (b) may make a determination under section 6.72 if the actual or *forecast new facilities investment* is less than the amount of \$15 million (*CPI adjusted*).

Approval for non-capital costs

- 6.76 A *service provider* may at any time apply to the *Authority* for the *Authority* to determine whether:
- (a) actual *non-capital costs* incurred by the *service provider* meet the requirements of section 6.40; or
 - (b) forecast *non-capital costs* proposed to be incurred by the *service provider* is forecast to meet the requirements of section 6.40.⁴⁰¹
- 6.77 If an *application* is made to the *Authority* under section 6.76, then subject to section 6.80 the *Authority* must make and *publish* a determination (subject to such conditions as the *Authority* may consider appropriate) within 70 *business days*.⁴⁰²
- 6.77A The *Authority* may extend the deadline in section 6.77 if, before the day on which the time would otherwise have expired, it *publishes* notice of, and *reasons* for, its decision to extend the deadline.⁴⁰³
- 6.78 Before making any determination under section 6.77, the *Authority* must consult the public.⁴⁰⁴
- 6.79 The effect of a determination under section 6.77 is to bind the *Authority* when it approves *proposed revisions*, but in the case of forecast *non-capital costs* under section 6.76(b) the *Authority* is only bound if the actual *non-capital costs* incurred are within 5% of the forecast *non-capital costs* proposed to be incurred.⁴⁰⁵
- 6.80 The *Authority*:
- (a) must make a determination under section 6.77 if the actual or forecast *non-capital costs* are equal to or greater than the amount of \$1.5 million (*CPI adjusted*); and
 - (b) may make a determination under section 6.77 if the actual or forecast *non-capital costs* are less than the amount of \$1.5 million (*CPI adjusted*).

⁴⁰¹ Section 6.76 amended by WAGG No 180, 22 October 2008

⁴⁰² Section 6.77 amended by WAGG No 157, 18 September 2020

⁴⁰³ Section 6.77A inserted by WAGG No 157, 18 September 2020

⁴⁰⁴ Section 6.78 amended by WAGG No 157, 18 September 2020

⁴⁰⁵ Section 6.79 amended by WAGG No 157, 18 September 2020

Approval for access reform costs⁴⁰⁶

- 6.81 A *service provider* may apply to the *Authority* for the *Authority* to determine the amount that the *service provider* may recover in respect of *access reform costs* incurred by the *service provider*.⁴⁰⁷
- 6.82 The *Authority* must determine that the *service provider* may recover the total *access reform costs* incurred by the *service provider* except to the extent that it considers that any *access reform costs* incurred by the *service provider* have not been incurred by the *service provider* acting efficiently.⁴⁰⁸
- 6.83 Any amount determined by the *Authority* under section 6.81 is deemed to be added to the *non-capital costs* component of *approved total costs* for a *covered network* in the relevant *access arrangement*.⁴⁰⁹

Subchapter 6.4 – Multi-function assets⁴¹⁰

- 6.84 If a *network asset* is used to provide *services* other than *covered services* (a “**multi-function asset**”), the *Authority* must, in accordance with the *multi-function asset principles*, in an *access arrangement* for an *access arrangement period*, reduce the *target revenue* for the *service provider* for a *pricing year* within that *access arrangement period* by an amount equal to 30% of the *net incremental revenue*.⁴¹¹
- 6.85 In making a decision under section 6.84, the *Authority* must have regard to the *multi-function asset policy* and the *multi-function asset guidelines*.⁴¹²
- 6.86 The *multi-function asset principles* are as follows:
- (a) the *service provider* should be encouraged to use assets that provide *covered services* for the provision of other kinds of *services* where that use is efficient and does not materially prejudice the provision of *covered services*;
 - (b) a *multi-function asset* revenue reduction should not be dependent on the *service provider* deriving a positive commercial outcome from the use of the asset other than for *covered services*;
 - (c) a *multi-function asset* revenue reduction should be applied where the use of the asset other than for *covered services* is material;
 - (d) regard should be had to the manner in which costs of *multi-function assets* have been recovered or revenues of *multi-function assets* have been reduced in respect of the relevant asset in the past and the *reasons* for adopting that manner of reduction; and

⁴⁰⁶ Heading to section 6.81 inserted by WAGG No 157, 18 September 2020

⁴⁰⁷ Section 6.81 inserted by WAGG No 157, 18 September 2020

⁴⁰⁸ Section 6.82 inserted by WAGG No 157, 18 September 2020

⁴⁰⁹ Section 6.83 inserted by WAGG No 157, 18 September 2020

⁴¹⁰ Heading to section 6.84 inserted by WAGG No 157, 18 September 2020

⁴¹¹ Section 6.84 inserted by WAGG No 157, 18 September 2020

⁴¹² Section 6.85 inserted by WAGG No 157, 18 September 2020

- (e) any reduction effected under section 6.84 should be compatible with other incentives provided under this Code.⁴¹³
- 6.87 For the purpose of section 6.86(c), the use of a *multi-function asset* other than for *covered services* is material if the *net incremental revenue* derived from the use of all *multi-function assets* in a *pricing year* is greater than \$1 million (*CPI adjusted*).⁴¹⁴
- 6.88 The *Authority* must make and *publish* guidelines setting out the approach the *Authority* proposes to take in applying the *multi-function asset principles* (which may include a methodology that the *Authority* proposes to use to determine reductions for the purposes of section 6.84) and must consult the public in accordance with Appendix 7 before making and *publishing* the *multi-function asset guidelines*.⁴¹⁵

⁴¹³ Section 6.86 inserted by WAGG No 157, 18 September 2020

⁴¹⁴ Section 6.87 inserted by WAGG No 157, 18 September 2020

⁴¹⁵ Section 6.88 inserted by WAGG No 157, 18 September 2020

Chapter 6A — Alternative options⁴¹⁶

Network Opportunity Map⁴¹⁷

6A.1 A *service provider* must *publish* and update a network opportunity map (“*network opportunity map*”) by no later than 1 October each year.⁴¹⁸

6A.2 A *network opportunity map* must include:

- (a) a description of the *service provider’s network*;
- (b) a description of its operating environment;
- (c) the methodologies used in preparing the *network opportunity map*, including methodologies used to identify transmission and distribution system *constraints* and any assumptions applied;
- (d) analysis and explanation of any aspects of forecasts and information provided in the *network opportunity map* that have changed significantly from previous forecasts and information provided in the preceding year;
- (e) forecasts for the 5 year forward planning period, including at least:
 - (i) a description of the forecasting methodology used, sources of input information, and the assumptions applied; and
 - (ii) load forecasts for zone substations;
 - (iii) to the extent practicable, primary distribution feeders, having regard to:
 - A. the number of customer connections;
 - B. energy consumption; and
 - C. estimated total output of known embedded generating units,including, where applicable, for each item any capacity or voltage constraints on distribution feeders where applicable including estimated constraint periods; and
- (f) forecasts of future zone sub-stations including:
 - (i) location;

⁴¹⁶ Heading inserted by WAGG No 157, 18 September 2020

⁴¹⁷ Heading to section 6A.1 inserted by WAGG No 157, 18 September 2020

⁴¹⁸ Section 6A.1 inserted by WAGG No 157, 18 September 2020

- (ii) future level of output, consumption or power flow (in MW) of a *generating plant or load*; and
 - (iii) proposed commissioning time (estimate of month and year);
- (g) a description of any factors that may have a material impact on the *service provider's network*, including factors affecting:
 - (i) fault levels;
 - (ii) voltage levels;
 - (iii) power system security requirements; and
 - (iv) the quality of supply to other *users* (if relevant);
- (h) the annual deferred value for *augmentations* for the next 5 years;
- (i) for all *network asset* retirements and for all *network asset* de-ratings that, in each case, would result in transmission and distribution system *constraints*, that are planned over the forward planning period, the following information in sufficient detail relative to the size or significance of the *network asset*:
 - (i) a description of the *network asset*, including location;
 - (ii) the reasons, including methodologies and assumptions used by the *service provider*, for deciding that it is necessary or prudent for the *network asset* to be retired or de-rated, taking into account factors such as the condition of the *network asset*;
 - (iii) the date from which the *service provider* proposes that the *network asset* will be retired or de-rated; and
 - (iv) if the date to retire or de-rate the *network asset* has changed since the previous *network opportunity map*, an explanation of why this has occurred;
- (j) a high-level summary of each:
 - (i) *major augmentation* for which the *regulatory test* has been completed in the preceding year or is in progress; and
 - (ii) *priority project*;
- (k) a summary of all *committed* investments to be carried out within the forward planning period with an estimated capital cost of \$2 million or more that are to address a *network* issue, including:
 - (i) a brief description of the investment, including its purpose, its location, the estimated capital cost of the investment and an estimate of the date (month and year) the investment is expected to become operational;
 - (ii) where there are reasonable *alternative options* to that investment, a brief description of the *alternative options* considered by the *service*

provider in deciding on the preferred investment, including an explanation of the ranking of these options to the investment;

- (l) information on the *service provider's* asset management approach, including:
 - (i) a summary of any asset management strategy employed by the *service provider*;
 - (ii) an explanation of how the *service provider* takes into account the cost of line losses when developing and implementing its asset management and investment strategy;
 - (iii) a summary of any issues that may impact on the transmission and distribution system *constraints* identified in the *network opportunity map* that has been identified through carrying out asset management;
 - (iv) information about where further information on the asset management strategy and methodology adopted by the *service provider* may be obtained.⁴¹⁹

Alternative options strategy and vendor register⁴²⁰

6A.3 The *service provider* must develop a strategy ("**alternative options strategy**") for:

- (a) engaging with providers of *alternative options*; and
- (b) considering *alternative options*.⁴²¹

6A.4 The *service provider* must:

- (a) engage with providers of *alternative options* and consider *alternative options* for addressing transmission and distribution system *constraints* in accordance with its *alternative options strategy*;
- (b) document its *alternative options strategy* which must include the information specified in section 6A.5;
- (c) review and *publish* a revised *alternative options strategy* by no later than 1 October, which must be updated at least once every 2 years;
- (d) establish and maintain a vendor register by which parties can register their interest in being notified of developments relating to *network* planning and expansion; and
- (e) negotiate in good faith with a provider of *alternative options* regarding the terms for an alternative option service contract based on the *model alternative option service contract*.⁴²²

⁴¹⁹ Section 6A.2 inserted by WAGG No 157, 18 September 2020

⁴²⁰ Heading to section 6A.3 inserted by WAGG No 157, 18 September 2020

⁴²¹ Section 6A.3 inserted by WAGG No 157, 18 September 2020

⁴²² Section 6A.4 inserted by WAGG No 157, 18 September 2020

6A.5 The *service provider's alternative options strategy* must include the following information:

- (a) a description of how the *service provider* will investigate, develop, assess and report on potential *alternative options* including references to the *network opportunity map* (if relevant);
- (b) a description of the *service provider's* process to engage and consult with potential providers of *alternative options* to determine their level of interest and ability to participate in the development process for potential *alternative options*;
- (c) an outline of the process followed by the *service provider* when negotiating with providers of *alternative options* to further develop potential *alternative options*;
- (d) an outline of the information a provider of *alternative options* is to include in a proposal for *alternative options*, including, where possible, an example of a best practice *alternative options* proposal;
- (e) an outline of the criteria that will be applied by the *service provider* in evaluating *alternative options* proposals including by reference to the *network opportunity map* (if relevant);
- (f) an outline of the principles that the *service provider* considers in developing the payment levels for *alternative options*;
- (g) a reference to any applicable incentive schemes for the implementation of *alternative options* and whether any specific criteria is applied by the *service provider* in its application and assessment of the scheme;
- (h) worked examples to support the description of how the *service provider* will assess potential *alternative options* in accordance with paragraph (a) above;
- (i) a hyperlink to any relevant, publicly available information produced by the *service provider*;
- (j) a *model alternative option service contract* that provides a framework agreement for the *service provider* to negotiate *alternative options*;
- (k) the amount of *alternative options* costs incurred since publishing the previous *alternative options strategy*;
- (l) a description of how parties may be listed on the vendor register; and
- (m) the *service provider's* contact details.⁴²³

Net Benefit Valuation Guidelines⁴²⁴

6A.6 The *Authority* must:

⁴²³ Section 6A.5 inserted by WAGG No 157, 18 September 2020

⁴²⁴ Heading to section 6A.6 inserted by WAGG No 157, 18 September 2020

- (a) make and *publish* guidelines that provide guidance as to acceptable methodologies for valuing *net benefits* by a *service provider*, which methodologies must include, but are not limited to, for the *SWIS*, consideration of changes in costs and benefits for participants in the *Wholesale Electricity Market*; and
- (b) consult the public in accordance with Appendix 7 before making and *publishing* any guidelines under section 6A.6(a).⁴²⁵

Model alternative option service contract⁴²⁶

6A.7 The *model alternative option service contract* forming part of the *service provider's alternative options strategy* under section 6A.5(j) must:

- (c) be reasonable; and
- (d) be sufficiently detailed and complete to enable the *alternative options provider* to understand in advance how the *model alternative option service contract* will be applied; and
- (e) contain provisions that can be utilised to specify the rights and obligations agreed between the *service provider* and the *alternative options provider* in respect to at least the following matters:
 - (i) scope and standard of the *alternative option*;
 - (ii) security;
 - (iii) technical compliance requirements;
 - (iv) testing and maintenance;
 - (v) record keeping, audits and inspection;
 - (vi) confidentiality and privacy;
 - (vii) invoicing and payments;
 - (viii) liability and indemnities;
 - (ix) insurance;
 - (x) suspension and *force majeure*;
 - (xi) default and termination;
 - (xii) assignment and sub-contracting;
 - (xiii) dispute resolution; and

⁴²⁵ Section 6A.6 inserted by WAGG No 157, 18 September 2020

⁴²⁶ Heading to section 6A.7 inserted by WAGG No 157, 18 September 2020

(xiv) warranties.⁴²⁷

- 6A.8 The *Authority* must approve a *model alternative option service contract* if it is reasonably satisfied that it complies with section 6A.7.⁴²⁸
- 6A.9 If the *Authority* does not approve a *model alternative option service contract*, the *Authority* must notify the *service provider* of the changes required for it to be approved.⁴²⁹
- 6A.10 The *Authority* may consult the public before making a decision to approve or not approve a *model alternative option service contract*.⁴³⁰

⁴²⁷ Section 6A.7 inserted by WAGG No 157, 18 September 2020

⁴²⁸ Section 6A.8 inserted by WAGG No 157, 18 September 2020

⁴²⁹ Section 6A.9 inserted by WAGG No 157, 18 September 2020

⁴³⁰ Section 6A.10 inserted by WAGG No 157, 18 September 2020

Chapter 7 – Pricing methods and tariff structure statements⁴³¹

'Pricing methods' defined

7.1 In this Code “**pricing methods**” means the structure of *reference tariffs* included in a *tariff structure statement* under this Chapter 7, which determines how *target revenue* is allocated across and within *reference services*.⁴³²

Tariff structure statements⁴³³

7.1A A *tariff structure statement* of a *service provider* of a *covered network* must set out the *service provider's pricing methods*, and must include the following elements:

- (a) the structures for each proposed *distribution reference tariff*,
- (b) the *charging parameters* for each proposed *distribution reference tariff*, and
- (c) a description of the approach that the *service provider* will take in setting each *distribution reference tariff* in each *price list* of the *service provider* during the relevant *access arrangement period* in accordance with sections 7.2 to 7.12.⁴³⁴

7.1B A *tariff structure statement* must comply with:

- (a) the *pricing principles*; and
- (b) any applicable *framework and approach*.⁴³⁵

7.1C A *network service provider* must comply with the *tariff structure statement* approved by the *Authority* and any other applicable requirements in this Code when the *service provider* is setting the *reference tariffs* for *reference services*.⁴³⁶

7.1D A *tariff structure statement* must be accompanied by a *reference tariff change forecast* which sets out, for each *reference tariff*, the *service provider's* forecast of the weighted average annual price change for that *reference tariff* for each *pricing year* of the *access arrangement period*.⁴³⁷

⁴³¹ Heading amended by WAGG No 157, 18 September 2020

⁴³² Section 7.1 amended by WAGG No 157, 18 September 2020

⁴³³ Heading to section 7.1A inserted by WAGG No 157, 18 September 2020

⁴³⁴ Section 7.1A inserted by WAGG No 157, 18 September 2020

⁴³⁵ Section 7.1B inserted by WAGG No 157, 18 September 2020

⁴³⁶ Section 7.1C inserted by WAGG No 157, 18 September 2020

⁴³⁷ Section 7.1D inserted by WAGG No 157, 18 September 2020

Form of pricing methods

7.2 A *tariff structure statement* may contain any *pricing methods* provided they collectively meet the objectives set out in sections 7.3 and 7.4 and otherwise comply with this Chapter 7.⁴³⁸

{Examples:

- The *pricing methods* may result in *tariffs* which distinguish between:
 - voltage levels; and
 - classes of *users* or *users* by reference to their *end-use customers*.
- The *pricing methods* may result in *tariffs* which relate to specific *connection points*, and may result in *tariffs* which involve a combination of fixed and variable amounts related to one or more of the following elements:
 - demand levels (maximum kW or kVA per period);
 - energy quantities involved (kWh or kVAh per period); and
 - time of use.
- If the *pricing methods* use quantities in determining *tariffs*, they may use minimum, maximum or actual quantities.⁴³⁹

Pricing objective⁴⁴⁰

7.3 Subject to sections 7.3K, 7.7 and 7.12⁴⁴¹, the *pricing methods* in a *tariff structure statement* must have the objective (the “**pricing objective**”) that the *reference tariffs* that a *service provider* charges in respect of its provision of *reference services* should reflect the *service provider’s* efficient costs of providing those *reference services*.⁴⁴²

Application of the pricing principles⁴⁴³

7.3A Subject to sections 7.3B, 7.3K, 7.7 and 7.12, a *service provider’s reference tariffs* must comply with the *pricing principles* set out in sections 7.3D to 7.3J.⁴⁴⁴

7.3B Subject to section 7.3K, a *service provider’s reference tariffs* may not vary from the *reference tariffs* that would result from complying with the *pricing principles* set out in

⁴³⁸ Section 7.2 amended by WAGG No 157, 18 September 2020

⁴³⁹ Note to section 7.2 amended by WAGG No 157, 18 September 2020

⁴⁴⁰ Heading to section 7.3 amended by WAGG No 157, 18 September 2020

⁴⁴¹ Section 7.3 amended by WAGG No 207, 8 November 2005

⁴⁴² Section 7.3 amended by WAGG No 157, 18 September 2020; Section 7.3 amended by WAGG No 134, 30 July 2021

⁴⁴³ Heading to section 7.3A inserted by WAGG No 157, 18 September 2020

⁴⁴⁴ Section 7.3A inserted by WAGG No 157, 18 September 2020; Section 7.3A amended by WAGG No 134, 30 July 2021

sections 7.3D to 7.3H, except to the extent necessary to give effect to the *pricing principles* set out in sections 7.3I to 7.3J.⁴⁴⁵

7.3C A *service provider* must comply with section 7.3A in a manner that will contribute to the achievement of the *pricing objective*.⁴⁴⁶

Pricing principles⁴⁴⁷

7.3D For each *reference tariff*, the revenue expected to be recovered must lie on or between:

- (a) an upper bound representing the *stand-alone cost of service provision for customers* to whom or in respect of whom that *reference tariff* applies; and
- (b) a lower bound representing the avoidable cost of not serving the *customers* to whom or in respect of whom that *reference tariff* applies.⁴⁴⁸

7.3E The *charges* paid by, or in respect of, different *customers* of a *reference service* may differ only to the extent necessary to reflect differences in the *average cost of service provision* to the *customers*.

{Examples of factors which may result in the *charges* paid by different *customers* of a *reference service* differing from each other, include:

- the quantities of *reference service* supplied or to be supplied; or
- a *customer's* time pattern of *network* usage; or
- the technical characteristics or requirements of the *facilities and equipment* at the relevant *connection point*; or
- the nature of the plant or equipment required to provide the *reference service*; or
- the periods for which the *reference service* is to be supplied; or
- subject to section 7.7, a *customer's* location.⁴⁴⁹

7.3F The structure of *reference tariffs* must, so far as is consistent with the *Code objective*, accommodate the reasonable requirements of *users* collectively and *end-use customers* collectively.

{Example: *Customers* may prefer more of the *average cost of service provision* to be recovered using *tariff* components that vary

⁴⁴⁵ Section 7.3B inserted by WAGG No 157, 18 September 2020; Section 7.3B amended by WAGG No 134, 30 July 2021

⁴⁴⁶ Section 7.3C inserted by WAGG No 157, 18 September 2020

⁴⁴⁷ Heading to section 7.3D inserted by WAGG No 157, 18 September 2020

⁴⁴⁸ Section 7.3D inserted by WAGG No 157, 18 September 2020

⁴⁴⁹ Section 7.3E inserted by WAGG No 157, 18 September 2020

with usage or demand than might otherwise be the case under section 7.6.⁴⁵⁰

- 7.3G Each *reference tariff* must be based on the forward-looking efficient costs of providing the *reference service* to which it relates to the *customers* currently on that *reference tariff* with the method of calculating such cost and the manner in which that method is applied to be determined having regard to:
- (a) the additional costs likely to be associated with meeting demand from *end-use customers* that are currently on that *reference tariff* at times of greatest utilisation of the relevant part of the *service provider's network*; and
 - (b) the location of *end-use customers* that are currently on that *reference tariff* and the extent to which costs vary between different locations in the *service provider's network*.⁴⁵¹
- 7.3H The revenue expected to be recovered from each *reference tariff* must:
- (a) reflect the *service provider's* total efficient costs of serving the *customers* that are currently on that *reference tariff*;
 - (b) when summed with the revenue expected to be received from all other *reference tariffs*, permit the *service provider* to recover the expected revenue for the *reference services* in accordance with the *service provider's access arrangement*; and
 - (c) comply with sections 7.3H(a) and 7.3H(b) in a way that minimises distortions to the price signals for efficient usage that would result from *reference tariffs* that comply with the *pricing principle* set out in section 7.3G.⁴⁵²
- 7.3I The structure of each *reference tariff* must be reasonably capable of being understood by *customers* that are currently on that *reference tariff*, including enabling a *customer* to predict the likely annual changes in *reference tariffs* during the *access arrangement period*, having regard to:
- (a) the type and nature of those *customers*;
 - (b) the information provided to, and the consultation undertaken with, those *customers*.⁴⁵³
- 7.3J A *reference tariff* must comply with this Code and all relevant *written laws* and *statutory instruments*.⁴⁵⁴
- 7.3K Despite sections 7.3D to 7.3H, a *reference tariff* may include a component, applicable where a *user* exceeds its contractual entitlements to transfer electricity into or out of the *network* at a *connection point*, which component is not set by reference to the *service provider's* costs, but instead is set at a level to act as a disincentive to the *user*

⁴⁵⁰ Section 7.3F inserted by WAGG No 157, 18 September 2020

⁴⁵¹ Section 7.3G inserted by WAGG No 157, 18 September 2020

⁴⁵² Section 7.3H inserted by WAGG No 157, 18 September 2020

⁴⁵³ Section 7.3I inserted by WAGG No 157, 18 September 2020

⁴⁵⁴ Section 7.3J inserted by WAGG No 157, 18 September 2020

exceeding its contractual entitlements. Such component should be determined having regard to the following principles:

- (a) the component must be set at a level which provides a material disincentive to the *user* transferring into or out of the *network* quantities of electricity above its contractual entitlements; and
- (b) in determining that level, regard is to be had to the potential adverse impact on the *network*, other *customers* and *generators*, and the *service provider* of the *user* transferring into or out of the *network* quantities of electricity above its contractual entitlements.⁴⁵⁵

7.3L Unless otherwise determined by the *Authority*, section 7.3K does not apply to *connection points* servicing *end use customers* with a contract maximum demand not exceeding 1 MVA or *end use customers* with solar photovoltaic *generating plant* not exceeding 1 MVA in capacity.⁴⁵⁶

[Heading not used]⁴⁵⁷

7.4 [Not used]⁴⁵⁸

[Heading not used]⁴⁵⁹

7.5 [Not used]⁴⁶⁰

Tariff components

7.6 Unless a *tariff structure statement* containing alternative *pricing methods* would better achieve the *Code objective*, and subject to section 7.3K, for a *reference service*.⁴⁶¹

- (a) the incremental cost of service provision should be recovered by *tariff* components that vary with usage or demand; and
- (b) any amount in excess of the incremental cost of service provision should be recovered by *tariff* components that do not vary with usage or demand.

Postage stamp charges in certain cases

7.7 The *tariff* applying to a *standard tariff user* in respect of a *standard tariff exit point* must not differ from the *tariff* applying to any other *standard tariff user* in respect of a *standard tariff exit point* as a result of differences in the geographic locations of the *standard tariff exit points*.

⁴⁵⁵ Section 7.3K inserted by WAGG No 134, 30 July 2021

⁴⁵⁶ Section 7.3L inserted by WAGG No 134, 30 July 2021

⁴⁵⁷ Heading to section 7.4 deleted by WAGG No 157, 18 September 2020

⁴⁵⁸ Section 7.4 deleted by WAGG No 157, 18 September 2020

⁴⁵⁹ Heading to section 7.5 deleted by WAGG No 157, 18 September 2020

⁴⁶⁰ Section 7.5 deleted by WAGG No 157, 18 September 2020

⁴⁶¹ Section 7.6 amended by WAGG No 157, 18 September 2020; Section 7.6 amended by WAGG No 134, 30 July 2021

‘Equivalent tariff’ defined

7.8 In sections 7.9 and 7.10, “**equivalent tariff**” means:

- (a) for a *reference service* — the *reference tariff*; and
- (b) for a *non-reference service* — the *tariff* that it is reasonably likely would have been set as the *reference tariff* had the *non-reference service* been a *reference service*.

Prudent discounts

7.9 If a *user* seeks to implement initiatives to promote the economically efficient investment in and operation of the *covered network*, a *service provider* must reflect in the *user’s tariff*, by way of a discount, a share of any reductions in either or both of the *service provider’s capital-related costs* or *non-capital costs* which arise in relation to the initiative by:⁴⁶²

- (a) by entering into an agreement with a *user* to apply a discount to the equivalent *tariff* to be paid by the *user* for a *covered service*; and
- (b) then, recovering the amount of the discount from other *users* of *reference services* through *reference tariffs*.

Discounts for distributed generating plant

7.10 If a *user* seeks to *connect distributed generating plant* to a *covered network*, a *service provider* must reflect in the *user’s tariff*, by way of a discount, a share of any reductions in either or both of the *service provider’s capital-related costs* or *non-capital costs* which arise as a result of the *entry point* for *distributed generating plant* being located in a particular part of the *covered network* by:

- (a) entering into an agreement with a *user* to apply a discount to the equivalent *tariff* to be paid by the *user* for a *covered service*; and
- (b) then, recovering the amount of the discount from other *users* of *reference services* through *reference tariffs*.

Access arrangement must detail policies regarding discounts

7.11 An *access arrangement* must contain a detailed policy setting out how the *service provider* will implement:

- (a) if the *service provider* so chooses – section 7.9; and
- (b) section 7.10,

including a detailed mechanism for determining when a *user* will be entitled to receive a discount and for calculating the discount to which the *user* will be entitled.

⁴⁶² Section 7.9 amended by WAGG No 157, 18 September 2020

Tariff equalisation contributions must be included as a tariff component for distribution network users

- 7.12 If an amount is added to the *target revenue* under section 6.37A and is intended to be recovered from *users of reference services* through one or more *reference tariffs*, then the recovery must have the objective of⁴⁶³:
- (a) applying only to *users of reference services* provided in respect of *exit points* on the *distribution system*; and
 - (b) being equitable in its effect as between the *users* referred to in section 7.12(a); and
 - (c) otherwise being consistent with the *Code objective*.⁴⁶⁴

⁴⁶³ Section 7.12 amended by WAGG No 206, 8 December 2006

⁴⁶⁴ Section 7.12 further amended by WAGG No 206, 8 December 2006

Chapter 8 – Price lists

Submission and approval of price lists if required⁴⁶⁵

8.1 A *service provider* must:

- (a) submit to the *Authority*, as soon as practicable, and in any case within 15 *business days*, after the *Authority* publishes its *final decision* under section 4.17, a *price list* (the “*initial price list*”) for the first *pricing year* of the *access arrangement period*; and
- (b) submit to the *Authority*, at least 3 months before the commencement of the second and each subsequent *pricing year* of the *access arrangement period*, a further *price list* (an “*annual price list*”) for the relevant *pricing year*.⁴⁶⁶

8.1A If a *service provider’s access arrangement*:

- (a) requires it to submit *price lists* to the *Authority* for approval, the process set out in sections 8.2 to 8.7 will apply upon the *service provider* submitting its *price list* under section 8.1; or
- (b) does not require it to submit *price lists* to the *Authority* for approval, the *Authority* must *publish* the *price list* within 5 *business days* after the *service provider* submits the *price list* under section 8.1, and that *price list* will be deemed to be an *approved price list*.⁴⁶⁷

8.2 The *Authority* must approve a *price list* if the *Authority* is satisfied that:

- (a) the *price list* complies with Chapter 7 and this Chapter 8 and the *service provider’s access arrangement*, including any applicable *tariff structure statement*; and
- (b) all forecasts associated with the *price list* are reasonable.⁴⁶⁸

8.3 If the *Authority* determines that a *price list* is deficient:

- (a) the *Authority* may require the *service provider*, within 10 *business days* after receiving notice of the determination, to re-submit the *price list* with the amendments necessary to correct the deficiencies identified in the determination and (unless the *Authority* permits further amendment) no further amendment; or

⁴⁶⁵ Heading to section 8.1 amended by WAGG No 157, 18 September 2020

⁴⁶⁶ Section 8.1 amended by WAGG No 157, 18 September 2020

⁴⁶⁷ Section 8.1A inserted by WAGG No 157, 18 September 2020

⁴⁶⁸ Section 8.2 amended by WAGG No 157, 18 September 2020

- (b) the *Authority* may itself make the amendments necessary to correct the deficiencies.⁴⁶⁹
- 8.4 If the *service provider* fails to comply with a requirement under section 8.3, or the resubmitted *price list* fails to correct the deficiencies in the former *price list*, the *Authority* may itself amend the *price list* to bring it into conformity with the requirements of this Chapter 8, the *service provider's access arrangement* and the *service provider's tariff structure statement* for the relevant *access arrangement period*.⁴⁷⁰
- 8.5 For the purposes of amending a *price list* under section 8.3(b) or section 8.4, the *Authority* may have regard to the forecast price changes for the relevant *pricing year* as set out in any applicable *reference tariff change forecast*.⁴⁷¹
- 8.6 The *Authority* must, within 15 *business days* from the date of submission of an *initial price list* by a *service provider* under section 8.1(a), *publish* an *approved price list* (including any amendments made by the *Authority* under section 8.3(b) or section 8.4) with respect to that *initial price list*.⁴⁷²
- 473
- 8.7 The *Authority* must, within 30 *business days* from the date of submission of an *annual price list* by a *service provider* under section 8.1(b), *publish* an *approved price list* (including any amendments made by the *Authority* under section 8.3(b) or section 8.4) with respect to that *annual price list*.⁴⁷⁴
- 8.8 If the *Authority* does not *publish* an *approved price list* by the date specified in section 8.6 or 8.7 (as applicable), the *approved price list* most recently in effect continues in effect until the *Authority publishes* a revised *approved price list* in accordance with section 8.6 or 8.7 (as applicable) and that revised *approved price list* takes effect in accordance with section 8.11.⁴⁷⁵
- 8.9 If the *Authority* does not *publish* its *final decision* under section 4.17 by the date specified in section 4.18A, the *approved price list* most recently in effect continues in effect until:
- (a) the *Authority publishes* its *final decision* under section 4.17; and
 - (b) the *service provider* submits its *initial price list* under section 8.1(a); and
 - (c) the *Authority publishes* an *approved price list* with respect to that *initial price list* in accordance with section 8.1A or 8.6 (as applicable); and

⁴⁶⁹ Section 8.3 amended by WAGG No 157, 18 September 2020

⁴⁷⁰ Section 8.4 amended by WAGG No 157, 18 September 2020

⁴⁷¹ Section 8.5 amended by WAGG No 157, 18 September 2020

⁴⁷² Section 8.6 amended by WAGG No 157, 18 September 2020

⁴⁷³ Heading to section 8.7 deleted by WAGG No 157, 18 September 2020

⁴⁷⁴ Section 8.7 amended by WAGG No 157, 18 September 2020

⁴⁷⁵ Section 8.8 amended by WAGG No 157, 18 September 2020

- (d) that *approved price list* takes effect in accordance with section 8.10(a) or 8.11 (as applicable).⁴⁷⁶

8.10 An *approved price list published* under section 8.1A(b) takes effect:

- (a) in the case of an *initial price list* – at the commencement of the first *pricing year* of the relevant *access arrangement period*; and
- (b) in the case of an *annual price list* – at the commencement of the *pricing year* to which the *price list* relates.⁴⁷⁷

8.11 An *approved price list published* under section 8.6 or 8.7 takes effect from a date specified by the *Authority*, provided that the date specified by the *Authority* must be the date set out in section 8.10(a) or 8.10(b) (as applicable) unless the *Authority* considers there are circumstances which reasonably justify a departure from such date.

{Note: an example of circumstances which would reasonably justify the *Authority* departing from the date set out in section 8.10(a) or 8.10(b) would be where the previous *approved price list* has continued to have effect pursuant to section 8.8 and a new *pricing year* has commenced, in which case the *Authority* could specify that the revised *approved price list* will take effect from the date it is *published*.}⁴⁷⁸

Contents of price list⁴⁷⁹

8.12 A *price list* must:

- (a) set out the proposed *reference tariffs* for the relevant *access arrangement period*;
- (b) set out, for each proposed *reference tariff*, the *charging parameters* and the elements of service to which each *charging parameter* relates;
- (c) set out the nature of any variation or adjustment to the *reference tariff* that could occur during the course of the *pricing year* and the basis on which it could occur;
- (d) demonstrate compliance with this Code and the *service provider's access arrangement*, including the *service provider's tariff structure statement* for the relevant *access arrangement period*;
- (e) for any *pricing year* other than the first *pricing year* in an *access arrangement period*, demonstrate how each proposed *reference tariff* is consistent with the corresponding forecast price change for that *reference tariff* for the relevant *pricing year* as set out in the relevant *reference tariff change forecast*, or explain any material differences between them; and

⁴⁷⁶ Section 8.9 inserted by WAGG No 157, 18 September 2020

⁴⁷⁷ Section 8.10 inserted by WAGG No 157, 18 September 2020

⁴⁷⁸ Section 8.11 inserted by WAGG No 157, 18 September 2020

⁴⁷⁹ Heading to section 8.12 inserted by WAGG No 157, 18 September 2020

- (f) describe the nature and extent of change from the previous *pricing year* and demonstrate that the changes comply with this Code and the *service provider's access arrangement*.⁴⁸⁰

Revision of reference tariff change forecast⁴⁸¹

- 8.13 At the same time as a *service provider* submits a *price list* under section 8.1, the *service provider* must submit to the *Authority* a revised *reference tariff change forecast* which sets out, for each *reference tariff*, the *service provider's* forecast of the weighted average annual price change for that *reference tariff* for each remaining *pricing year* of the *access arrangement period*, and updated so as to take into account that *price list*.⁴⁸²

Publication of information about tariffs⁴⁸³

- 8.14 A *service provider* must maintain on its website:
- (a) its current *tariff structure statement*;
 - (b) its current *reference tariff change forecast*; and
 - (c) its current *approved price list*.⁴⁸⁴
- 8.15 A *service provider* must, within 5 *business days* from the date the *Authority publishes* its *final decision* under section 4.17 for that *service provider's access arrangement*, *publish* the *tariff structure statement* approved or contained in the approved *access arrangement* and the accompanying *reference tariff change forecast*.⁴⁸⁵
- 8.16 A *service provider* must *publish* the information referred to in section 8.14 within 5 *business days* from the date the *Authority publishes* an *approved price list* under section 8.1A, section 8.6 or section 8.7 (as applicable) for that *service provider*.⁴⁸⁶

⁴⁸⁰ Section 8.12 inserted by WAGG No 157, 18 September 2020

⁴⁸¹ Heading to section 8.13 inserted by WAGG No 157, 18 September 2020

⁴⁸² Section 8.13 inserted by WAGG No 157, 18 September 2020

⁴⁸³ Heading to section 8.14 inserted by WAGG No 157, 18 September 2020

⁴⁸⁴ Section 8.14 inserted by WAGG No 157, 18 September 2020

⁴⁸⁵ Section 8.15 inserted by WAGG No 157, 18 September 2020

⁴⁸⁶ Section 8.16 inserted by WAGG No 157, 18 September 2020

Chapter 9 – Regulatory test

{Note: The *regulatory test* applies only to *proposed major augmentations*. It applies to a *proposed major augmentation* whether the *service provider* proposes to undertake the *proposed major augmentation*:

- (a) in order to provide *covered services*, but not specifically in relation any particular project; or
- (b) in relation to a project involving the *generation* of or consumption of electricity.

The *regulatory test* cannot require a project involving the *generation* or consumption of electricity to be located in a particular place or to be altered in any other way. The *regulatory test* can only affect what network *augmentations* are undertaken in order to accommodate the project.}

Subchapter 9.1 – Introductory

Objectives of this Chapter 9

9.1 The objectives of this Chapter 9 (“**Chapter 9 objectives**”) are:

- (a) to ensure that before a *service provider* commits to a *proposed major augmentation* to a *covered network*, the *major augmentation* is properly assessed to determine whether it maximises the *net benefit after considering alternative options*; and
- (b) to provide an incentive to a *service provider*, when considering *augmentation* to a *covered network*, to select the option (which may involve a *major augmentation* or may involve not proceeding with an *augmentation* at all) which maximises the *net benefit after considering alternative options*; and
- (c) to minimise:
 - (i) delay to projects and other developments; and
 - (ii) administrative and regulatory costs; and
 - (iii) any other barriers to the entry of *generators* and *consumers* into the electricity market,

arising from the *application* of the *regulatory test*.

No major augmentation without regulatory test determination

9.2 A *service provider* must not commit to a *major augmentation* before the *Authority* determines, or is deemed to determine, under section 9.13 or 9.18, as applicable, that the test in section 9.14 or 9.20, as applicable, is satisfied.

‘Regulatory test’ defined

9.3 The “**regulatory test**” is an assessment under this Chapter 9 of whether a *proposed major augmentation* to a *covered network* maximises the *net benefit after considering alternative options*.

9.4 A “**net benefit after considering alternative options**” means a net benefit (measured in present value terms to the extent that it is possible to do so) to those who *generate, transport and consume* electricity in the *covered network* and any *interconnected system*, having regard to all reasonable *alternative options*, including the likelihood of each *alternative option* proceeding.

‘Committed’ defined

9.5 Subject to section 9.6, a *service provider* has “**committed**” to a *major augmentation* when the *service provider*, intending to undertake the *major augmentation*, begins to put its intention into effect by doing an act which is more than merely preparatory to undertaking the *major augmentation*, including by:

(a) making a substantial financial commitment in respect of the *major augmentation*, such as committing to:

(i) a significant obligation which is legally binding; or

(ii) an obligation which would have significant commercial repercussions if cancelled, discontinued or dishonoured;

or

(b) commencing, or procuring the commencement of, construction of the *major augmentation*.

9.6 A *service provider* will not be considered to have *committed* to undertaking a *major augmentation* merely because the *service provider* has:

(a) undertaken preparatory system or other studies in respect of the *major augmentation*; or

(b) engaged in preparatory planning, design or costing activities in respect of the *major augmentation*; or

(c) obtained an approval in respect of the *major augmentation*, unless the approval comes within the description in section 9.5(a) or 9.5(b).

Authority may make a determination that an augmentation is or is not a major augmentation

9.7 A *service provider* may request the *Authority*, as part of or prior to a decision under sections 9.13 or 9.18 (as applicable), having regard to the *forecast new facilities investment* for a proposed *augmentation*, to determine whether or not the proposed *augmentation* is a *major augmentation*.

9.8 A determination by the *Authority* under section 9.7 is conclusive evidence of whether the proposed *augmentation* is a *major augmentation*.

Service provider must make information available

- 9.9 A *service provider* must use its reasonable endeavours to ensure that it makes sufficient information available in a timely manner in respect of a *proposed major augmentation* to maximise the opportunity for potential *alternative options* to be viable.

Subchapter 9.2 – Regulatory test process

Regulatory test as part of access arrangement approval process

- 9.10 A *service provider* may submit a *major augmentation proposal* as part of its *proposed access arrangement*, in which case sections 9.11 to 9.14 apply.
- 9.11 A *major augmentation proposal* submitted under section 9.10:
- (a) must describe in detail each *major augmentation* to which the *major augmentation proposal* relates; and
 - (b) must state that, in the *service provider's* view, each *proposed major augmentation* maximises the *net benefit after considering alternative options*; and
 - (c) may be amended in a revised *proposed access arrangement* submitted under section 4.16; and
 - (d) may rely on information from the *whole of system plan* if relevant to the *major augmentation proposal*.⁴⁸⁷
- 9.12 The invitation under section 4.9 for submissions on the *proposed access arrangement* must invite submissions on the *service provider's* statement under section 9.11(b), including submissions on reasonable *alternative options* to each *proposed major augmentation*.
- 9.13 The *Authority's final decision* under section 4.17 must state whether the test in section 9.14 is satisfied or is not satisfied.⁴⁸⁸
- 9.14 The test in this section 9.14 is satisfied if the *Authority* is satisfied that:
- (a) the *service provider's* statement under section 9.11(b) is defensible; and
 - (b) the *service provider* has applied the *regulatory test* properly to each *proposed major augmentation*:
 - (i) using reasonable market development scenarios which incorporate varying levels of demand growth at relevant places; and
 - (ii) using reasonable timings, and testing alternative timings, for project commissioning dates and construction timetables for the *major augmentation* and for *alternative options*;

⁴⁸⁷ Section 9.11 amended by WAGG No 157, 18 September 2020

⁴⁸⁸ Section 9.13 amended by WAGG No 157, 18 September 2020

Regulatory test not as part of access arrangement approval process

- 9.15 A *service provider* may submit a *major augmentation proposal* other than as part of the *access arrangement approval* process, in which case sections 9.16 to 9.22 apply.
- 9.16 A *major augmentation proposal* submitted under section 9.15:
- (a) must describe in detail each *major augmentation* to which the *major augmentation proposal* relates; and
 - (b) must state that, in the *service provider's* view, each *proposed major augmentation* maximises the *net benefit after considering alternative options*; and
 - (c) must demonstrate that the *service provider* has conducted a consultation process in respect of each *proposed major augmentation* which:
 - (i) included public consultation under Appendix 7; and
 - (ii) gave all *interested persons* a reasonable opportunity to state their views and to propose *alternative options* to the *proposed major augmentations*, and that the *service provider* had regard to those views and *alternative options*; and
 - (iii) involved the *service provider* giving reasonable consideration to any information obtained under sections 9.16(c)(i) and 9.16(c)(ii) when forming its view under section 9.16(b);and
 - (d) must comply with the current requirements *published* under section 9.17.
 - (e) may include a request that the *Authority* give prior approval under section 6.72 in respect of the *new facilities investment* for one or more *proposed major augmentations*; and
 - (f) may include information from the *whole of system plan* if relevant to the *major augmentation proposal*.⁴⁸⁹
- 9.17 The *Authority* must *publish*, and may from time to time *publish* variations to, its requirements for a *major augmentation proposal* submitted under section 9.16, which requirements must be directed to ensuring that the *Authority* receives sufficient information in a suitable form to enable it to efficiently and effectively apply the test in section 9.20.
- 9.18 The *Authority* must in respect of a *major augmentation proposal* submitted under section 9.15 make and *publish* a determination whether the test in section 9.20 is satisfied or is not satisfied, and must do so:
- (a) if the *Authority* has consulted the public under section 9.19 — within 45 *business days*; and

⁴⁸⁹ Section 9.16 amended by WAGG No 157, 18 September 2020

- (b) otherwise — within 25 *business days*,
after receiving the *major augmentation proposal*.
- 9.19 The *Authority* may consult the public under Appendix 7 before making a determination under section 9.18.
- 9.20 The test in this section 9.20 is satisfied if the *Authority* is satisfied that:
- (a) the *service provider's* statement under section 9.16(b) is defensible; and
 - (b) the *service provider* has applied the *regulatory test* properly to each *proposed major augmentation*:
 - (i) using reasonable market development scenarios which incorporate varying levels of demand growth at relevant places; and
 - (ii) using reasonable timings, and testing alternative timings, for project commissioning dates and construction timetables for the *major augmentation* and for *alternative options*;
- and
- (c) the consultation process conducted by the *service provider* meets the criteria in section 9.16(c).
- 9.21 If the *Authority* is unable to determine whether the test set out in section 9.20 is satisfied or is not satisfied because the *service provider* has not provided adequate information (despite the *Authority* having notified the *service provider* of this fact and given the *service provider* a reasonable opportunity, having regard to the time periods specified in section 9.18, to provide adequate information), then the *Authority* may determine that the test in section 9.20 is not satisfied.
- 9.22 If the *Authority* has not *published* a determination under section 9.18 within the time limits specified in that section, then the *Authority* is deemed to have determined that the test in section 9.20 is satisfied.

Regulatory test may be expedited, otherwise modified or waived

- 9.23 If the *Authority* forms the view that the application of the *regulatory test* under sections 9.10 to 9.14 or sections 9.15 to 9.22 in respect of a *proposed major augmentation* would be contrary to the Chapter 9 objectives, including because:
- (a) there are no, or it is unlikely that there are any, viable *alternative options* to the *proposed major augmentation*; or
 - (b) the nature of the *proposed major augmentation* is such that significant advance planning is required and no *alternative options* exist; or
 - (c) the nature of the *proposed major augmentation*, or part of it, is such that it should be submitted to AEMO; or⁴⁹⁰

⁴⁹⁰ Section 9.23 amended by WAGG No 157, 18 September 2020

- (d) the nature of the funding of the *proposed major augmentation* means that the *proposed major augmentation* will not cause a net cost (measured in present value terms to the extent that it is possible to do so) to those who *generate, transport and consume* electricity in the *covered network* and any *interconnected system*,

then the *Authority* may, by *publishing* a notice:

- (e) expedite or otherwise modify the *application* of the *regulatory test* in respect of the *major augmentation* to the extent the *Authority* considers necessary to meet the *Chapter 9 objectives*; or
- (f) waive the application of the *regulatory test* in respect of the *major augmentation* if the *Authority* considers it necessary to do so to meet the *Chapter 9 objectives*.

9.24 Without limiting the circumstances in which the *Authority* may *publish* a notice under section 9.23, if a person requests the *Authority* to form a view under section 9.23 in respect of a *proposed major augmentation* which is described to the *Authority* in reasonable detail then the *Authority* must as soon as practicable form a view and either:

- (a) *publish* a notice under section 9.23; or
- (b) notify the person that the *Authority* does not propose to *publish* a notice under section 9.23.

9.24A If a person requests the *Authority* to form a view under section 9.23, the *Authority* may take into account any information obtained from the preparation of, or set out in the *whole of system plan*.⁴⁹¹

9.24B To avoid doubt, a *priority project* is not subject to the *regulatory test*.⁴⁹²

Vexatious etc alternative options

9.25 Neither the *service provider* nor the *Authority* is required by this Chapter 9 to have regard to an *alternative option* which is misconceived or is proposed on vexatious grounds.

Subchapter 9.3 – Anti-avoidance provisions

Anti-avoidance provisions

9.26 Section 9.27 applies if the *Authority* determines that a *service provider* has engaged in conduct with the purpose of avoiding or frustrating the objective in section 9.1(a).

9.27 The *Authority* may by notice to the *service provider* deem:

- (a) any two or more *augmentations* to constitute a single *augmentation*; or

⁴⁹¹ Section 9.24A inserted by WAGG No 157, 18 September 2020

⁴⁹² Section 9.24B inserted by WAGG No 157, 18 September 2020

- (b) any *augmentation* to constitute any two or more *augmentations*; or
- (c) any activity which has been attributed to an *augmentation* to be attributed to a different *augmentation*; or
- (d) any combination of sections 9.27(a), 9.27(b), or 9.27(c),

in which case the deeming has conclusive effect for the purposes of this Chapter 9.

9.28 A notice under section 9.27 must set out *reasons* for the *Authority's* decision under section 9.27.

9.29 A deeming under section 9.27 may:

- (a) relate to two or more *augmentations* whether or not they occur at the same time; and
- (b) relate to one or more *augmentations* whether or not they have been completed; and
- (c) specify the time at which a deemed thing occurred or will occur.

9.30 To avoid doubt, each reference in sections 9.27 and 9.29 to "*augmentation*" includes a *major augmentation* and an *augmentation* previously deemed under sections 9.27 and 9.29.

Chapter 10 – Dispute Resolution

Subchapter 10.1 – Introduction

Commercial Arbitration Act 2012 does not apply⁴⁹³

- 10.1 A proceeding under this Chapter 10 is not an arbitration within the meaning of the *Commercial Arbitration Act 2012*.⁴⁹⁴

Procedural rules

- 10.2 Appendix 5 applies in respect of an *access dispute*.

Subchapter 10.2 – Access Disputes

Notification of a dispute

- 10.3 An *applicant* or a *service provider* may notify the *Authority* in writing that an *access dispute* exists.
- 10.4 On receiving a notification under section 10.3, the *Authority* must give notice in writing of the *access dispute* to the other parties to the dispute.
- 10.5 An *applicant* or *service provider* who has given notice of an *access dispute* under section 10.3 may withdraw notification of the *access dispute* at any time by written notice to the *Authority* and all other parties to the *access dispute*.
- 10.6 If the notification of an *access dispute* is withdrawn under section 10.5, it is taken for the purposes of this Chapter 10 to never have been given.

Other parties joining

- 10.7 A person, other than a party to a dispute, may apply to the *arbitrator* to join and be heard in the *proceedings*.
- 10.8 The *arbitrator*:
- (a) must allow a person applying under section 10.7 to join the *proceedings* if the person is affected by the *proceedings* unless the *arbitrator* determines that doing otherwise is necessary to justly dispose of the issues in the *proceedings*; and

⁴⁹³ Heading to section 10.1 amended by WAGG No 157, 18 September 2020

⁴⁹⁴ Section 10.1 amended by WAGG No 157, 18 September 2020

- (b) may make such orders concerning the joinder as the *arbitrator* considers appropriate.

10.9 The *arbitrator* may on its own initiative:

- (a) direct a party to a dispute to provide it with sufficient information to enable it to identify other persons who might wish to apply under section 10.7 to join and be heard in the *proceedings*;

{Note: This may include information as to any (or any other) *applicants* and details of each *applicant's access application*.}

- (b) notify any person identified by it under section 10.9(a) that the dispute exists and the parties to the dispute.

10.10 The parties to a dispute must promptly comply with a direction under section 10.9(a).

Conciliation and reference to arbitration

10.11 On receiving a request to refer an *access dispute* to arbitration, the *Authority* must:

- (a) subject to section 10.12 and if the parties to the dispute agree, attempt to settle the dispute by conciliation; or
- (b) if the *Authority* does not attempt to settle the dispute by conciliation or conciliation fails to settle the dispute, refer the dispute to the *arbitrator*.

Authority not required to conciliate

10.12 The *Authority* is not obliged to attempt to settle the dispute by conciliation if the *Authority* is satisfied, on the application of a party to the *access dispute*, that there are good *reasons* why the dispute should not be settled by conciliation.

Expedited hearing of disputes under applications and queuing policy

10.13 Section 10.14 applies in respect of an *access dispute* ("**queuing dispute**") relating to an interim or procedural matter under an *applications and queuing policy*, in respect of which either:

- (a) the *service provider* and the *applicant* agree in writing to have the matter heard as a *queuing dispute*;
- (b) where the *arbitrator* determines (on application by either party) that a speedy resolution of the *queuing dispute* may permit the *access application* to be further progressed and an *access offer* made without the parties having to resort to a lengthy, full-scale *access dispute*.

10.14 Unless the *arbitrator* considers that the *Code objective* or the just resolution of the *queuing dispute* require a *queuing dispute* to be dealt with in another way, when hearing a *queuing dispute*:

- (a) the parties are to be restricted to one round of written submissions and one round of written submissions in reply (which may not be amended except by leave of the *arbitrator*); and

- (b) the hearing is to be conducted without legal representation (but parties may obtain legal advice in preparing the written submission); and
- (c) the *arbitrator* is to treat the objective of informality and expedition as paramount; and
- (d) the *arbitrator* and the parties must endeavour to ensure that the *queuing dispute* is determined within 10 *business days* after notice of the *queuing dispute* is given.

Factors which the arbitrator must have regard to

10.15 In exercising its functions under this Chapter 10 the *arbitrator* must have regard to:

{Note: Section 2.2 requires the *arbitrator* to have regard to the *Code objective* when exercising its functions under this Chapter 10.}

- (a) the geographical location of the network and the extent (if any) to which the network is interconnected with other networks; and
- (b) contractual obligations of the *service provider* or other persons already using the *covered network* (or both); and
- (c) the operational and technical requirements necessary for the safe and reliable operation of the *covered network*.

10.16 Section 10.15 does not limit the matters to which the *arbitrator* may have regard.

The arbitration

10.17 The *arbitrator* must make a decision on the matters the subject of the *access dispute* following the procedure prescribed in Appendix 5.

10.18 The *arbitrator* may at any time terminate an arbitration (without making a decision) if the *arbitrator* considers that:

- (a) the subject matter of the *access dispute* is trivial, misconceived or lacking in substance; or
- (b) the notification of the *access dispute* was vexatious; or
- (c) the party who notified the *access dispute* has not negotiated in good faith or has notified the *access dispute* prematurely or unreasonably.

Arbitrated tariff to be guided by access arrangement and price list

10.19 Subject to section 10.20, if an *access dispute* relates to the *tariff* that should apply to a *covered service*, the *arbitrator* must set the *tariff* payable by the *applicant* under the award having regard to the *access arrangement* and *price list* and Chapter 7.

Arbitrated tariffs for reference services

10.20 If an *access dispute* relates to the *tariff* that should apply to a *reference service*, then an award must not:

- (a) require the *applicant* to pay more than the *reference tariff* for the *reference service*, or
- (b) require the *service provider* to accept less than the *reference tariff* for the *reference service*.

Arbitrated terms for reference services

10.21 Subject to section 10.22, the *arbitrator* must not make an award specifying the terms of an *access contract* for a *reference service* that is inconsistent with the *standard access contract* for the *reference service* set out in the *service provider's access arrangement*.

10.22 The *arbitrator* must, in an award specifying the terms of an *access contract* for a *reference service*, deal with each matter which in the *standard access contract* for the *reference service* in the *access arrangement* is left to be agreed by the parties or determined by the *arbitrator* in a manner which:

- (a) has regard to the factors contained in section 10.15; and
- (b) is consistent with:
 - (i) any instructions about the matter contained in the *access arrangement*; and
 - (ii) the *Code objective*.

Arbitrated tariffs for non-reference services

10.23 Where the *arbitrator* is setting the *tariff* payable by the *applicant* for a *non-reference service*, the award should endeavour to achieve the following objectives:

- (a) when the awarded *tariff* is compared with the *reference tariff* for a comparable *reference service* (if any):
 - (i) if the *non-reference service* involves the provision of *services* to a higher standard, the differential between the awarded *tariff* and the *reference tariff* should reflect the increase in the *service provider's* incremental cost of service provision as a result of the provision of *services* to that higher standard;and
 - (ii) if the *non-reference service* involves the provision of *services* to a lower standard, the differential between the awarded *tariff* and the *reference tariff* should reflect the amount of the *service provider's* avoided cost of service provision as a result of the provision of *services* to that lower standard;and
- (b) subject to the discount provisions in the *service provider's access arrangement*, other *users* should not pay individual *reference tariffs* for *reference services* that are higher as a result of the differential referred to in section 10.23(a).

10.24 Where the *arbitrator* is awarding the *tariff* payable by the *applicant* for a *non-reference service*, the award must have regard to Chapter 7 and the *service provider's access arrangement* including the *standard access contract* contained in the *service provider's access arrangement*.⁴⁹⁵

10.25 Section 10.24 does not limit the matters to which the *arbitrator* must or may have regard.

Award by the arbitrator

10.26 The *arbitrator* must make a written award on access to the network by the *applicant*.

10.27 The award referred to in section 10.26:

- (a) must deal with the matter that was the basis for the notification of the dispute; and
- (b) may, subject to section 10.28, deal with any other matter which a party has requested the *arbitrator* to deal with that the *arbitrator* considers expedient to justly dispose of any *proceedings* before it.

10.28 The *arbitrator* cannot make an award under section 10.26 that deals with a matter that is, by agreement between the parties, no longer a matter which is in dispute.

10.29 Without limiting the generality of section 10.24 and subject to section 10.32, the award may, without limitation, do any one or more of the following:

- (a) specify the manner in which a party must comply with the *applications and queuing policy*; or
- (b) deal with the costs, timing or performance of functions in relation to the undertaking of proposed work, and may require a party to undertake any such function in a specified manner; or
- (c) require the *service provider* to provide access to a *covered service* requested by the *applicant*; or
- (d) subject to section 10.35, require the *applicant* to accept, and pay for, access to a service; or
- (e) specify the terms of the *access contract* including the discount to the *reference tariff* to which the *user* is entitled (if any) and the amount of any *contribution* and the terms on which it is to be provided; or
- (f) require the *service provider* to undertake and fund any *required work* including to augment the network; or
- (g) specify the extent to which the award overrides an earlier award or *contract for services*; or

⁴⁹⁵ Section 10.24 amended by WAGG No 157, 18 September 2020

- (h) make an “immunity determination” under the *Electricity Industry (Pilbara Networks) Regulations 2021*.⁴⁹⁶

10.29B The paragraphs of section 10.29 do not limit each other.⁴⁹⁷

10.30 Before making an award, the *arbitrator* must give a draft award to the parties to the arbitration and may have regard to representations that any of them may make on the *proposed award*.

10.31 When the *arbitrator* makes an award, the *arbitrator* must give the parties to the arbitration written *reasons* for the award.

Restrictions on access awards

10.32 The *arbitrator* cannot make an award that:

- (a) would impede the right of a *user* under a *contract for services* to obtain *services* unless the *user* agrees or the *arbitrator* is satisfied that the *user* is or will be compensated on just terms for in respect of the impeded right; or
- (b) is inconsistent with the *access arrangement* for the *covered network*; or
- (c) requires the *service provider* to provide *access* to a service designated as an *excluded service* in the *access arrangement*; or
- (d) affects an area of the State that is the subject of the exclusive license of another *service provider*; or
- (e) requires the *service provider* or another person to engage in an act or omit to engage in an act which would contravene a *written law* or a *statutory instrument*.⁴⁹⁸

Arbitrated award requiring work to be undertaken⁴⁹⁹

10.33 The *arbitrator* may make an award that would have the effect of requiring the *service provider* to undertake *work* only where the *arbitrator* is satisfied that:

- (a) the *work* is technically and economically feasible and consistent with the safe and reliable operation of the network; and
- (b) in the case of a *major augmentation*, sections 10.40 to 10.43 have been complied with.⁵⁰⁰

Effect of awards

10.34 Subject to section 10.35, an award is binding on the parties to the arbitration in which it is made.

⁴⁹⁶ Section 10.29 amended by WAGG No 180, 22 October 2008; section 10.29 amended by WAGG No 118, 2 July 2021

⁴⁹⁷ Section 10.29A inserted by WAGG No 180, 22 October 2008

⁴⁹⁸ Section 10.32(a) amended by WAGG No 180, 22 October 2008

⁴⁹⁹ Heading to section 10.33 amended by WAGG No 180, 22 October 2008

⁵⁰⁰ Section 10.33 amended by WAGG No 180, 22 October 2008

- 10.35 An *applicant* may, within 5 *business days* after an award is made which orders the parties to enter into an *access contract*, elect not to enter into an *access contract* as specified by the award by giving written notice of the election to the *arbitrator* and the *service provider*, in which case (subject to any *applications and queuing policy* provisions about lapse of *access applications* due to passage of time) the *applicant's access application* remains in effect.
- 10.36 Unless the *applicant* elects not to be bound by an award in accordance with section 10.35, if the award orders the parties to enter into an *access contract* then the *service provider* and *applicant* must enter into an *access contract* in the form specified in the award within 15 *business days* after it is made.

Costs of arbitration

- 10.37 Subject to sections 10.38 and 10.39, the costs of an arbitration (including the fees and costs of the *arbitrator*, if the parties are required to pay the fees and costs) are to be determined in the discretion of the *arbitrator* who may:
- (a) direct to and by whom and in what manner the whole or any part of the costs is to be paid; and
 - (b) fix or settle the amount of costs to be so paid or any part of the costs; and
 - (c) award costs to be fixed or settled as between party and party or as between solicitor and client; and
 - (d) award costs by reference to the Legal Practitioners (Supreme Court) (Contentious Business) Determination 2002 as amended or substituted from time to time.
- 10.38 The costs of complying with Subchapter 10.3 are to be borne equally by the parties unless the *arbitrator* considers there are compelling *reasons* to order otherwise.
- 10.39 If an award is made substantially in the form sought by an *applicant*, and the *applicant* elects under section 10.35 not to be bound by the award, then the fees and costs of the *arbitrator*, to the extent the parties are required to pay the fees and costs, are to be borne by the *applicant* unless the *arbitrator* considers there are compelling *reasons* to order otherwise.

Subchapter 10.3 – Application of the regulatory test in an arbitration

Arbitrator must make proposed award if award would require major augmentation

- 10.40 Before making an award under section 10.33 that would require a *service provider* to undertake a *major augmentation*, the *arbitrator* must:
- (a) make and provide to the parties to the dispute a *proposed award*; and
 - (b) direct the *service provider* to apply the process outlined in section 10.41 in relation to the *major augmentation* in the *proposed award* and specify a time by which the *service provider* must complete each step in the process.

Service provider must consult and submit major augmentation report

- 10.41 The *service provider* must, within the time specified by the *arbitrator*:
- (a) conduct a consultation process in respect of the *major augmentation* in the *proposed award* which complies with section 9.16(c); and
 - (b) then, submit a *major augmentation report* to the *Authority* that:
 - (i) demonstrates compliance with section 10.41(a); and
 - (ii) states whether, in the *service provider's* view, the *major augmentation* in the *proposed award* maximises the *net benefit after considering alternative options*.
- 10.42 The *service provider* must use its best endeavours to ensure that there are no unnecessary or unreasonable costs or delays in complying with section 10.41.

Service provider's costs of compliance, if applicant withdraws

- 10.43 If an *applicant* withdraws its notice of an *access dispute* under section 10.5 and the *service provider*:
- (a) has complied with sections 10.41 and 10.42; or
 - (b) is in the process of complying with section 10.41 and 10.42,
- then the *applicant* must indemnify the *service provider* for the *service provider's* costs of complying with sections 10.41 and 10.42 up to the date that the *service provider* receives the withdrawal notice.

Authority must publish determination regarding major augmentation report

- 10.44 The *Authority* must in respect of a *major augmentation* report make and *publish* a determination whether the test in section 10.46 is satisfied or is not satisfied, and must do so:
- (a) if the *Authority* has consulted the public under section 10.45 — within 45 *business days*; and
 - (b) otherwise — within 25 *business days*,
- after receiving the *major augmentation proposal*.
- 10.45 The *Authority* may consult the public under Appendix 7 before making a determination under section 10.44.
- 10.46 The test in this section 10.46 is satisfied if the *Authority* is satisfied that:
- (a) the *service provider's* statement under section 10.41(b)(ii) is defensible; and
 - (b) the *service provider* has applied the *regulatory test* properly to the *major augmentation* in the *proposed award*:

- (i) using reasonable market development scenarios which incorporate varying levels of demand growth at relevant places; and
- (ii) using reasonable timings, and testing alternative timings, for project commissioning dates and construction timetables for the *major augmentation* and for *alternative options*;

and

- (c) the consultation process conducted by the *service provider* under section 10.41(a) meets the criteria in section 9.16(c).

10.47 The *Authority* must make a determination under section 10.44 on the basis of all the material before it and must have regard to, but is not bound by, the *service provider's* view under section 10.41(b)(ii).

10.48 The *Authority* must give the *arbitrator* and the parties to the dispute a copy of its determination under section 10.44.

10.49 If the *Authority* is unable to make a determination under section 10.44 because the *service provider* has not provided adequate information (despite the *Authority's* having notified the *service provider* of this fact and given the *service provider* a reasonable opportunity, having regard to the time periods specified in section 10.44, to provide adequate information), then the *Authority*:

- (a) must notify the *arbitrator* and the parties to the dispute of the fact and provide a description of the circumstances; and
- (b) is not required to make a determination under section 10.44 in relation to the *major augmentation* in the *proposed award*.

Arbitrator must have regard to Authority's determination

10.50 In determining whether to make an award that would have the effect of requiring the *service provider* to undertake the *major augmentation* described in the *proposed award* or an *augmentation* of a different nature (whether a *major augmentation* or not) the *arbitrator* must have regard to, but is not bound by, the *Authority's* determination under section 10.44.

10.51 For the purposes of section 10.50, without limiting the matters to which the *arbitrator* must or may have regard, the *arbitrator* may have regard to the manner in which the *service provider* complied with sections 10.41 and 10.42.

Subchapter 10.4 – Contractual Disputes

Jurisdiction of arbitrator

10.52 The *arbitrator* has jurisdiction to hear a *contractual dispute*.

Procedural rules

10.53 Except to the extent that the *contract for services* provides otherwise, sections 10.3 to 10.6 and Appendix 5 apply to the *arbitrator's* hearing of a *contractual dispute*, with

appropriate modifications including the substitution of “*contractual dispute*” for all references to “*access dispute*”.⁵⁰¹

⁵⁰¹ Section 10.53 amended by WAGG No 180, 22 October 2008

Chapter 11 – Service standards

Service provider must comply with service standards

- 11.1 A *service provider* must provide *reference services* at a service standard at least equivalent to the *service standard benchmarks* set out in the *access arrangement* and must provide *non-reference services* to a service standard at least equivalent to the service standard in the *access contract*.

Authority to monitor service standards

- 11.2 The *Authority* must monitor and, at least once each year, *publish* a *service provider's* actual service standard performance against the *service standard benchmarks*.
- 11.3 The *Authority* may, acting reasonably, request a “***service standard performance report***” from a *service provider* for the purposes of monitoring the *service provider's* actual service standard performance and the *service provider* must provide the *Authority* with a *service standard performance report* within the time specified by the *Authority* in its request, which time must not be less than 20 *business days*.
- 11.4 In a request under section 11.3 the *Authority* may specify:
- (a) a period of time which must be covered in the *service standard performance report*; and
 - (b) criteria to be addressed in the *service standard performance report*; and
 - (c) the format required for the *service standard performance report*, and the *service provider* must comply with the *Authority's* specifications.
- 11.5 The *Authority* may from time to time, for the purposes of monitoring a *service provider's* actual service standard performance:
- (a) consult with *users* of the *service provider's* network; and
 - (b) *publish* a request for submissions from *consumers* supplied using the network.⁵⁰²

Penalties for breach of service standards

- 11.6 If a *service provider* does not comply with section 11.1, then in order to minimise the likelihood of the *service provider* being excessively penalised for its failure to comply with section 11.1, the *Authority* must have regard to:
- (a) any remedies awarded (or likely to be awarded) against the *service provider* under contracts for *services* in relation to the act or omission which resulted in the *service provider* not complying with section 11.1; and

⁵⁰² Section 11.5 amended by WAGG No 157, 18 September 2020

(b) the *service standards adjustment mechanism*,

before determining whether to impose a civil penalty under regulations made under section 118(2) of the Act.

Chapter 12– Technical Rules

Objectives of the technical rules

- 12.1 The objectives for *technical rules* are that they:
- (a) are reasonable; and
 - (b) do not impose inappropriate barriers to entry to a market; and
 - (c) are consistent with *good electricity industry practice*; and
 - (d) are consistent with relevant *written laws* and *statutory instruments*.
- 12.2 The *Authority* must not approve *technical rules* for a network unless it determines that the *technical rules*:
- (a) if the network is part of an *interconnected system* — work in an integrated fashion with the *technical rules* governing all interconnected networks; and
 - (b) reasonably accommodate the interconnection of further networks in the future.
- 12.3 The *Authority* must not approve *technical rules* for a network which would, if approved, require the *service provider* or another person to engage in an act or omit to engage in an act which would contravene a *written law* or a *statutory instrument*.

Persons bound by technical rules

- 12.4 Subject to section 12.4A and any exemptions granted under sections 12.34 and 12.41, the *service provider* and *users* of a network must comply with the *technical rules*.⁵⁰³

Limited application of technical rules in respect of certain non-covered networks in an interconnected system⁵⁰⁴

- 12.4A A *user* referred to in section 12.4 is a *service provider* of a *non-covered network* that connects to a *covered network* at a point (“**point of interconnection**”) then —
- (a) subject to section 12.4A(b), the *user* is not obliged to comply with the *covered network's technical rules* generally in respect of its operations and maintenance of the *non-covered network*, or to procure compliance with the *technical rules* by other persons; but
 - (b) the *user* must —
 - (i) ensure that its performance at the point of interconnection (as measured at the point of interconnection or, where appropriate,

⁵⁰³ Section 12.4 amended by WAGG No 183, 21 November 2014

⁵⁰⁴ Heading to section 12.4A inserted by WAGG No 183, 21 November 2014

elsewhere on the *covered network*) complies with the *technical rules*; and

- (ii) procure that its *users* and any other person with whom it has a contract for the provision of any good or service in relation to the *non-covered network*, operate in such a way as to allow it to comply with the obligation in section 12.4A(b)(i).⁵⁰⁵

Technical rules prevail over contract

12.5 If the provisions of a *contract for services* provided by means of a *covered network* are inconsistent with the *technical rules* for the network, then the contract is by force of this section amended from time to time to the extent necessary to comply with the *technical rules* except to the extent that section 12.4A, or an exemption to the *technical rules* granted under section 12.34 or 12.41, affects the contract.⁵⁰⁶

Covered networks must have technical rules⁵⁰⁷

12.6 Subject to this Chapter 12, a *covered network* must have *technical rules*.⁵⁰⁸

[Heading not used]⁵⁰⁹

12.6A [not used]⁵¹⁰

12.7 [not used]⁵¹¹

12.8 [not used]⁵¹²

12.8A [not used]⁵¹³

12.8B [not used]⁵¹⁴

⁵⁰⁵ Section 12.4A inserted by WAGG No 183, 21 November 2014

⁵⁰⁶ Section 12.5 amended by WAGG No 180, 22 October 2008; Section 12.5 amended by WAGG No 183, 21 November 2014

⁵⁰⁷ Heading to section 12.6 amended by WAGG No 183, 21 November 2014

⁵⁰⁸ Section 12.6 amended by WAGG No 180, 22 October 2008; Note to section 12.6 deleted by WAGG No 180, 22 October 2008; Section 12.6 amended by WAGG No 183, 21 November 2014

⁵⁰⁹ Heading to section 12.6A inserted by WAGG No 180, 22 October 2008; Heading to section 12.6A deleted by WAGG No 183, 21 November 2014

⁵¹⁰ Section 12.6A inserted by WAGG No 180, 22 October 2008; Section 12.6A deleted by WAGG No 183, 21 November 2014

⁵¹¹ Section 12.7 amended by WAGG No 180, 22 October 2008; Section 12.7 deleted by WAGG No 183, 21 November 2014

⁵¹² Section 12.8 amended by WAGG No 180, 22 October 2008; Section 12.8 deleted by WAGG No 183, 21 November 2014

⁵¹³ Section 12.8A inserted by WAGG No 13, 25 January 2008; Section 12.8A deleted by WAGG No 180, 22 October 2008

⁵¹⁴ Section 12.8B inserted by WAGG No 180, 22 October 2008; Section 12.8B deleted by WAGG No 183, 21 November 2014

12.9 [not used]⁵¹⁵

12.9A [not used]⁵¹⁶

Approval process for technical rules – Covered network

12.10 The *service provider* of a *covered network* must, at the same time as the *service provider* submits its *first access arrangement* under section 4.1, submit proposed *technical rules* to the *Authority*.

12.11 The approval process for *technical rules* submitted by the *service provider* of a *covered network* under section 12.10 is as follows:

- (a) subject to this section 12.11⁵¹⁷, the *technical rules* are, to the extent possible, to be processed in parallel with the *access arrangement*; and
- (b) the Chair of the *technical rules committee* must:
 - (i) within 20 *business days* before the last day by which the *Authority* must make its *draft decision* under section 4.12 — provide a *preliminary report* to the *Authority*; and
 - (ii) within 30 *business days* before the last day by which the *Authority* must make its *final decision* under section 4.18A — provide a *final report* to the *Authority*;⁵¹⁸

and

- (c) the *Authority* must within 15 *business days* after it makes a *draft decision* on the *proposed access arrangement* under section 4.12 *publish* draft *technical rules* which:
 - (i) if the *service provider's* proposed *technical rules* comply with this Chapter 12 and the *Code objective* — must be the *service provider's* proposed *technical rules*; and
 - (ii) otherwise — must be drafted by the *Authority* and based on the *service provider's* proposed *technical rules* and amended only to the extent necessary to comply with this Chapter 12 and the *Code objective*,

and at the same time the *Authority* must *publish* an invitation for submissions on the draft *technical rules*; and

- (d) a person may make a submission to the *Authority* on the draft *technical rules* within 15 *business days* after the invitation is *published* under section 12.11(c); and

⁵¹⁵ Section 12.9 amended by WAGG No 180, 22 October 2008; Section 12.9 deleted by WAGG No 183, 21 November 2014

⁵¹⁶ Section 12.9A inserted by WAGG No 180, 22 October 2008; Section 12.9A deleted by WAGG No 183, 21 November 2014

⁵¹⁷ Section 12.11 amended by WAGG No 207, 8 November 2005

⁵¹⁸ Section 12.11 amended by WAGG No 157, 18 September 2020

- (e) the *Authority* must consider any submissions on the draft *technical rules* made under section 12.11(d) and must, at the same time as it approves an *access arrangement* under section 4.17 or section 4.18, as applicable, approve and *publish* final *technical rules* which must be based on the draft *technical rules* and amended only to the extent necessary to comply with this Chapter 12 and the *Code objective*.⁵¹⁹
- 12.12 If the *Authority* drafts and approves an *interim access arrangement* under section 4.59 for a *covered network*:
- (a) the *Authority* must not draft, approve, or *publish technical rules* for the *covered network*; and
 - (b) any existing technical regulation continues to apply to the *covered network* until such time as an *access arrangement* is subsequently approved under Chapter 4.
- 12.13 If the *Authority* drafts and approves its own *access arrangement* under section 4.55 for a *covered network*, when the *Authority* consults the public under Appendix 7, the *Authority* must:
- (a) if it makes a draft decision under Appendix 7:
 - (i) draft and *publish* draft *technical rules* at the same time as it makes its draft decision; and
 - (ii) *publish* an invitation for submissions on the draft *technical rules* at the same time that it *publishes* an invitation for submissions on its draft decision under Appendix 7;and
 - (b) consider any submissions and draft, approve and *publish* final *technical rules* at the same time it makes and *publishes* its final decision under Appendix 7.

[Heading not used]⁵²⁰

12.13A [not used]⁵²¹

12.13B [not used]⁵²²

Have regard to current regulation in case of deadlock

12.14 Where —

⁵¹⁹ Section 12.11 amended by WAGG No 134, 30 July 2021

⁵²⁰ Heading to section 12.13A inserted by WAGG No 180, 22 October 2008; Heading to section 12.13A deleted by WAGG No 183, 21 November 2014

⁵²¹ Section 12.13A inserted by WAGG No 180, 22 October 2008; Section 12.3A deleted by WAGG No 183, 21 November 2014

⁵²² Section 12.13B inserted by WAGG No 180, 22 October 2008; Section 12.13B deleted by WAGG No 183, 21 November 2014

- (a) the *Authority* is required under this Chapter 12 to draft or approve *technical rules* for a *covered network*; and
- (b) the *technical rules committee* is in *deadlock* in relation to a matter on which it is required to provide advice to the *Authority*,

then the *Authority*, when drafting and approving *technical rules* for the *covered network*, must have regard to whether the current treatment of the matter referred to in section 12.14(b) under another instrument should be replicated in the *technical rules* but may permit replication only to the extent that the treatment of that matter in that instrument is not contrary to the *Code objective*.⁵²³

Commencement of technical rules

12.15 When the *Authority* approves *technical rules* for a *covered network*, it must specify a *technical rules start date* for the *technical rules*, which must be:

- (a) consistent with the *Code objective*; and
- (b) at least 30 *business days* after the approval is *published*.⁵²⁴

Technical rules committee

12.16 Subject to this Chapter 12, the *Authority* may, at any time and from time to time, establish a *technical rules committee* for a *covered network* or an *interconnected system*.⁵²⁵

12.17 The *Authority* must establish a *technical rules committee* for a *covered network* or the *interconnected system* of which the *covered network* is a part to perform the functions described in section 12.23 for the first *technical rules* for a *covered network*:

- (a) if the *covered network* is part of an *interconnected system*; or
- (b) if the *service provider* of the *covered network* requests the *Authority* to establish a *technical rules committee* for the *covered network* or *interconnected system*.

12.18 A *technical rules committee* established under section 12.17 must be established in sufficient time for the *technical rules committee* to perform the functions described in section 12.23 for the first *technical rules* for the *covered network*.

12.19 A *technical rules committee*:

- (a) must consist of at least:
 - (i) a representative of the *service provider*; and
 - (ii) [not used]; and

⁵²³ Section 12.14 amended by WAGG No 180, 22 October 2008; Section 12.14 amended by WAGG No 183, 21 November 2014

⁵²⁴ Section 12.15 amended by WAGG No 183, November 2014

⁵²⁵ Section 12.16 amended by WAGG No 183, 21 November 2014

- (iii) at least one person representing users of the network; and
 - (iv) a representative of the Coordinator; and
 - (v) a representative of *AEMO*;
 - and
 - (b) may consist of any other person that the *Authority* considers appropriate, and a person on a *technical rules committee* is a “**member**” of the *technical rules committee*.⁵²⁶
- 12.19A The *Authority* may determine that a member of a *technical rules committee* is to receive remuneration or an allowance and the *Authority* may fix the amount of that remuneration or allowance.⁵²⁷
- 12.19B Subject to section 12.19C, when establishing a *technical rules committee*, the *Authority* must set the terms of reference for a *technical rules committee* which must include, at a minimum, requirements in respect of:
- (a) frequency of meetings; and
 - (b) meeting procedures.⁵²⁸
- 12.19C The terms of reference for a *technical rules committee* must provide:
- (a) that, notwithstanding that the *Authority* may require additional members, the quorum of a *technical rules committee* will consist of the representatives in section 12.19(a)(i), 12.19(a)(iv) and 12.19(a)(v); and
 - (b) that the *technical rules committee* may establish one or more subcommittees in the performance of its duties but only with the prior consent of the *Authority*.⁵²⁹
- 12.20 The Chair of a *technical rules committee* is the person who, at that time, is the member of the *technical rules committee* that is the representative of the *Coordinator*.⁵³⁰
- 12.21 Any communication to the *Authority* from a *technical rules committee* must be provided to the *Authority* by the Chair of the *technical rules committee* and not by any other member.
- 12.22 A person who is represented on, or is a member of, a *technical rules committee* is not precluded from making submissions to the *Authority* in relation to proposed *technical rules* in a capacity other than as a person who is represented on, or is a member of, the *technical rules committee*.

⁵²⁶ Section 12.19 amended by WAGG No 157, 18 September 2020

⁵²⁷ Section 12.19A inserted by WAGG No 157, 18 September 2020

⁵²⁸ Section 12.19B inserted by WAGG No 157, 18 September 2020

⁵²⁹ Section 12.19C inserted by WAGG No 157, 18 September 2020

⁵³⁰ Section 12.20 amended by WAGG No 157, 18 September 2020

- 12.23 A *technical rules committee*, in performing its functions under section 12.11(b) and 12.51B and if otherwise requested:
- (a) [not used]
 - (b) [not used]
 - (c) must, when requested by the *Authority*, advise the *Authority* on any matter connected with the *approval* of, or decision not to approve, *technical rules* or draft or proposed *technical rules* or a proposal to amend *technical rules*; and
 - (d) must, when requested by the *Authority*, conduct a *review* of the operation of:
 - (i) technical rules or a part of technical rules; or
[not used]
 - (ii) this Chapter 12 or a part of this Chapter 12,
and advise the *Authority* of the outcome of the *review*; and⁵³¹
 - (e) must, when requested by the *Authority*:
 - (i) assist a person to comply with the processes and procedures developed and published under section 12.50A; and
 - (ii) request further information from a person in respect of a proposal to amend *technical rules* in accordance with section 12.50F.⁵³²
- 12.24 A *technical rules committee* must perform the functions described in section 12.23 in accordance with the objectives in section 12.1.
- 12.25 In the case of *deadlock*, the Chair of the *technical rules committee* must advise the *Authority* of:
- (a) the details of the *deadlock*; and
 - (b) the position held by each member of the *technical rules committee* on the matter the subject of the *deadlock*.
- 12.26 If the *Authority* is advised of a *deadlock* under section 12.25, it must form a view on the matter the subject of the *deadlock* and advise the *technical rules committee* of its view, and the *technical rules committee* must proceed on the basis of the view advised to it.
- 12.27 The *Authority* may:
- (a) from time to time, subject to section 12.19C, amend any terms of reference for a *technical rules committee* or provide directions to a *technical rules committee* in relation to:

⁵³¹ Section 12.23 amended by WAGG No 180, 22 October 2008; Section 12.23 amended by WAGG No 183, 21 November 2014

⁵³² Section 12.23 amended by WAGG No 157, 18 September 2020

- (i) the procedures it must follow in performing its functions; and
 - (ii) the manner in which it must perform its functions; and
- (b) dissolve, alter or reconstitute a *technical rules committee*.⁵³³

Recommendations from the technical rules committee

12.28 The *Authority* must have regard to any advice provided by the *technical rules committee* under section 12.23:⁵³⁴

- (a) in deciding whether to approve or not approve proposed *technical rules* for a network; and
- (b) in deciding whether to approve or not approve a proposal to amend *technical rules* for a network; and⁵³⁵
- (c) in drafting its own *technical rules* for a network.

12.29 Section 12.28 does not limit the matters to which the *Authority* must or may have regard.

Authority may observe the technical rules committee

12.30 Subject to section 12.31, the *Authority* may appoint a representative to observe any aspect of the operation of the *technical rules committee*, including by:

- (a) attending any meeting of the *technical rules committee*; and
- (b) inspecting any documents (including working papers) provided to or by the *technical rules committee* in the performance of its functions.

12.31 A representative of the *Authority* under section 12.30 must not participate in any decision making process of the *technical rules committee*.

Scope and content of technical rules

12.32 Unless a different form of *technical rules* will better achieve the *Code objective* or the objectives set out in section 12.1, the *technical rules* must address the matters listed in Appendix 6.

Person applies to service provider for exemption from technical rules

12.33 A *user*, *applicant* or controller may apply to a *service provider* for an exemption from one or more requirements of *technical rules*.

12.34 A *service provider* must as soon as practicable determine an application under section 12.33:

⁵³³ Section 12.27 amended by WAGG No 157, 18 September 2020

⁵³⁴ Section 12.28 amended by WAGG No 180, 22 October 2008

⁵³⁵ Section 12.28 amended by WAGG No 157, 18 September 2020

- (a) as a *reasonable and prudent person* on reasonable technical and operational grounds; and
- (b) having regard to the effect the proposed exemption will, if granted, have on the *service providers* and *users* of the *covered network* and any interconnected network,⁵³⁶

and must grant the exemption if the *service provider* determines that in all the circumstances the disadvantages of requiring the person applying for the exemption to comply with the requirement are likely to exceed the advantages.

12.35 An exemption under section 12.34:

- (a) may be granted for a specified period or indefinitely; and
- (b) may be subject to any reasonable conditions the *service provider* considers fit, in which case the person granted the exemption must comply with the conditions, or may be unconditional; and
- (c) may be varied or revoked by the *service provider* after reasonable notice to the person granted the exemption.

12.36 A *service provider* must notify a person applying for an exemption of its determination under section 12.33 as soon as practicable after making the determination.

12.37 A person may apply to a *service provider* for an exemption granted to a person under section 12.34 to be revoked and the *service provider* must consider the application and within a reasonable time advise the person of the *service provider's* determination in relation to the application.

12.38 A *service provider* must provide to the *Authority* a notice giving details of any grant, revocation or variation of an exemption under section 12.34 or 12.35(c) and the *Authority* must place the notice on the *public register*.

12.39 Without limiting the generality of the type of exemptions that may be granted under section 12.34, exemptions to *technical rules* may be transitional in nature and may include provisions allowing a person time to comply with the *technical rules*.

Service provider applies to Authority for authorisation to grant exemption from technical rules

12.40 A *service provider* may apply to the *Authority* for an exemption from one or more requirements of *technical rules* for the *service provider* and all *applicants*, *users* and controllers of the *covered network* (“**network persons**”).

12.41 The *Authority* must as soon as practicable determine an application under section 12.40:

- (a) as a *reasonable and prudent person* on reasonable technical and operational grounds; and

⁵³⁶ Section 12.34 amended by WAGG No 183, 21 November 2014

- (b) having regard to the effect the proposed exemption will, if granted, have on the *service providers* and *users* of the *covered network* and any interconnected network,⁵³⁷

and must grant the exemption if the *Authority* determines that in all the circumstances the disadvantages of requiring the network persons to comply with the requirement are likely to exceed the advantages.

12.42 The *Authority* may refer a *service provider's* application under section 12.40 to the *technical rules committee* and request the *technical rules committee's* advice on the application and must, subject to complying with the time limit under section 12.44, have regard to the advice of the *technical rules committee* in making its determination under section 12.41.

12.43 An exemption under section 12.41:

- (a) may be granted for a specified period or indefinitely; and
- (b) may be subject to any reasonable conditions the *service provider* considers fit, in which case the network persons must comply with the conditions, or may be unconditional; and
- (c) may be varied or revoked by the *service provider* after reasonable notice to the network persons.

12.44 The *Authority* must notify the *service provider* of its determination under section 12.41:

- (a) where the *Authority* has consulted the public in accordance with Appendix 7 — within 45 *business days* of receiving the application under section 12.40; or
- (b) where the *Authority* has not consulted the public in accordance with Appendix 7 — within 25 *business days* of receiving the application under section 12.40.⁵³⁸

12.45 A person may apply to the *Authority* for an exemption granted in respect of a *covered network* under section 12.41 to be revoked and the *Authority* must consider the application and within a reasonable time advise the person of the *Authority's* determination in relation to the application.⁵³⁹

12.46 Before granting, varying or revoking an exemption under section 12.41, the *Authority* may consult the public in accordance with Appendix 7.

12.47 The *Authority* must *publish* a notice giving details of any grant, revocation or variation of an exemption under section 12.41.

12.48 Without limiting the generality of the type of exemptions that may be granted under section 12.41, exemptions to *technical rules* may be transitional in nature and may include provisions allowing network persons time to comply with *technical rules*.

⁵³⁷ Section 12.41(b) amended by WAGG No 183, 21 November 2014

⁵³⁸ Section 12.44(b) amended by WAGG No 180, 22 October 2008

⁵³⁹ Section 12.45 amended by WAGG No 183, 21 November 2014

12.49 If the *Authority* grants an exemption under section 12.41, then the *arbitrator* may have regard to the waiver in making an award in any *access dispute* relating to the *covered network*.⁵⁴⁰

Amendments to technical rules

12.50 A proposal to amend *technical rules* may be submitted to the *Authority* at any time by any interested person and must be placed on the *public register*.⁵⁴¹

12.50A The *Authority* may develop and *publish* processes and procedures outlining the requirements for proposals to amend *technical rules* which must be adhered to by any interested person submitting a proposal to amend *technical rules*.⁵⁴²

12.50B The *Authority* may amend any processes and procedures developed and published under section 12.50A by *publishing* a new process or procedure or by *publishing* amendments to existing processes and procedures.⁵⁴³

12.50C The *Authority* may, but is not obliged to:

- (a) assist a person to comply with the processes and procedures developed and published under section 12.50A; or
- (b) request the *technical rules committee* to assist a person to comply with the processes and procedures developed and published under section 12.50A.⁵⁴⁴

12.50D A proposal to amend *technical rules* will only be deemed to be submitted once the *Authority* considers that it is complete and meets the requirements of any processes and procedures developed and published by the *Authority* under section 12.50A.⁵⁴⁵

12.50E The *Authority* must place a proposal to amend *technical rules* on the *public register* once it is deemed to be submitted in accordance with section 12.50D.⁵⁴⁶

12.50F The *Authority*, or the *technical rules committee* if requested by the *Authority*, may, after a proposal to amend *technical rules* is deemed to be submitted to the *Authority* in accordance with section 12.50D, request further information from the person who submitted the proposal to amend *technical rules*.⁵⁴⁷

12.51 The *Authority*, by *publishing* a notice, may reject a proposal to amend *technical rules* if, in the *Authority's* opinion, the proposal:

- (a) is misconceived or lacking in substance; or
- (b) has been made on trivial or vexatious grounds; or

⁵⁴⁰ Section 12.49 amended by WAGG No 183, 21 November 2014

⁵⁴¹ Section 12.50 amended by WAGG No 157, 18 September 2020

⁵⁴² Section 12.50A inserted by WAGG No 157, 18 September 2020

⁵⁴³ Section 12.50B inserted by WAGG No 157, 18 September 2020

⁵⁴⁴ Section 12.50C inserted by WAGG No 157, 18 September 2020

⁵⁴⁵ Section 12.50D inserted by WAGG No 157, 18 September 2020

⁵⁴⁶ Section 12.50E inserted by WAGG No 157, 18 September 2020

⁵⁴⁷ Section 12.50F inserted by WAGG No 157, 18 September 2020

- (c) has not been developed in accordance with the processes and procedures developed and published by the *Authority* under section 12.50A; or
- (d) is materially similar to, or seeks to address the same or similar issues or provisions in *technical rules*:
 - (i) currently being considered by the *Authority* under an alternative proposal to amend *technical rules*; or
 - (ii) which have been considered by the *Authority* in the previous 12 months.⁵⁴⁸

12.51A The *Authority*:

- (a) may at the same time and as part of the same assessment process, consider multiple proposals to amend *technical rules* that are similar or seek to address the same or similar issues or provisions of the *technical rules*; and
- (b) is not required to consider proposals to amend *technical rules* in the order in which they are received by the *Authority*.⁵⁴⁹

12.51B The *Authority* must request the advice of the *technical rules committee* in respect of any proposals to substantially amend *technical rules* that the *Authority* does not reject in accordance with section 12.51.⁵⁵⁰

12.51C The *Authority* must provide the *technical rules committee* with a time by which to provide the advice requested under section 12.51B, which must take into account the scope and complexity of the proposal to amend the *technical rules*, and be not less than 15 *business days*.⁵⁵¹

12.51D The *technical rules committee* may request the *Authority* to provide additional time to consider the proposal to amend *technical rules* and the *Authority* must act reasonably in considering any request for additional time.⁵⁵²

12.51E The *Authority* may, acting reasonably, make a decision on a proposal to amend *technical rules* without the advice of the *technical rules committee* if the *technical rules committee* does not provide the advice requested under section 12.51B within the required timeframe, including any additional time provided in accordance with section 12.51D.⁵⁵³

12.51F The *Authority* is required to place on the *public register*:

- (a) any advice received from the *technical rules committee* in respect of any proposals to amend *technical rules* requested under section 12.51B;

⁵⁴⁸ Section 12.51 amended by WAGG No 157, 18 September 2020

⁵⁴⁹ Section 12.51A inserted by WAGG No 157, 18 September 2020

⁵⁵⁰ Section 12.51B inserted by WAGG No 157, 18 September 2020

⁵⁵¹ Section 12.51C inserted by WAGG No 157, 18 September 2020

⁵⁵² Section 12.51D inserted by WAGG No 157, 18 September 2020

⁵⁵³ Section 12.51E inserted by WAGG No 157, 18 September 2020

- (b) any other advice taken into account in making a final decision in respect of a proposal to amend *technical rules*, except to the extent that it includes *confidential material*; and
 - (c) if applicable, the reasons why the *Authority* made a decision on a proposal to amend *technical rules* without the advice of the *technical rules committee* in accordance with section 12.51E.⁵⁵⁴
- 12.52 At any time before the *review* under section 12.56 commences, the *Authority* may decide to defer consideration of a proposal to amend the *technical rules* for the *Western Power Network* until the *review* if, in the *Authority's* opinion, deferring consideration of the proposal would better achieve the *Code objective*.⁵⁵⁵
- 12.53 As soon as practicable, the *Authority* must consider whether any amendments to *technical rules* proposed under section 12.50, and not rejected under section 12.51, are consistent with this Chapter 12 and the *Code objective*, having regard, among other things, to section 12.4A and any exemptions granted under sections 12.34 and 12.41, and then either:⁵⁵⁶
- (a) approve the proposed amendments to the *technical rules* in the proposed form; or
 - (b) approve the proposed amendments to the *technical rules* in a modified form; or
 - (c) not approve the proposed amendments to the *technical rules*,
by *publishing* a notice of its decision, and if the decision was to approve the proposed amendments, the date on which the amendments commence.⁵⁵⁷
- 12.54 If the *Authority* considers a proposed amendment to *technical rules* to be substantial, the *Authority*:
- (a) must consult the public in accordance with Appendix 7 (as if sections A7.12, A7.18, A7.19, A7.23 and A7.24 do not apply) before making a decision to approve or not approve the proposed amendment; and
 - (b) [not used].⁵⁵⁸
- 12.54A The *Authority* will use reasonable endeavours to assess and make a final decision in respect of all proposals to amend *technical rules* within 150 *business days* from the date the proposal to amend *technical rules* is deemed to be submitted to the *Authority* in accordance with section 12.50D.⁵⁵⁹

⁵⁵⁴ Section 12.51F inserted by WAGG No 157, 18 September 2020

⁵⁵⁵ Section 12.52 amended by WAGG No 180, 22 October 2008

⁵⁵⁶ Section 12.53 amended by WAGG No 183, 21 November 2014

⁵⁵⁷ Section 12.53 amended by WAGG No 157, 18 September 2020

⁵⁵⁸ Section 12.54 amended by WAGG No 157, 18 September 2020; Section 12.54 amended by WAGG No 134, 30 July 2021

⁵⁵⁹ Section 12.54A inserted by WAGG No 157, 18 September 2020

Notification of changes to technical laws

12.55 If a representative of the Coordinator notifies the *Authority* of a material change to a relevant *written law* or *statutory instrument* which the Coordinator's representative considers may affect the operation of *technical rules* for one or more *covered networks* ("**material change**"), then the *Authority* must refer the material change to one or more appropriately constituted *technical rules committees* for advice which must be provided to the *Authority* in a reasonable time and may include a proposal to amend the *technical rules* for one or more *covered networks* under section 12.50. ⁵⁶⁰

Review of technical rules

12.56 The *Authority* must cause a *review* of the *technical rules* for the *Western Power Network* to be carried out approximately 6 months before the *target revisions commencement date* in the *first access arrangement* for the *covered network*. ⁵⁶¹

12.57 The purpose of the *review* under section 12.56 is:

- (a) to assess the effectiveness of the *technical rules* in achieving the objectives in section 12.1 and the *Code objective*; and
- (b) to consider any proposals to amend the *technical rules* which have been deferred under section 12.52.

12.58 The *Authority* may carry out the *review* under section 12.56 in the manner it considers best achieves the *Code objective*.

Coordination with other service providers in an interconnected system

12.59 A *service provider* that operates a network in an *interconnected system* must cooperate with a *service provider* of an interconnected network ("**other service provider**") to the standard of a *reasonable and prudent person*.

12.60 In complying with section 12.59, a *service provider* must:

- (a) cooperate with an other *service provider* who is *processing* an *access application* to enable the other *service provider* to *process* the *access application* expeditiously; and
- (b) liaise as necessary with other *service providers* in relation to:
 - (i) [not used];⁵⁶²
 - (ii) the planning and development of interconnected networks.

⁵⁶⁰ Section 12.55 amended by WAGG No 183, 21 November 2014

⁵⁶¹ Section 12.56 amended by WAGG No 180, 22 October 2008

⁵⁶² Section 12.60 amended by WAGG No 157, 18 September 2020

[Heading not used]⁵⁶³

12.61 [not used]⁵⁶⁴

12.62 [not used]⁵⁶⁵

[Heading not used]⁵⁶⁶

12.63 [not used]⁵⁶⁷

12.64 [not used]⁵⁶⁸

[Heading not used]⁵⁶⁹

12.65 [not used]⁵⁷⁰

12.66 [not used]⁵⁷¹

12.67 [not used]⁵⁷²

[Heading not used]⁵⁷³

12.68 [not used]⁵⁷⁴

⁵⁶³ Heading to section 12.61 inserted by WAGG No 180, 22 October 2008; Heading to section 12.61 deleted by WAGG No 183, 21 November 2014

⁵⁶⁴ Section 12.61 inserted by WAGG No 180, 22 October 2008; Section 12.61 deleted by WAGG No 183, 21 November 2014

⁵⁶⁵ Section 12.62 inserted by WAGG No 180, 22 October 2008; Section 12.62 deleted by WAGG No 183, 21 November 2014

⁵⁶⁶ Heading to section 12.63 inserted by WAGG No 180, 22 October 2008; Heading to section 12.63 deleted by WAGG No 183,

⁵⁶⁷ Section 12.63 inserted by WAGG No 180, 22 October 2008; Section 12.63 deleted by WAGG No 183, 21 November 2014

⁵⁶⁸ Section 12.64 inserted by WAGG No 180, 22 October 2008; Section 12.64 deleted by WAGG No 183, 21 November 2014

⁵⁶⁹ Heading to Section 12.65 inserted by WAGG No 180, 22 October 2008; Heading to section 12.65 deleted by WAGG No 13, 21 November 2014

⁵⁷⁰ Section 12.65 inserted by WAGG No 180, 22 October 2008; Section 12.65 deleted by WAGG No 183, 21 November 2014

⁵⁷¹ Section 12.66 inserted by WAGG No 180, 22 October 2008; Section 12.66 deleted by WAGG No 183, 21 November 2014

⁵⁷² Section 12.67 inserted by WAGG No 180, 22 October 2008; Section 12.67 deleted by WAGG No 183, 21 November 2014

⁵⁷³ Heading to section 12.68 inserted by WAGG No 22 October 2008; Heading to section 12.68 deleted by WAGG No 183, 21 November 2014

⁵⁷⁴ Section 12.68 inserted by WAGG No 180, 22 October 2008; Section 12.68 deleted by WAGG No 183, 21 November 2014

Support services for technical rules committee⁵⁷⁵

- 12.69 It is a function of the *Authority* to provide support services that a *technical rules committee* reasonably requires for the *technical rules committee* to meet its obligations and functions under the *Code*.⁵⁷⁶
- 12.70 Support services provided to the *technical rules committee* by the *Authority* may include, but are not limited to:
- (a) making staff members available to assist the *technical rules committee*;
 - (b) procuring consultants to assist the *technical rules committee*;
 - (c) making meeting rooms available for the *technical rules committee*;
 - (d) scheduling meetings of the *technical rules committee*; and
 - (e) taking minutes at a meeting of the *technical rules committee*.⁵⁷⁷

Reporting by the Authority⁵⁷⁸

- 12.71 The *Authority* must publish for each financial year:
- (a) the number of proposals to amend *technical rules* received for the financial year; and
 - (b) the number of proposals to amend *technical rules* that were rejected; and
 - (c) the total number of *business days* taken to make a final decision in respect of each proposal to amend *technical rules* from the date of deemed submission; and
 - (d) in respect of proposals to amend *technical rules* where a final decision was not made within 150 *business days* from the date of deemed submission, the number of proposals to amend *technical rules* and the reason the final decision was not made within 150 *business days*.⁵⁷⁹
- 12.72 Where the *Authority*, or the *technical rules committee* acting on the request of the *Authority*, requests further information in respect of a submitted proposal to amend *technical rules* in accordance with section 12.50F, the period of time between the request being made and the provision of the further information requested is not to be taken into account when considering the timeframe taken by the *Authority* to make a final decision in respect of the reporting obligation set out in section 12.71(c) and 12.71(d).⁵⁸⁰

⁵⁷⁵ Heading to section 12.69 inserted by WAGG No 157, 18 September 2020

⁵⁷⁶ Section 12.69 inserted by WAGG No 157, 18 September 2020

⁵⁷⁷ Section 12.70 inserted by WAGG No 157, 18 September 2020

⁵⁷⁸ Heading to section 12.71 inserted by WAGG No 157, 18 September 2020

⁵⁷⁹ Section 12.71 inserted by WAGG No 157, 18 September 2020

⁵⁸⁰ Section 12.72 inserted by WAGG No 157, 18 September 2020

Chapter 13 – Ringfencing

Service provider must comply with ringfencing objectives and rules

- 13.1 Except to the extent that the *Authority* grants an exemption under section 13.31, a *service provider* must, in relation to a *covered network*:
- (a) comply with the *ringfencing objectives*; and
 - (b) if *ringfencing rules* apply to the *covered network* – comply with the *ringfencing rules*.

Application of ringfencing objectives and rules to integrated providers

- 13.2 If the *service provider* for a *covered network* is an *integrated provider*, a reference in this Chapter 13 to an “**associate**” of the *service provider* or of its *network business* includes any *other business* of the *service provider*.

‘Ringfenced business’ defined

- 13.3 In this Chapter 13, “**ringfenced business**” means:
- (a) for an *integrated provider* — the *network business*; or
 - (b) for any other *service provider* — the *service provider*.

Other business must have deemed access contract

- 13.4 If:
- (a) a *service provider* for a *covered network* is an *integrated provider*; and
 - (b) the *network business* provides one or more *covered services* to an *other business*,
- then:
- (c) by 3 months after the *access arrangement start date*, the *network business* and the *other business* must record in writing the full terms and conditions of the arrangement by which the *network business* is to provide the *covered services* to the *other business* (“**deemed access contract**”); and
 - (d) unless the contrary intention appears, a reference in this Code to *access contract* includes a *deemed access contract* under section 13.4(c); and
 - (e) unless the contrary intention appears, a reference in this Code to *user* includes the *other business* under a *deemed access contract* under section 13.4(c).

Associate contracts

- 13.5 Without limiting section 13.4 a *service provider* must, by 3 months after the *access arrangement start date*, record in writing the full terms and conditions of any contract, arrangement or understanding by which it provides *covered services* to an *associate* (“**associate contract**”).

Amendments to associate contracts and deemed access contracts

- 13.6 If an *associate contract* or a *deemed access contract* is amended by agreement between the parties or otherwise varied or terminated, the *service provider* must within 5 *business days* notify the *Authority* that the *associate contract* or a *deemed access contract* has been amended, varied or terminated.

- 13.7 A *service provider* must, if requested by the *Authority*, provide an *associate contract* or a *deemed access contract* to the *Authority* within the time specified by the *Authority*.

- 13.8 The *Authority* must, if it considers that an *associate contract* or a *deemed access contract*:

- (a) is contrary to the *Code objective*; or
- (b) may have been entered into for the purpose of preventing or hindering access by any person to *services*,

require a *service provider*, by notice, to ensure that the *ringfenced business* provides *covered services* to the *associate* on terms and conditions which are not contrary to the *Code objective* and do not have the purpose of preventing or hindering access by any person to *services*, and may, without limiting the *Authority's* powers and subject to section 13.9, specify the terms and conditions for the provision of *covered services* by the *ringfenced business* to the *associate*.

- 13.9 In specifying the terms and conditions for the provision of *covered services* by a *ringfenced business* to an *associate* under section 13.8, the *Authority* must not specify any more changes to the existing terms and conditions than are necessary to ensure that the terms and conditions are not contrary to the *Code objective* and do not prevent or hinder access by any person to *services*.

- 13.10 The *Authority* may consult the public in accordance with Appendix 7 before imposing a requirement under sections 13.8.

Ringfencing objectives

- 13.11 The *ringfencing objectives*, in relation to a *service provider* of a *covered network*, are that:

- (a) the *ringfenced business* must not carry on a *related business*; and
- (b) subject to section 13.11(d), only marketing staff of the *ringfenced business* may have access to or possession of, or make use of, *commercially sensitive information*; and
- (c) subject to section 13.11(d) and any *written law* including this Code, and except to the extent that the information comes into the public domain

otherwise than by disclosure by the *service provider*, *commercially sensitive information*:

- (i) must be used only for the purpose for which that information was developed or provided; and
 - (ii) must not be disclosed to any person (including any servant, consultant, independent contractor or agent of any *associate* of the *ringfenced business*) without the prior consent of the person who provided it or to whom it relates; and
- (d) *commercially sensitive information* may be disclosed to and used by the *service provider's senior staff* but:
- (i) only to the minimum extent necessary from time to time for good corporate governance; and
 - (ii) where possible only in summary or aggregated form or otherwise in a form that minimises the disclosure of any commercially sensitive or confidential details; and
 - (iii) for use only in relation to the *ringfenced business* and only for the purpose for which it was developed or provided,
- (e) any goods or *services* that the *ringfenced business* provides to, or receives from, any *associate* of the *ringfenced business* must be provided or received on terms that would be reasonable if the parties were dealing at arm's length; and
- (f) any goods or *services* that the *ringfenced business* provides to, or receives from, a third party operating in competition with an *associate* of the *ringfenced business* must be provided or received on a basis that does not competitively or financially disadvantage the third party, relative to the *associate*; and
- (g) the *service provider's* accounts and records relating to its *covered network* must be kept in a way that:
- (i) provides a comprehensive view of the *ringfenced business's* legal and equitable rights and liabilities in relation to the *covered network*; and
 - (ii) provides a true and fair view of:
 - A. the *network business* as distinct from any *other business* carried on by the *service provider* or any *associate* of the *service provider*; and
 - B. income derived from, and expenditure relating to, the *covered network*; and
 - C. the *service provider's* assets and liabilities so far as they relate to the *covered network*;
- and

- (iii) provides sufficient information to enable the *price control* and *pricing methods*, and these *ringfencing objectives* and any applicable *ringfencing rules*, to be applied in a reasonable manner; and
 - (iv) enables all revenue received by the *service provider* from the provision of goods or *services* to an *associate* of the *ringfenced business* to be separately identified; and
 - (v) enables all expenditure by the *service provider* on goods or *services* provided by an *associate* of the *ringfenced business* to be separately identified; and
- (h) the *service provider*, when entering into service agreements, including asset management agreements, ensures that the terms and conditions of each agreement facilitates the implementation of these *ringfencing objectives* and any *ringfencing rules*.

Factors the Authority must have regard to

13.12 In exercising its functions under this Chapter 13 the *Authority* must have regard to the geographical location of the *covered network* and the extent (if any) to which it is interconnected with other networks.

13.13 Section 13.12 does not limit the matters to which the *Authority* must or may have regard.

Authority may approve ringfencing rules

13.14 The *Authority*:

- (a) may at any time; and
- (b) must for a *covered network* if it determines that the *ringfencing objectives* are not being achieved for the *covered network*,

draft and approve *ringfencing rules*, for the purpose of ensuring that the *ringfencing objectives* are achieved.

13.15 Without limiting section 13.14, a *service provider* may submit *ringfencing rules* to the *Authority* for approval.

13.16 *Ringfencing rules* may be expressed to apply to:

- (a) one or more specified *covered networks*; or
- (b) all *covered networks* in a specified geographical area or *interconnected system*; or
- (c) any other specified class or classes of *covered networks*,

in each case with or without specified exceptions.

13.17 The *Authority* must not approve *ringfencing rules* which would, if approved, require a *service provider* or other person to engage in an act or omit to engage in an act which would contravene a *written law* or a *statutory instrument*.

- 13.18 The *Authority* may at any time revoke or vary any *ringfencing rules*.
- 13.19 Subject to section 13.20, before approving, revoking or varying *ringfencing rules*, the *Authority* must consult the public in accordance with Appendix 7.
- 13.20 The *Authority* may at any time correct clerical mistakes, or errors arising from accidental slips or omissions, in any *ringfencing rules* without consulting the public in accordance with Appendix 7 if it considers that doing so will not unduly prejudice a person.
- 13.21 The *Authority* must place on the *public register* a copy of any approved, revoked or varied *ringfencing rules*.

Ringfencing rules and compliance procedures are not confidential

- 13.22 *Ringfencing rules* and *ringfencing compliance procedures* :
- (a) are not *confidential material* for the purposes of this Code; and
 - (b) must not be claimed by the *service provider* to be, and are not, confidential in any way.

Additional ringfencing rules for an integrated provider

- 13.23 *Ringfencing rules* which apply to an *integrated provider* may:
- (a) add to the *ringfencing objectives* for the *integrated provider*; and
 - (b) deal with any matter the *Authority* considers necessary or convenient to:
 - (i) achieve the *Code objective* or the *ringfencing objectives*; or
 - (ii) maintain the confidence of those who *generate, transport* or *consume* electricity that the *Code objective* or the *ringfencing objectives* are being achieved;
- and
- (c) without limiting section 13.23(b), require the physical separation of all or part of the *network business's* offices, equipment or marketing staff from those of any *other business*.

- 13.24 Section 13.23 does not limit sections 13.14 to 13.21.

Service provider to procure compliance by its associates

- 13.25 *Ringfencing rules* which apply to a *covered network* may require a *service provider* to procure an *associate* of the *ringfenced business* to comply with any one or more of:
- (a) the *ringfencing objectives*; and
 - (b) any applicable *ringfencing rules*; and
 - (c) the *ringfencing compliance procedures*.

- 13.26 Without limiting section 13.25, *ringfencing rules* which apply to a *covered network* may require a *service provider* to procure any *associate* of the *ringfenced business* that undertakes activities for the *ringfenced business* in relation to the network under service agreements, including asset management agreements:
- (a) to establish and *maintain* a separate set of accounts in respect of the activities undertaken for the *ringfenced business* in relation to the network; and
 - (b) to allocate any costs that are shared between an activity for which accounts are kept under section 13.26(a) and another activity according to a methodology for allocating costs that is transparent; and
 - (c) to provide the accounts established and *maintained* under section 13.26(a) to the *Authority* at the *Authority's* request.

Commencement time for ringfencing rules

- 13.27 An approval, variation or revocation of *ringfencing rules* may be expressed to take effect immediately or at one or more specified times.
- 13.28 If no time is specified, an approval, variation or revocation of the *ringfencing rules* takes effect 3 months after it is placed on the *public register*.

Exemptions from ringfencing requirements

- 13.29 The *Authority* must not grant Electricity Networks Corporation⁵⁸¹ an exemption from this Chapter 13.
- 13.30 A *service provider* may apply to the *Authority* for an exemption from a provision of the *ringfencing objectives* or the *ringfencing rules* in respect of the *covered network*.
- 13.31 Subject to section 13.29, the *Authority* may grant a *service provider* an exemption from a provision of the *ringfencing objectives* or the *ringfencing rules* in respect of a *covered network* if the *Authority* determines in all the circumstances that the disadvantages of requiring the *service provider* to comply with the provision are likely to exceed the advantages.
- 13.32 An exemption under section 13.31:
- (a) may be granted for a specified period or indefinitely;
 - (b) may be unconditional or subject to any conditions the *Authority* considers fit in which case the *service provider* must comply with the conditions; and
 - (c) may be varied or revoked by the *Authority* after reasonable notice to the *service provider*.
- 13.33 A person may apply to the *Authority* for an exemption granted to a *service provider* under section 13.31 to be revoked and the *Authority* must consider the application and within a reasonable time advise the person of the *Authority's* determination in relation to the application.

⁵⁸¹ Section 13.29 amended by WAGG No 59, 31 March 2006

- 13.34 Before granting, varying or revoking an exemption under section 13.31, the *Authority* must consult the public under Appendix 7.
- 13.35 The *Authority* must *publish* details of any grant, revocation or variation of an exemption under section 13.31.
- 13.36 Without limiting the generality of the type of exemptions that may be granted under section 13.31, exemptions to *ringfencing rules* may be transitional in nature and may include provisions allowing a *service provider* time to comply with *ringfencing objectives* or *ringfencing rules*, which time must be as short as the *Authority* considers to be reasonably practicable.

Compliance monitoring and compliance reporting

- 13.37 A *service provider* must:
- (a) establish, *maintain* and implement effective procedures (“***ringfencing compliance procedures***”) to ensure and monitor its compliance with section 13.1; and
 - (b) when requested by the *Authority*, provide a copy of its *ringfencing compliance procedures* to the *Authority*; and
 - (c) at reasonable intervals determined by the *Authority* from time to time, assess its compliance with, and the effectiveness of, its *ringfencing compliance procedures*, and its compliance with section 13.1, and provide a report to the *Authority* regarding the assessment.

{Note: Information provided under section 13.37(c) will be one of the factors considered by the *Authority* under section 13.14(b).}

- 13.38 The *Authority* must place the *service provider’s ringfencing compliance procedures* on the *public register*.
- 13.39 No act or omission by the *Authority* concerning the adequacy or effectiveness of a *service provider’s ringfencing compliance procedures* affects the *service provider’s* obligations under section 13.1.
- 13.40 Nothing in any *ringfencing compliance procedures* limits section 13.1 or 13.14.
- 13.41 The *Authority* may from time to time *publish* guidelines setting out model *ringfencing compliance procedures* and model reporting procedures in relation to *ringfencing compliance procedures*.

Breach of ringfencing requirements

- 13.42 A *service provider* must report to the *Authority* details of any breach of section 13.1 immediately upon becoming aware of the breach.
- 13.43 A person who considers that a *service provider* has breached section 13.1 may provide details of the breach to the *Authority*.
- 13.44 On receipt of details under sections 13.42 or 13.43 the *Authority* must, and any other time on its own initiative the *Authority* may, consider whether to make a determination under section 13.14(b).

Service provider to provide information to Authority and arbitrator

- 13.45 The *service provider* of a *covered network* must comply with any request by the *Authority* or the *arbitrator* to inspect or make copies of the *service provider's* accounts and records for the *covered network*.

Chapter 14 – Administration and Miscellaneous

Service provider to provide information on access arrangements

- 14.1 A *service provider* of a *covered network* must establish and *maintain* an information package in relation to the *covered network* which includes:
- (a) the *access arrangement* and *access arrangement information* for the *covered network*, or if there is no *access arrangement*, any *proposed access arrangement* for the *covered network*; and
 - (b) any *price list* in effect for the *covered network*; and
 - (c) any notices in respect of the *covered network* or the *access arrangement* provided to the *Authority* under this Code or the *access arrangement*; and
 - (d) references to any issues papers or decisions and *reasons published* by the *Authority* or the Minister in respect of the *covered network*, with details of where those papers or decisions may be accessed.
- 14.2 A *service provider* of a *covered network* must, if requested by a *user* or an *applicant*, provide a copy of the information package for the *covered network* to the *user* or *applicant* within 10 *business days* of the request, subject to the *user* or *applicant* paying any reasonable fee requested by the *service provider* for copying the information package.
- 14.3 On the request of a *user*, a *service provider* must promptly notify the *user* of the additional capacity that will be provided by an *augmentation* to be funded by that *user* if the quantity of that additional capacity is reasonably capable of being determined.⁵⁸²

Data collection regarding target revenue

- 14.4 A *service provider* must in accordance with *good electricity industry practice*:
- (a) throughout an *access arrangement period* collect and *maintain* data on any variables used in the *access arrangement* or *access arrangement information* in connection with cost allocations for the derivation of *target revenue*; and
 - (b) make that information available to the *Authority* on reasonable request.

Public register

- 14.5 The *Authority* must establish and *maintain* a *public register* and place on that register:
- (a) this Code; and

⁵⁸² Section 14.3 amended by WAGG No 134, 30 July 2021

- (b) a listing of the *covered networks*; and
- (c) a description of each *covered network*; and
- (d) for each *covered network*:
 - (i) each *proposed access arrangement* and *proposed revisions* submitted to the *Authority*; and
 - (ii) each *access arrangement information* and amended *access arrangement information* submitted to the *Authority*; and
 - (iii) each submission received in relation to an *access arrangement*, *proposed revisions* to an *access arrangement*, *access arrangement information*, *framework and approach*, *tariff structure statement* and *price lists*; and
 - (iv) each *draft decision* or *final decision* made by the *Authority* or Board under this Code; and
 - (v) the current *access arrangement* and *access arrangement information*; and
- (e) anything else that is required under this Code to be placed on the *public register*.⁵⁸³

14.6 The *public register* must be *maintained* in *electronic form* and:

- (a) may be kept solely in *electronic form* if the *Authority*:
 - (i) *maintains* and makes available at its premises a means of *accessing the public register in electronic form*; and
 - (ii) provides a copy of any item on the *public register* to any person on request and the payment of a reasonable fee; and
- (b) otherwise — must be *maintained* in both *electronic form* and hard copy form and the *Authority*:
 - (i) must make the hard copy *public register* available for inspection during ordinary business hours on *business days* at its principal place of business; and
 - (ii) must provide a copy of any item on the *public register* to any person on request and the payment of a reasonable fee.

14.7 Without limiting section 14.6, the *Authority* is required to make available for inspection during ordinary business hours on *business days* at its principal place of business copies of:

- (a) this Code as amended from time to time; and

⁵⁸³ Section 14.5 amended by WAGG No 157, 18 September 2020

- (b) each amendment made to this Code.

Register of interested persons

- 14.8 The *Authority* must *maintain a register of interested persons* for each *network* (or, at the *Authority's* discretion, all *networks*) to be used by the *Authority* in the performance of its functions under this Code, including in connection with public consultation under Appendix 7.
- 14.9 The *Authority* must endeavour to *maintain* the currency of the *register of interested persons* by periodically advertising in newspapers, industry journals and in any other form of media which it considers appropriate.
- 14.10 Where the *Authority* is required to send a notice to each person listed on the *register of interested persons* in respect of a *network*, the *Authority* may send the notice electronically and if a person listed on the *register of interested persons* has not provided an electronic address to the *Authority* or if the electronic address provided is not current or is not functioning, the *Authority* is not required to send the person the notice.

Protection for the Authority

- 14.11 The *Authority* is not liable for any loss or damage to third parties resulting from or in connection with the *public register* or *register of interested persons*, including but not limited to loss or damage resulting from:
- (a) errors or omissions in the *public register* or *register of interested persons*; or
 - (b) failure to *maintain* the currency of the *public register* or *register of interested persons*; or
 - (c) failure of electronic notices where the *Authority publishes* a thing.

Treatment of confidential information

- 14.12 Subject to section 14.13, where a *disclosing person* provides *relevant material* to a *recipient* in accordance with this Code, the *disclosing person* may, at the time at which the *relevant material* is provided, give notice to the *recipient* that the *relevant material* or part of the *relevant material* is *confidential material*.
- 14.13 A *disclosing person*:
- (a) may give notice to the *recipient* that *relevant material* is *confidential material* only if the *relevant material* is in fact *confidential material*, and where only a part or parts of the *relevant material* is *confidential material*, the *disclosing person* may give notice only in respect of those parts; and
 - (b) must in a notice under section 14.12 specify in reasonable detail the basis upon which the *disclosing person* makes the claim that the *relevant material* is *confidential material*.
- 14.14 The *recipient* must not disclose, *advertise* or *publish* any *confidential material* to any person (other than a worker of the *recipient* who is bound by an adequate confidentiality undertaking), unless the *recipient* is of the opinion:

- (a) that the disclosure of the *confidential material* would not cause detriment to the *disclosing person* or another person; or
- (b) that, although the disclosure of the *confidential material* may cause detriment to the *disclosing person* or another person, either:
 - (i) if the *recipient* is the *Authority*,⁵⁸⁴ the public benefit in disclosing it outweighs the detriment; or
 - (ii) the *recipient* is:
 - A. expressly required by this Code to disclose it despite any claim of confidentiality; or
 - B. required by another *written law* or *statutory instrument* to disclose it.

14.15 For the purposes of section 14.14, a disclosure cannot cause detriment to a person if the thing disclosed is already in the public domain (other than by disclosure by the *recipient* in breach of section 14.14).

How this Code applies to multiple service providers

14.16 These sections 14.16 to 14.21 apply if there is more than one *service provider* in connection with a *network*, including if:

- (a) the *network* is owned or operated by two or more persons as a joint venture or partnership; or
- (b) the *network* is owned and operated by different persons; or
- (c) a *network* is legally owned by a person or persons on trust for others.

14.17 In such a case each *service provider* in connection with the *network* is referred to in these sections 14.16 to 14.21 as a *participant*.

14.18 If this Code requires or permits something to be done by the *service provider*, that thing may be done by one of the *participants* on behalf of all the *participants*, provided that each *participant* complies with this Code.

{Note: For example, a *proposed access arrangement* may be submitted under section 4.1 by one *participant* on behalf of all *participants*.}

14.19 If a provision of this Code refers to the *service provider* bearing any costs, the provision applies as if the provision referred to any of the *participants* bearing any costs.

14.20 If a provision of this Code, other than Chapter 13, refers to the *service provider* doing something, the provision applies as if the provision referred to one or more of the *participants* doing the thing on behalf of all the *participants*.

14.21 If:

⁵⁸⁴ Section 14.14 amended by WAGG No 180, 22 October 2008

- (a) there is more than one *service provider* in connection with a *network*; and
- (b) one is the owner and another is the operator; and
- (c) responsibility for complying with the obligations imposed by this Code on the *service provider* is allocated among them by their *access arrangements* or their *access arrangement*,

then each *service provider* is responsible for complying with the obligations allocated to it.

How this Code applies to successor service providers

14.22 If a person becomes a *service provider* in relation to a *covered network*, for example, if:

- (a) the person purchases a *covered network*; or
- (b) a license is cancelled under section 35 of the Act and the assets, rights and interests of the former licensee vest in the person under regulations under section 35(4) of the Act,

then,

- (c) the *network* remains a *covered network*;
- (d) any *access arrangement* approved under this Code continues to apply to the *network* concerned despite the change in *service provider* and binds the person in the same way it bound other *service providers* immediately before the person became a *service provider* with respect to the *network* concerned; and
- (e) any arbitration award made under the *Code* continues to apply to the *network* concerned despite the change in *service provider* and binds the person in the same way it bound other *service providers* immediately before the person became a *service provider* with respect to the *network* concerned.

Authority may seek advice

14.23 The *Authority* in the performance of a function under this Code may seek advice from the Director of Energy Safety on matters relating to the performance of that function, for which purpose the Director of Energy Safety is to be treated as a worker of the *Authority*.

14.24 The Director of Energy Safety:

- (a) has the function of providing advice under section 14.23; and
- (b) is not obliged to provide advice under section 14.23.

14.25 Section 14.23 does not limit the *Authority's* power to seek advice from any person.

CPI adjustment

14.26 Where this Code refers to an amount being "**CPI adjusted**" then the *Authority* must:

- (a) adjust the amount (including as previously *CPI adjusted*) from each 1 July, to reflect the change in *CPI* between the *CPI published* for the March quarter immediately preceding the adjustment and the *CPI published* for the March quarter of the previous year; and
- (b) *publish* the adjusted amount.

General process for public consultation

14.27 Appendix 7 has effect.

Detailed provisions regarding contributions for certain work on the Western Power Network⁵⁸⁵

14.28 Appendix 8 has effect.⁵⁸⁶

Guidelines by the Authority⁵⁸⁷

14.29 The *Authority* must *publish* guidelines in accordance with:

- (a) section 6.32D;
- (b) section 6.56;
- (c) section 6.88;
- (d) section 6A.6; and
- (e) section 9.17.⁵⁸⁸

14.30 The *Authority* may *publish* guidelines in accordance with:

- (a) section 4.5; and
- (b) section 13.41.⁵⁸⁹

14.31 The *Authority* may waive the requirement for a *service provider* to comply with one or more guidelines *published* and referred to in sections 14.29 and 14.30.⁵⁹⁰

14.32 Before granting a waiver under section 14.31, the *Authority* must:

- (a) consult the public in accordance with Appendix 7;
- (b) determine whether the granting of a waiver better achieves the *Code objective*; and

⁵⁸⁵ Heading to section 14.28 inserted by WAGG No 137, 29 June 2007; Heading to section 14.28 amended by WAGG No 180, 22 October 2008

⁵⁸⁶ Section 14.28 inserted by WAGG No 137, 29 June 2007

⁵⁸⁷ Heading to section 14.29 inserted by WAGG No 157, 18 September 2020

⁵⁸⁸ Section 14.29 inserted by WAGG No 157, 18 September 2020

⁵⁸⁹ Section 14.30 inserted by WAGG No 157, 18 September 2020

⁵⁹⁰ Section 14.31 inserted by WAGG No 157, 18 September 2020

- (c) determine whether the advantages of granting the waiver outweigh the disadvantages, in particular the disadvantages associated with decreased regulatory certainty and increased regulatory cost and delay.⁵⁹¹
- 14.33 Without limiting section 14.31, a *service provider* may at any time request the *Authority* to waive a requirement for the *service provider* to comply with one or more guidelines in accordance with section 14.31.⁵⁹²
- 14.34 The *Authority* may, from time to time, amend or replace the guidelines referred to in sections 14.29 and 14.30 in accordance with the consultation process specified for such guidelines.⁵⁹³
- 14.35 Nothing prevents the *Authority* from *publishing* any of the guidelines referred to in sections 14.29 and 14.30 in the same document as another guideline, provided that if the *Authority* does so, the *Authority* must clearly state in that document which guidelines the document contains.⁵⁹⁴

⁵⁹¹ Section 14.32 inserted by WAGG No 157, 18 September 2020

⁵⁹² Section 14.33 inserted by WAGG No 157, 18 September 2020

⁵⁹³ Section 14.34 inserted by WAGG No 157, 18 September 2020

⁵⁹⁴ Section 14.35 inserted by WAGG No 157, 18 September 2020

Chapter 15 – Transitional

Minister may make determinations

- 15.1 The Minister may determine, after consultation with affected parties, how any matter in progress immediately before the commencement of Part 8 of the Act is to be treated, after that commencement, for the purposes of the provisions of the *Code*.
- 15.1A The Minister may determine that a project is a *priority project* for the purposes of the provisions of the *Code*.⁵⁹⁵
- 15.2 The Minister must *publish* a determination made under section 15.1 or section 15.1A in the *Gazette*.⁵⁹⁶
- 15.2A At the time of *publishing a priority project determination* the Minister must also *publish* the *reasons* for the *priority project determination*, including the basis on which the Minister considers that the *priority project determination* meets the *Code objective*.⁵⁹⁷

Access arrangements for SWIS to be compatible with market

- 15.3 Without limiting sections 5.34 to 5.36, an *access arrangement* for a *covered network* which forms part of the *SWIS* may specify as *trigger events* one or more events or sets of circumstances in connection with the arrangements established under Part 9 of the Act.

Access arrangements to be compatible with changes to contestability

- 15.4 Without limiting sections 5.34 to 5.36, an *access arrangement* for a *covered network* may specify as *trigger events* one or more events or sets of circumstances in connection with changes to the thresholds for contestability with respect to electricity supply.

Preservation of Western Power Network actions⁵⁹⁸

- 15.5 If an action could have been commenced before the *referee* under the previous regime immediately before 1 July 2007 seeking a remedy in respect of a thing done or not done before 1 July 2007 in connection with or arising out of a *prior application*, an action may be commenced before the *arbitrator* seeking the remedy in respect of the thing.⁵⁹⁹
- 15.6 Section 15.5 does not extend any period of limitation or waive any other requirement under the previous regime for commencing an action.⁶⁰⁰

⁵⁹⁵ Section 15.1A inserted by WAGG [No], [date]

⁵⁹⁶ Section 15.2 amended by WAGG [No], [date]

⁵⁹⁷ Section 15.2A inserted by WAGG [No], [date]

⁵⁹⁸ Heading to section 15.5 amended by WAGG No 180, 22 October 2008

⁵⁹⁹ Section 15.5 inserted by WAGG No 137, 29 June 2007

⁶⁰⁰ Section 15.6 inserted by WAGG No 137, 29 June 2007

- 15.7 If a person commences an action before the *arbitrator* seeking a remedy under section 15.5, the *arbitrator*—
- (a) may hear the matter under Chapter 10; and
 - (b) may make any determination in respect of the matter which is consistent with—
 - (i) the *Code objective*; and
 - (ii) the Act and this Code generally.⁶⁰¹

[Heading not used]⁶⁰²

- 15.8 [not used]⁶⁰³

Transitional arrangements for 2020 (No. 2) amendments⁶⁰⁴

- 15.9 By 1 October 2021, a *service provider* must *publish*:
- (a) the first *network opportunity map* in accordance with section 6A.1; and
 - (b) the first *alternative options strategy* in accordance with sections 6A.3 and 6A.4.⁶⁰⁵
- 15.10 The amendments made to section 5.1 by the *2020 (No. 2) amendments* only apply on and from the next *review* of the *access arrangement* for the *Western Power Network* after the *2020 (No. 2) amendments*, and do not:
- (a) entitle the *Authority* to vary a *service provider's access arrangement* under section 4.41; or
 - (b) require a *service provider* to propose revisions to its *access arrangement* prior to the next *revisions submission date* for the *service provider's access arrangement*.⁶⁰⁶
- 15.11 Sections 15.12 to 15.16 are transitional provisions that apply only in respect of the application of the next *review* of the *access arrangement* for the *Western Power Network* after the *2020 (No. 2) amendments* and not any subsequent *reviews*.⁶⁰⁷
- 15.12 Section 4.A2(f) is deleted and replaced with “a list of and classification of services which must specify whether services are *reference services* or *non-reference services*, and may specify the eligibility criteria for each *reference service*, the structure and *charging parameters* for each *distribution reference tariff* and a description of the

⁶⁰¹ Section 15.6 inserted by WAGG No 137, 29 June 2007

⁶⁰² Heading to section 15.8 amended by WAGG No 180, 22 October 2008; Heading to section 15.8 deleted by WAGG No 157, 18 September 2020

⁶⁰³ Section 15.8 inserted by WAGG No 137, 29 June 2007; Section 15.8 deleted by WAGG No 157, 18 September 2020

⁶⁰⁴ Heading to section 15.9 inserted by WAGG No 157, 18 September 2020

⁶⁰⁵ Section 15.9 inserted by WAGG No 157, 18 September 2020

⁶⁰⁶ Section 15.10 inserted by WAGG No 157, 18 September 2020

⁶⁰⁷ Section 15.11 inserted by WAGG No 157, 18 September 2020

approach to setting each *distribution reference tariff* in accordance with sections 7.2 to 7.12".⁶⁰⁸

- 15.13 The requirement to *publish* documents by 31 months prior to the *target revisions commencement date* in section 4.A4 does not apply.⁶⁰⁹
- 15.14 The requirement to make and *publish* the final *framework and approach* by no later than 23 months prior to the *target revisions commencement date* in section 4.A9 does not apply provided that the *Authority* must comply with its obligations under section 4.A9 by no later than 2 August 2021.⁶¹⁰
- 15.15 The requirement to submit *proposed revisions* and revised *access arrangement information* to the *Authority* by no later than 17 months prior to the *target revisions commencement date* in section 4.48 does not apply provided that the *service provider* must comply with its obligations under section 4.48 by no later than 1 February 2022.⁶¹¹
- 15.16 The *target revisions commencement date* is 1 July 2023.⁶¹²
- 15.17 Notwithstanding section 12.50, prior to 1 August 2021, a proposal to amend *technical rules* may only be submitted under section 12.50 by:
- (a) the *service provider*; or
 - (b) the Chair of the *technical rules committee*; or
 - (c) a *service provider* of an interconnected network.⁶¹³

⁶⁰⁸ Section 15.12 inserted by WAGG No 157, 18 September 2020

⁶⁰⁹ Section 15.13 inserted by WAGG No 157, 18 September 2020


⁶¹⁰ Section 15.14 inserted by WAGG No 157, 18 September 2020

⁶¹¹ Section 15.15 inserted by WAGG No 157, 18 September 2020

⁶¹² Section 15.16 inserted by WAGG No 157, 18 September 2020

⁶¹³ Section 15.17 inserted by WAGG No 157, 18 September 2020

Appendix 1 – Flowchart of access arrangement approval process⁶¹⁴



⁶¹⁴ Flowchart to Appendix 1 deleted and replaced by WAGG No 157, 18 September 2020

Appendix 2 – Model Applications and Queuing Policy

615

This Appendix 2 leaves some matters to be completed when an *applications and queuing policy* is incorporated into an *access arrangement*. These matters are noted in square brackets, eg. “[x]”.

The variable can be a simple absolute number or may follow a more sophisticated structure designed by the *service provider* to best suit the characteristics of its *covered network* and business. For example, if [x] is the time by which a *service provider* must make an *access offer* for a *class 1 application*, the *service provider* may specify that [x] is 5 *business days* where the application is in respect of between one and 100 existing *connection points* and [x] is 10 *business days* where the application is in respect of more than 100 *connection points*.

The variables proposed by a *service provider* are subject to approval by the *Authority* under Chapter 4, and (without limiting the *Authority’s* discretion or duties) must be consistent with the *Code objective* and section 5.1(g).

Footnotes following each matter in square brackets contain instructions to the *Authority*. The footnotes form part of this model *applications and queuing policy* and, like these introductory notes, have legal effect.

Subappendix 2.1– Interpretation

Definitions and Interpretation

A2.1 In this *applications and queuing policy*, unless the contrary intention is apparent:

“**access contract**” has the same meaning as “access agreement” does in Part 8 of the Act.

{Note: At the time this Code was made, the definition in section 103 of the Act was:

‘ “**access agreement**” means an agreement under the Code between a network service provider and another person (a “network user”) for that person to have access to services. ’⁶¹⁵

“**access offer**” means a form of *access contract* which complies with clause A2.103 or A2.105, as applicable, which has been *signed* by the *service provider* and is in such a form that it can, without anything else being required, become an *access contract* when *signed* by an *applicant*.

“**Act**” means the *Electricity Industry Act 2004*.

⁶¹⁵ Appendix 2 amended by WAGG No 207, 8 November 2005

⁶¹⁶ Note to clause A2.1 amended by WAGG No 180, 22 October 2008

“applicant” means an *applicant* under this *applications and queuing policy* for an *access contract*, or for the modification of any other *contract for services*, and includes a prospective *applicant*.⁶¹⁷

“application” means an *access application* under this *applications and queuing policy* (as amended under this *applications and queuing policy*) and includes any additional information provided by the *applicant* in relation to the *access application*.

“application form” means the form referred to in clause A2.22 contained in a *service provider’s access arrangement*.

“bypass”, in relation to an application (**“bypassed application”**), means that the *first come first served* principle is not applied in respect of the bypassed application, so that an application with later *priority* receives an *access offer* before the *bypassed* application.

“capacity increase” means an increase in a *user’s* capacity under a *contract for services* in respect of a *connection point*.⁶¹⁸

“capacity increase notice” means a notice, under clause A2.30, provided by a *user* to a *service provider* in respect of a *user’s* request for *capacity increase*.

“class 1 application” has the meaning given to it in clause A2.5.

“class 2 application” has the meaning given to it in clause A2.6.

“class 3 application” has the meaning given to it in clause A2.7.

619

“Code” means the Electricity Networks Access Code 2004.

“competing”, in relation to two or more applications, means (subject to section 5.9A of the *Code*) that the provision of the *covered service* sought in one application may impede the *service provider’s* ability to provide the *covered services* that are sought in the *other applications*.⁶²⁰

“confidential information” means information disclosed, by an *applicant* or a *disclosing person*, to the *service provider*, in or in connection with, an application or a *capacity increase* notice which the *disclosing person* (acting as a *reasonable and prudent person*) has identified as being commercially sensitive or confidential.

621

622

“CPI” means the Consumer Price Index (all groups) for the Weighted Average of Eight Capital Cities *published* by the Australian Bureau of Statistics from time to time

⁶¹⁷ Clause A2.1 amended by WAGG No 180, 22 October 2008

⁶¹⁸ Clause A2.1 amended by WAGG No 180, 22 October 2008

⁶¹⁹ Clause A2.1 amended by WAGG No 207, 8 November 2005

⁶²⁰ Clause A2.1 amended by WAGG No 180, 22 October 2008

⁶²¹ Clause A2.1 amended by WAGG No 180, 22 October 2008

⁶²² Clause A2.1 amended by WAGG No 180, 22 October 2008

or, if the Consumer Price Index (all groups) for the Weighted Average of Eight Capital Cities ceases to be *published*, such alternative index as the *service provider* may reasonably determine, and in all cases the *CPI* figure is to be adjusted to correct for any effects of a change in the rate of *GST*.

“**customer transfer code**” means a code made under section 39(1) or section 39(2a) of the Act in respect of the matter referred to in section 39(2)(b) of the Act.

“**customer transfer request**”:

- (a) if “customer transfer request” is defined in the *customer transfer code* — has the meaning given to that term in the *customer transfer code*; and
- (b) otherwise — means a request by an incoming *user* to the *service provider* to transfer an outgoing *user's access rights* and obligations in respect of a *contestable customer* to the *incoming user*.

“**disclosing person**”, in relation to an application or a *capacity increase notice*, means a person who discloses *confidential information* to the *service provider* in, or in connection with, an application or a *capacity increase notice*, as applicable.

“**dormant application**” means an application that was lodged by the *applicant* on a date that is more than three years before the date on which the *service provider* is considering the application under clause A2.78 and in respect of which the *service provider* has not made an *access offer*.

“**first come first served**” means that an *applicant* with earlier *priority* receives an *access offer* before an *applicant* with later *priority*.

“**GST**” means goods and *services* tax or similar value added tax levied or imposed in Australia pursuant to the *A New Tax System (Goods and Services Tax) Act 1999* of the Commonwealth or otherwise on a supply.

“**initial response**” means the initial response of the *service provider* to an *applicant* under clause A2.89 in relation to an application.

“**law**” means “written laws” and “statutory instruments” as defined in the *Code* and rules of the general law including the common law and equity.

“**lodgement fee**” means:

- (a) for an application — the fee specified under clause A2.14; or
- (b) for a *capacity increase notice* — the fee specified under clause A2.35.

“**materially different**”, in relation to an amended application, includes an amended application which is materially different to the original application in respect of any one or more of the criteria specified in clause A2.75.

“**maximum demand**” means the highest amount of electrical power in respect of electricity transferred, or forecast to be transferred, over a specified period (half hour, day, week, month, season or year) at an *exit point*.

“**preliminary assessment**” means the preliminary assessment of the *service provider* to an *applicant* under clause A2.93 in relation to an application.

“priority”, in relation to an application, means the priority that the *applicant* has, as against any other *applicant* with a *competing* application, to obtain *access to covered services*.

“project” means a project identified in a *tender notice*.

“project related application” means an *application* designated under clause A2.58 by the *service provider*, acting as a *reasonable and prudent person*, as a *project-related application*, provided that the *applicant* has not notified the *service provider* under clause A2.60 that the application is not a *project-related application*.

“proponent” means a person who gives a *tender notice* to the *service provider* in respect of a *project*.

“proposed controller” means a person who owns, operates or controls *facilities and equipment* at a *connection point* and who is specified by an *applicant* in an application in respect of a *connection point*.

“queue” means a *first come first served* queue described in clauses A2.47 to A2.48.

“queuing rules” means the principles described in clauses A2.46 to A2.48 that apply to determine the *priority* of an application.

“requested capacity” means, in respect of a *connection point*, the capacity requested to become contracted capacity under the *access contract* for which an application is made.

“services end date” means, in respect of a *connection point*, the date on which the *service provider* ends the provision of *services* to the *user* in respect of that *connection point*.

“services start date” means, in respect of a *connection point*, the date on which the *service provider* commences providing *services* to the *user* in respect of that *connection point*.

“signed” by the *service provider* or the *applicant* means duly signed or otherwise executed by or on behalf of all persons who comprise the *service provider* or the *applicant*, as the case may be.

“spare capacity” means the capacity, from time to time, of the *covered network* as configured at the time to provide *covered services* having regard to the *service provider’s* contractual obligations in respect of the *covered network*.

“tender notice” means a notice given to the *service provider* under clause A2.56(a).

“transfer matters”, in relation to a *customer transfer request*, has the meaning given to it in clause A2.43.

“workers” of a person means the directors, officers, servants, employees, agents, sub- contractors and consultants of the person.

A2.2 Unless the contrary intention is apparent, a term with a defined meaning in the *Code* has the same meaning in this *applications and queuing policy*.

A2.3 Unless the contrary intention is apparent:

- (a) a rule of interpretation in the *Code*; and
- (b) the *Interpretation Act 1984*,

apply to the interpretation of this *applications and queuing policy*.

Transition of prior applications

[x]⁶²³

Negotiations in good faith

A2.4 The *service provider* must negotiate in good faith with an *applicant* regarding the terms for an *access contract* for a *covered service*.

Classes of applications

A2.5 A “**class 1 application**” is an application:

- (a) by an *applicant* who is already a *user* of the *network*; and
- (b) in respect of one or more existing *connection points*; and
- (c) seeking only a *reference service* at the *reference tariff*; and
- (d) which does not require any *augmentation*.

A2.6 A “**class 2 application**” is an *application*:

- (a) by an *applicant* who is not already a *user* of the *network*; and
- (b) which otherwise meets the requirements for a *class 1 application*.

A2.7 A “*class 3 application*” is an application which does not meet the requirements for a *class 1 application* or *class 2 application*.

624

A2.8 If an *application* is initially misclassified by a *service provider* in its notification under clause A2.89 (for example because it is initially thought that the *application* is not likely to require an *augmentation*, but one later proves necessary) or requires reclassification because it has been amended, then the *service provider* may reclassify it and the relevant clauses of this *applications and queuing policy* appropriate to its new classification apply as though the new classification had applied to the *application* from the date the *application* was originally lodged.

⁶²³ Insert transition of prior applications provisions, if applicable. To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. See section 5.7(i) of the *Code*.

⁶²⁴ Clause A2.7 amended by WAGG No 207, 8 November 2005

Subappendix 2.2– The application

Informal communications

A2.9 Prior to lodging an *application* with a *service provider*, an *applicant* may contact the *service provider* to discuss the proposed *application*, including matters such as:

- (a) what classification will likely apply to the proposed *application*;
- (b) whether it is likely that there is sufficient *spare capacity* to provide the requested *covered services* or whether there may be *required work*, including whether it is likely that any new *connection assets* will be required to provide the *covered services* requested in the *application*; and
- (c) if it is likely that there will be *required work* — whether or not a *contribution* will likely be required from the *applicant* under the *contributions policy* in respect of the *required work* and a good faith estimate of the approximate amount of the *contribution*; and
- (d) if it is likely that there will be *required work* — a good faith estimate of the likely time required for the undertaking of the work; and
- (e) what system or other studies are likely to be required in the *processing* of the *application*, whether the *service provider* is able to undertake the studies and the approximate costs of such studies,

and the *service provider* must engage in such discussions in good faith and use all reasonable endeavours to satisfactorily and promptly address any matters raised by the *applicant*.⁶²⁵

A2.10 The discussions under clause A2.9 are not binding on a *service provider*, and the *service provider* is not liable for any error or omission that is made as a *reasonable and prudent person* in the discussions under clause A2.9.

Confidentiality

A2.11 Information which the *service provider* is required to disclose under clauses A2.68(a), A2.68(b) or A2.68(c) is not *confidential information*.

A2.12 The *service provider* must not disclose *confidential information* unless:

- (a) the disclosure is made to the *Authority* on a confidential basis; or
- (b) the disclosure is made to a worker of the *service provider* who is bound by an adequate confidentiality undertaking; or
- (c) the disclosure is made with the consent of the *disclosing person*; or
- (d) the disclosure is required or allowed by *law*, or by the *arbitrator* or another court or tribunal constituted by *law*; or

⁶²⁵ Clause A2.9 amended by WAGG No 180, 22 October 2008

- (e) the information has entered the public domain other than by breach of this clause A2.12; or
- (f) the information could be inferred by a *reasonable and prudent person* from information already in the public domain.

Costs of processing application

- A2.13 For an *application* other than a *class 3 application*, an *applicant* must pay to the *service provider* the *lodgement fee* prescribed in clause A2.14 for the *application* at the time it lodges the *application*.
- A2.14 The *lodgement fee* is:
- (a) for a *class 1 application* — $\$[x]^{626}$; and
 - (b) for a *class 2 application* — $\$[x]^{627}$.
- A2.15 For a *class 3 application*, an *applicant* must, when requested by the *service provider*, pay an amount to the *service provider* or a third party in respect of a reasonable cost incurred, or to be incurred within a reasonable timeframe, in *processing* the *application*.
- A2.16 The total of the costs referred to in clause A2.15 must not exceed the reasonable costs which would be incurred by a prudent *service provider*, acting efficiently and in good faith, in accordance with *good electricity industry practice*, seeking to achieve the lowest practicable cost of *processing* the *application*.
- A2.17 The costs referred to in clause A2.15 must not include any costs of the *service provider* in relation to an *access dispute* (which are to be awarded by the *arbitrator* under Chapter 10).
- A2.18 The *service provider* may adjust the amounts referred to in clauses A2.14(a) and A2.14(b) (including as previously adjusted) from each 1 July in accordance with section 14.26(a) of the *Code* and must provide a notice setting out the adjusted amounts to the *Authority*, and the *Authority* must place the notice on the *public register*.
- A2.19 A dispute between an *applicant* and the *service provider* regarding a cost under clause A2.15 may be referred by either party to the *arbitrator* for determination, in which case the *arbitrator* may either affirm the amount or reduce it.

⁶²⁶ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. The value inserted for variable $[x]$ may be expressed as a single value or by a more sophisticated structure for example a range of numbers but should not exceed a forecast of reasonable costs which would be incurred by a *service provider* acting as a *reasonable and prudent person* seeking to achieve the lowest practicable cost of processing an *application* of the relevant class in relation to the relevant *network*.

⁶²⁷ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. The value inserted for variable $[x]$ may be expressed as a single value or by a more sophisticated structure for example a range of numbers but should not exceed a forecast of reasonable costs which would be incurred by a prudent *service provider*, acting efficiently and in good faith, in accordance with *good electricity industry practice*, seeking to achieve the lowest practicable cost of processing an *application* of the relevant class in relation to the relevant *network*.

Lead times for applications

A2.20 An *applicant* must endeavour to lodge an *application* to the *service provider*:

- (a) for a *class 1 application* — at least $[x]^{628}$ *business days* before the requested *services start date*; and
- (b) for a *class 2 application* — at least $[x]^{629}$ *business days* before the requested *services start date*; and
- (c) for a *class 3 application* — within a reasonable time before the requested *services start date*, having regard to the time required for undertaking any necessary work.⁶³⁰

Access application

A2.21 The *access application* process is commenced by the *applicant* giving a written *application* to the *service provider* on the *application form* in the *service provider's access arrangement* using reasonable endeavours to accurately and completely address each item in the *application form*.

A2.22 The *service provider* must include an *application form* in its *access arrangement* which makes provision for an *applicant* to provide the following information to the *service provider* in respect of an *application*:

- (a) the full name and address of the *applicant*; and
- (b) whether the *applicant* is acting as agent for any person in making the *application*, and if so, details of the *applicant's* principals; and
- (c) the *applicant's* preliminary classification of the *application*; and
- (d) any conditions precedent that the *applicant* seeks for the requested *access contract*; and
- (e) whether the *application* is being made in connection with a tender process under clauses A2.56 to A2.61; and
- (f) the *covered services* requested, and for each requested *covered service*:
 - (i) the requested *services start date* and requested *services end date*; and
 - (ii) the location or meter number of each requested *connection point*, as applicable; and

⁶²⁸ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. Unless the *Authority* considers that the *Code objective* and the objectives in section 0 require otherwise, the value inserted for variable $[x]$ should not exceed 10 in respect of services to be added to an existing *access contract*, and 25 otherwise.

⁶²⁹ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. Unless the *Authority* considers that the *Code objective* and the objectives in section 0 require otherwise, the value inserted for variable $[x]$ should not exceed 25.

⁶³⁰ Clause A2.20 amended by WAGG No 180, 22 October 2008

- (iii) the requested *service standards*; and
 - (iv) the requested *tariff*; and
 - (v) any additional terms the *applicant* seeks in respect of the *covered service*; and
- (g) for each requested *connection point*:
- (i) such information regarding the *facilities and equipment* at the *connection point* to the extent required by:
 - A. the *technical rules*; or
 - B. the *service provider* acting as a *reasonable and prudent person*,and
 - (ii) if the *applicant* wishes to nominate a *proposed controller* for the *connection point*, information in reasonable detail regarding the *proposed controller*; and
 - (iii) if the *connection point* is an *entry point* — the proposed *declared sent out capacity* (expressed in kW or kVA) of the plant connected or to be connected at the *entry point*; and
 - (iv) if the *connection point* is an *exit point* — the expected *maximum demand* (expressed in kW or kVA) connected or to be connected at each *exit point*;
- and
- (h) if the *applicant* so chooses, the *applicant's* preliminary proposal in relation to whether any *contribution* under the *contributions policy* will be paid or (except in the case of a headworks *charge*) provided in kind, and the preliminary proposed terms on which that may occur (but this does not prevent the *applicant* from making an alternative proposal once the scope of any *required work* is better known);⁶³¹ and
 - (i) such information concerning the *applicant* as the *service provider* requires, acting reasonably, to assess the *applicant's* ability to meet its obligations under the requested *access contract*.

A2.23 An *applicant* may request in an *application* a *preliminary assessment* of a *class 3 application*.

A2.24 When an *application* contains estimates or forecasts of any information —

- (a) the *service provider* may treat that estimated or forecast information as factual information; and

⁶³¹ Clause A2.22 amended by WAGG No 180, 22 October 2008

- (b) the *application* is a warranty by the *applicant* to the *service provider* that each such estimate or forecast is the *applicant's* best estimate or forecast as a *reasonable and prudent person*.

Errors or omissions in an application

- A2.25 If the *service provider* becomes aware of any material error or omission in an *application* or purported *application* it must immediately notify the *applicant* about it and may request information under clause A2.28.
- A2.26 If an *applicant* is notified by the *service provider* or otherwise becomes aware of any material error or omission in an *application*, it must amend the *application* to remedy it as soon as practicable after becoming aware of it.
- A2.27 If remedying an error or omission in an *application* amounts to a material amendment to the *application*, clauses A2.73 and A2.74 apply.

Additional information

- A2.28 At any time, the *service provider* may, acting as a *reasonable and prudent person*, request the *applicant* to provide further information that the *service provider* reasonably requires to enable it to process the *application*.
- A2.29 An *applicant* who receives an information request under clause A2.28 must provide the requested information to the *service provider* as soon as reasonably practicable.

Subappendix 2.3– Capacity increase notices and customer transfer requests

Capacity increase notice

- A2.30 A *user* may request a *capacity increase* by providing a *capacity increase notice* to the *service provider*.
- A2.31 Within 10 *business days* of receipt of a *capacity increase notice* under clause A2.30, the *service provider* must determine, and notify the *user*, whether or not it accepts the *capacity increase*.
- A2.32 The *service provider* must accept the *capacity increase* if it forms the view as a *reasonable and prudent person* that:
 - (a) accepting the *capacity increase* would not be likely to impede the ability of the *service provider* to provide a *covered service* sought in an *access application* lodged by another *applicant*; and
 - (b) it is not likely that there will be *required work* to provide the *capacity increase*, and otherwise the *service provider* must reject the *capacity increase*.⁶³²

⁶³² Clause A2.32 amended by WAGG No 180, 22 October 2008

- A2.33 If the *service provider* accepts the *capacity increase* under clause A2.31 then the *service provider* and the *user* must, as soon as practicable, arrange to amend the *user's contract for services* in accordance with the *capacity increase*.⁶³³
- A2.34 If the *service provider* does not accept the *capacity increase* under clause A2.31 then the *service provider* must state in its notice under clause A2.31 that the *user* must make an *application* under Subappendix 2.2 to increase its capacity as described in the *capacity increase notice*.

Lodgement fees for capacity increase notices

- A2.35 For a *capacity increase notice* an *applicant* must pay to the *service provider* the a *lodgement fee* of \$[x]⁶³⁴ at the time it lodges the *capacity increase notice*.
- A2.36 The *service provider* may adjust the amount referred to in clause A2.35 (including as previously adjusted) from each 1 July in accordance with section 14.26(a) of the *Code* and must provide a notice setting out the adjusted amount to the *Authority*, and the *Authority* must place the notice on the *public register*.

Lead times for capacity increase notices

- A2.37 An *applicant* must endeavour to lodge a *capacity increase notice* to the *service provider* at least [x]⁶³⁵ *business days* before the requested *services start date*.

Form of capacity increase notices

- A2.38 A *capacity increase notice* must:
- (a) provide sufficient information to the *service provider* to enable the *service provider* to process the *capacity increase notice*; and
 - (b) comply with any requirements for *capacity increase notice* under a *law*.

Additional information

- A2.39 At any time, the *service provider* may, acting as a *reasonable and prudent person*, request the *applicant* to provide further information that the *service provider* reasonably requires to enable it to process a *capacity increase notice*.
- A2.40 An *applicant* who receives an information request under clause A2.39 must provide the requested information to the *service provider* as soon as reasonably practicable.

⁶³³ Clause A2.33 amended by WAGG No 180, 22 October 2008

⁶³⁴ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. The value inserted for variable [x] may be expressed as a single value or by a more sophisticated structure for example a range of numbers but should not exceed a forecast of reasonable costs which would be incurred by a prudent *service provider*, acting efficiently and in good faith, in accordance with *good electricity industry practice*, seeking to achieve the lowest practicable cost of processing a *capacity increase notice* in relation to the relevant *network*.

⁶³⁵ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. Unless the *Authority* considers that the *Code* objective and the objectives in section 0 require otherwise, the value inserted for variable [x] should not exceed 10.

Customer transfer requests

- A2.41 An incoming *user* may lodge a *customer transfer request* with the *service provider*.
- A2.42 The *service provider*, incoming *user* and outgoing *user* must comply with the *customer transfer code* with respect to a *customer transfer request*.
- A2.43 To the extent that there is no *customer transfer code* or the *customer transfer code* does not make provision for any of the following matters ("**transfer matters**"):
- (a) the timing of the lodgement and processing of the *customer transfer request*; and
 - (b) the fees, if any, applying to the *customer transfer request*; and
 - (c) the form of the *customer transfer request*; and
 - (d) information required to be provided by or to any person in connection with the *customer transfer request*; and
 - (e) any other matter which it is necessary or convenient to deal with to facilitate the efficient processing of the *customer transfer request*,
- the *service provider*, incoming *user* and outgoing *user* must:
- (f) comply with any provisions in the *access arrangement* dealing with the *transfer matters*; and
 - (g) to the extent that the *access arrangement* does not make provision for a *transfer matter*, as *reasonable and prudent persons*, act in a manner which facilitates the efficient processing of the *customer transfer request*.
- A2.44 A *customer transfer request* is not to be assessed as an *application* and the *queuing rules* do not apply to the processing of a *customer transfer request*.

Subappendix 2.4 – The Queue

Queuing rules apply only when there are competing applications

- A2.45 The *queuing rules* apply only where there are *competing applications*.

Queuing rules determine priority of applications

- A2.46 The *queuing rules* apply to determine the *priority* of an *applicant's application* in the *queue*.
- A2.47 Subject to clause A2.61, the *priority* of an *applicant's application* in a *queue* is to be determined by reference to the time at which the *application* is lodged, which is the time at which the *service provider* actually receives the *application*.
- A2.48 If an *applicant* submits more than one *application*, then the *applicant* has a different *priority* in respect of each *application*, and every reference in the *queuing rules* to the

applicant's priority is to be read as a reference to the *applicant's priority* in respect of the relevant *application*.

More than one queue

A2.49 Under clause A2.47 there may from time to time be more than one *queue* in respect of a *network*.

{Example: One group of *applications* may relate to new *generation* projects in one part of a *covered network* and another group of *applications* may relate to new *consumers* at an industrial area at a different part of the *covered network* and each group of applications may be in a separate queue.}

First come first served principle

A2.50 Subject to clauses A2.51 to A2.62, the *service provider* must ensure that an *applicant* with earlier *priority* receives an *access offer* before an *applicant* with later *priority* (“**first come first served**”).

Bypass

A2.51 Subject to the process in clauses A2.53 to A2.55, *bypass* is permitted to the extent necessary to better achieve the *Code objective*.

A2.52 Without limiting clause A2.51, circumstances where the *bypass* test in clause A2.51 might be satisfied include:

- (a) where an *application* that has earlier *priority* in a *queue* cannot, and an *application* with later *priority* can, presently proceed to an *access contract* or otherwise progress through the *applications* process, for example because:
 - (i) the *applicant* with earlier *priority* has not obtained environmental or other approvals that it requires in order to proceed; or
 - (ii) of delays in *processing* the *application* that has earlier *priority* caused by the arbitration of an *access dispute* under Chapter 10; or
- (b) where an *applicant* fails to use reasonable endeavours to progress its *application* in accordance with this *applications and queuing policy*; or
- (c) where the *application* is frivolous, vexatious or was not made in good faith.

A2.53 If the *service provider* considers that the *bypass* test in clause A2.51 is satisfied in relation to an *application*, it must give the *applicant* a notice (subject to clause A2.12) setting out in reasonable detail the basis on which the *service provider* considers that the *bypass* test in clause A2.51 is satisfied and requiring the *applicant* to either:

- (a) if possible, progress the *application*; or
- (b) otherwise provide information to the *service provider* demonstrating why the *application* should not be *bypassed*.

A2.54 At least [x]⁶³⁶ *business days* after giving a notice under clause A2.53, the *service provider* must make a fresh determination, having regard to all *relevant material* including anything which has occurred, and any information provided, since the notice was given under clause A2.53 whether the *bypass* test in clause A2.51 is satisfied, and if the *service provider* considers that the *bypass* test in clause A2.51 is satisfied, it may *bypass* the *application* to the extent permitted under clause A2.51.

A2.55 If the *service provider* *bypasses* an *application* under clause A2.54, the *service provider* must (subject to clause A2.12) provide *reasons* to the *applicant* for its decision to *bypass* the *application* including information in reasonable detail explaining on what basis the *service provider* determined that *bypassing* the *application* was necessary to better achieve the *Code objective* under clause A2.51.

Applications in relation to tender projects etc

A2.56 Clauses A2.58 to A2.60 apply:

- (a) where a *proponent* gives notice (“**tender notice**”) to the *service provider* that it is requesting tenders or proposals in connection with a *project* and that some or all of the persons lodging tenders or proposals in connection with the *project* may wish to *transport* electricity from or to the *project* and may lodge a *class 3 application* for that purpose; and
- (b) where the *service provider* has not been given a *tender notice* by a *proponent* but two or more *applications* have been lodged with the *service provider*, each of which is expressly designated as being made in connection with the same tender process.

A2.57 When a *proponent* requests tenders or proposals in connection with a *project* the *proponent* must also inform *applicants* who may lodge tenders or proposals in connection with the *project* to specify on their *application forms* that the *application* is being made in connection with the tender process for the *project*.

A2.58 When a *class 3 application* is lodged with the *service provider*, the *service provider* must determine as a *reasonable and prudent person* whether it is lodged for the purpose of transporting electricity from or to a *project*, and if so it must by notice to the *applicant* designate the *application* as a *project-related application*.

A2.59 For the purposes of A2.58, the *service provider* must determine that an *application* is lodged for the purpose of transporting electricity from or to a *project* where the *application* provides that it is made in connection with a tender process under clauses A2.56 to A2.61.

A2.60 If an *applicant* receives a notice from the *service provider* under clause A2.58, the *applicant* may notify the *service provider* that its *application* is not a *project-related application* and the *service provider* must deal with the *application* on the basis that it is not a *project-related application*.

⁶³⁶ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. Unless the *Authority* considers that the *Code objective* and the objectives in section 0 require otherwise, the value inserted for variable [x] should not be less than 20.

- A2.61 All *project-related applications* for a *project* are to be treated as having the same *priority*, equal to the *priority* attaching to the earlier of:
- (a) the date the *service provider* received the *tender notice* from the *proponent*; or
 - (b) such other date that the *service provider* becomes aware that an invitation to tender for the *project* has been announced.
- A2.62 If the *service provider* is of the opinion that one or more *access contracts* have been entered into in connection with a *project*, the *service provider* must:
- (a) liaise with the *proponent* of the *project* to determine whether its opinion is correct; and
 - (b) if it determines that its opinion is correct, give notice to each other *applicant* that has made an *application* in connection with the *project* that:
 - (i) one or more *access contracts* have been entered into in connection with the *project*; and
 - (ii) its *application's priority* in the *queue* is now the *priority* that its *application* would have had in accordance with the *first come first served* principle if it had not been designated as a *project-related application*.

Reserve capacity auctions for SWIS

A2.63 [X]⁶³⁷

Processing of applications not affected

- A2.64 Nothing in the *queuing rules* prevents the *service provider* from *processing* more than one *application* concurrently.
- A2.65 To avoid doubt, the *service provider* must comply with the timeframes set out in this *applications and queuing policy* in respect of each *application* which is lodged with the *service provider*, whether or not it is *processing* more than one *application* concurrently.

Exercising an option not affected

- A2.66 An option granted to a *user* as part of the terms of an *access contract* to extend the duration of the *access contract* is not an *application* and is not subject to the *queuing rules* if it is exercised in accordance with its terms.

⁶³⁷ If applicable, insert provisions regarding *processing of applications* made in connection with a tender process under a *law* made under Part 9 of the *Act*. To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. See section 5.7(h) of the *Code*.

Priority of withdrawn applications

A2.67 An *application* which is withdrawn or deemed by this *access arrangement* to have been withdrawn loses its *priority* under the *queuing rules*, even if it is subsequently amended or resubmitted.

Provision of information about position in queue

A2.68 The *service provider* must make known to any *applicant* with an *application* in a *queue*:

- (a) in respect of each *competing application* in the *queue*:
 - (i) the fact that the *competing application* exists in the *queue*; and
 - (ii) whether the *competing application* is ahead of, or behind, the *applicant's* position in the *queue* and if any of the *competing applications* are *project-related applications*; and
- (b) a description of the circumstances which caused the *applications* in the *queue* to be *competing applications* (including information in reasonable detail regarding the aggregated capacity requirements of those *competing applications* which are ahead of the *applicant* in the *queue*); and
- (c) the likely time until the making of an *access offer*, the commissioning of any necessary *augmentation* and the undertaking of any other *required work*; and
- (d) except to the extent that it is prevented from doing so by clause A2.12, in respect of each *competing application* in the *queue*:
 - (i) the capacity requirements of the *competing application*; and
 - (ii) the geographic location at which the *competing application* seeks the capacity; and
 - (iii) reasonable details regarding any work required by the *competing application*.⁶³⁸

A2.69 The information in clause A2.68 must be provided:

- (a) upon initial lodgement of an application; and
- (b) at any time after a reasonable request by the *applicant* for updated information; and
- (c) as soon as practicable after a material change in the information previously notified under this clause A2.69, including when information of the kind referred to in clause A2.68(d) which was previously withheld on the ground that the *service provider* was prevented from doing so by clause A2.12 is no longer entitled to be withheld on that ground.

⁶³⁸ Clause A2.68 amended by WAGG No 180, 22 October 2008

Subappendix 2.5 – Amendment and withdrawal of application

Amendment to application

A2.70 An *applicant* may at any time by notice to the *service provider* amend an application.

A2.71 Without limiting clause A2.70, an amendment to an application may include a change to the identity of the *applicant* in which case the other information in the application must also be amended accordingly.

Amending application to address necessary work⁶³⁹

A2.72 Without limiting clause A2.70, if an application would require any *required work* or result in the *user* being required to pay a *headworks charge*, then at any time after the *service provider* provides the necessary information the *applicant* may revise its application to add to the application the terms of a *payment contract* or (except in connection with the *headworks charge*) a works contract under the *contributions policy*.⁶⁴⁰

Priority of amended applications

A2.73 Subject to clause A2.74, an amended application has the same *priority* as the original application.

A2.74 Subject to clause A2.75, if an amended application is *materially different* from the original application, and if the difference is such that an *applicant* whose *competing application* has a date of *priority* subsequent to the original application is materially prejudiced in terms of the likelihood, timing and terms of its obtaining *access* (compared with that later *applicant's* position with respect to the original application), then:

- (a) if it is possible to construe the amended application as a combination of the original application and a notional supplementary application (whether for further *capacity* or otherwise) — then the original application retains its *priority* and the notional supplementary application has *priority* according to the time of amendment; but
- (b) otherwise — the amended application has *priority* according to the time of amendment.

A2.75 For the purposes of clause A2.74, without limiting the ways in which an amended application may be *materially different* to the original application, an amended application is not *materially different* from the original application:

- (a) in terms of the capacity sought in the application, if the capacity sought in the amended application is $\pm[x]$ ⁶⁴¹ % of the capacity sought in the original application; and

⁶³⁹ Heading to clause A2.68 amended by WAGG No 180, 22 October 2008

⁶⁴⁰ Clause A2.68 amended by WAGG No 180, 22 October 2008

⁶⁴¹ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. The value inserted for variable $[x]$ should allow for the normal fine-tuning of output or load

- (b) in terms of the *charges* payable under the application, if the *charges* payable under the amended application are $\pm [x]^{642}$ % of the *charges* payable under the original application; and
- (c) to the extent that the amendment deals with the matters in clause A2.72; and
- (d) $[x]^{643}$

Withdrawal of application

A2.76 An *applicant* may at any time before it enters into an *access contract*, by notice in writing to the *service provider* withdraw an application.

Applications do not expire

A2.77 Subject to clause A2.78, an application does not expire due to the passage of time.

A2.78 Where the *service provider* holds the opinion as a *reasonable and prudent person* that it is unlikely that an *access offer* will be made in respect of a *dormant application*, then the *service provider* must give the *applicant* a notice requiring the *applicant* to provide information to the *service provider* demonstrating why the *dormant application* should not be taken to have been withdrawn by the *applicant*.

A2.79 At least $[x]^{644}$ *business days* after giving a notice under clause A2.78, the *service provider* must make a fresh determination, having regard to all *relevant material* including anything which has occurred, and any information provided, since the notice was given under clause A2.78 whether the *dormant application* should be taken to have been withdrawn by the *applicant*.

A2.80 If the *service provider* makes a determination under clause A2.79 that the *dormant application* should be taken to have been withdrawn by the *applicant* then the *dormant application* is deemed to have been withdrawn by the *applicant*.

as a *project* is developed. It is not intended to accommodate a material reconfiguration of the project (e.g. adding or removing a processing unit), nor to facilitate 'gaming' of the *queue*.

⁶⁴² To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*. The value inserted for variable $[x]$ should allow for the normal fine-tuning of output or load as a project is developed. It is not intended to accommodate a material reconfiguration of the *project* (e.g. adding or removing a processing unit), nor to facilitate 'gaming' of the *queue*.

⁶⁴³ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*, if applicable. If there are to be other criteria inserted in the *access arrangement*, to be taken into account when determining if an amended *application* is *materially different* from the original *application*, add "(d)".

⁶⁴⁴ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*, if applicable. Unless the *Authority* considers that the *Code objective* and the objectives in section 5.7 require otherwise, the value inserted for variable $[x]$ should not be less than 20.

Subappendix 2.6 – Processing the application and making the *access offer*

Service provider must be expeditious and diligent

A2.81 The *service provider* must process an application expeditiously and diligently.

Conditions precedent permitted in access contract

A2.82 The *service provider* and an *applicant* must negotiate in good faith regarding any conditions precedent that the *applicant* or *service provider* seeks to have included in an *access contract* in order to achieve the objectives set out in clause A2.83.

A2.83 The objectives of this *applications and queuing policy* with regard to conditions precedent are:

- (a) conditions precedent in *access contracts* should facilitate the development of electricity consuming and generating projects and provide flexibility; and
- (b) conditions precedent should not unduly impede the ability of the *service provider* to provide a *covered services* to *applicants* with later *priority* or cause uncertainty and delay; and
- (c) conditions precedent should not constitute an inappropriate barrier to entry into a market or be for the purpose of hindering or preventing *access* by any person to *covered services*.

Conditions precedent and determination of spare capacity

A2.84 In determining whether there is sufficient *spare capacity* to provide *covered services* requested in an application the *service provider*:

- (a) subject to clause A2.84(b), must regard any conditional *access contract* as being unconditional; and
- (b) must, for the purposes of determining *spare capacity* only, disregard its obligation to provide *covered services* under any conditional *access contract* that contains a condition precedent for which a period of longer than 18 months from the date the *access contract* was entered into is allowed for its fulfilment.

A2.85 To avoid doubt nothing in clause A2.84 prevents a *service provider* or an *applicant* from entering into an *access contract* that contains a condition precedent for which a period of longer than 18 months from the date the *access contract* was entered into is allowed for its fulfilment.

Security

A2.86 If the *service provider* determines that an *applicant's* technical or financial resources are such that a *reasonable and prudent person* would consider there to be a material risk that the *applicant* will be unable to meet its obligations under any *access contract* which results from the *applicant's* application, then the *service provider* may, subject to clause A2.87, require as a term of the *access contract* either or both of the following:

- (a) a provision, at the *applicant's* election, requiring the *applicant* to
 - (i) pay the *charges* for up to 2 months' *services* in advance; or
 - (ii) provide a bank guarantee in terms acceptable to the *service provider* (acting as a *reasonable and prudent person*), guaranteeing the *charges* for 2 months' *services*; or
 - (iii) if applicable, procure from the *applicant's* parent company a guarantee substantially in the form set out in the *service provider's access arrangement* guaranteeing the *charges* under the *access contract*;

and

- (b) if the *applicant* will be required to make a *contribution*, a provision, at the *applicant's* election, requiring the *applicant* to:
 - (i) provide a bank guarantee in terms acceptable to the *service provider* (acting as a
 - (ii) *reasonable and prudent person*), guaranteeing the *contribution*; or
 - (iii) if applicable, procure from the *applicant's* parent company a guarantee substantially in the form set out in the *service provider's access arrangement* guaranteeing the *contribution*.⁶⁴⁵

A2.87 If the *service provider* requires an *applicant* to provide security under clause A2.86, then:

- (a) the *applicant* may propose alternative arrangements (for example, more frequent payment) to manage the *service provider's* financial risk under the *access contract*, and
 - (b) if so, the *service provider* and the *applicant* must negotiate as *reasonable and prudent persons*, with a view to agreeing on alternative arrangements which meet the following objectives:
 - (i) minimising the extent to which the *service provider's* requirement for security from the *applicant* constitutes a barrier to the *applicant's* entry to a market; and
 - (ii) not contravening section 115 of the Act, and not otherwise hindering the *applicant's* ability to compete in upstream or downstream markets,
- but also in the view of a *reasonable and prudent person*:
- (iii) reasonably addressing the risk to the *service provider* that the *applicant* may be unable to meet the *applicant's* obligations under the *access contract*; and

⁶⁴⁵ Clause A2.86 amended by WAGG No 180, 22 October 2008

- (iv) being reasonably practicable for the *service provider* to administer.

A2.88 For the purposes of clauses A2.86 and A2.87, a reference:

- (a) to an *applicant* includes a *user* where the *user* has lodged a *capacity increase notice* or *customer transfer request*; and
- (b) to an application includes a *capacity increase notice* or *customer transfer request*.

Initial response

A2.89 Subject to clause A2.91, the *service provider* must provide an *initial response* to the *applicant* specifying:

- (a) if the application is a *class 1 application* or *class 2 application*, advising the *service provider's* classification of the application; or
- (b) if the application is a *class 3 application* advising the *service provider's* classification of the application and specifying:
 - (i) the time by which the *service provider* will provide a *preliminary assessment* (if requested); and
 - (ii) the time by which the *service provider* expects to make an *access offer*; and
 - (iii) whether the application has caused the *service provider* to give a notice under clause A2.53 to any person.

A2.90 The *initial response* must be provided:

- (a) for a *class 1 application* — within $[x]^{646}$ *business days* after the application is lodged; or
- (b) for a *class 2 application* — within $[x]^{647}$ *business days* after the application is lodged; or
- (c) for a *class 3 application* — within $[x]^{648}$ *business days* after the application is lodged.

A2.91 If, by the time by which the *service provider* is required to give an *applicant* an *initial response* under clause A2.90, the *service provider* has given the *applicant* an *access offer*, the *service provider* is not required to provide an *initial response* to the *applicant*.

⁶⁴⁶ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*, if applicable. Unless the *Authority* considers that the *Code objective* and the objectives in section 5.7 require otherwise, the value inserted for variable $[x]$ should not exceed 5.

⁶⁴⁷ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*, if applicable. Unless the *Authority* considers that the *Code objective* and the objectives in section 5.7 require otherwise, the value inserted for variable $[x]$ should not exceed 5.

⁶⁴⁸ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*, if applicable. Unless the *Authority* considers that the *Code objective* and the objectives in section 5.7 require otherwise, the value inserted for variable $[x]$ should not exceed 20.

A2.92 An *initial response* is not binding on a *service provider*, and the *service provider* is not liable for any error or omission, which is made as a *reasonable and prudent person*, in an *initial response*.

Preliminary assessment

A2.93 If an application contains a request for a *preliminary assessment* of a *class 3 application*, the *service provider* must give the *applicant* a *preliminary assessment* setting out at least the following information:

- (a) whether it is likely that there is sufficient *spare capacity* to provide the requested *covered services* or whether any *required work* is likely to be required to provide those *covered services*, including whether it is likely that any new *connection assets* will be required to provide the *covered services* requested in the application; and
- (b) whether or not a *contribution* is likely to be required from the *user* under the *contributions policy* and an estimate of the amount of the *contribution* which will be sought; and
- (c) a good faith estimate of the likely time required for the undertaking of any *required work*; and
- (d) a description of what system or other studies are likely to be required in the *processing* of the application, information regarding whether the *service provider* is able to undertake the studies and an estimate of the approximate costs of such studies.⁶⁴⁹

A2.94 If, by the time by which the *service provider* is required to give an *applicant* a *preliminary assessment* under clause A2.93, the *service provider* has given the *applicant* an *access offer*, the *service provider* is not required to provide a *preliminary assessment* to the *applicant*.

A2.95 The *preliminary assessment* must be provided as soon as practicable after the application is lodged, having regard to the nature of the application.

Progress reporting

A2.96 An *applicant* must upon request by the *service provider* (which request must not be made more frequently than once per month) provide a progress report to the *service provider* containing information in reasonable detail regarding its application, including whether there has been any material change in any information previously provided by the *applicant*.

A2.97 The *service provider* must upon request by the *applicant* (which request must not be made more frequently than once per month) provide a progress report to the *applicant* containing information in reasonable detail regarding the *processing* of the application, including:

- (a) whether there has been any material change in any estimates of costs or times previously provided by the *service provider*; and

⁶⁴⁹ Clause A2.93 amended by WAGG No 180, 22 October 2008

- (b) if the application requests a *preliminary assessment*, whether there has been any material change in any of the matters listed in clause A2.93.

A2.98 If an *applicant* has requested a *preliminary assessment* the *applicant* must not request a progress report until one month after the *applicant* has received the *preliminary assessment*.

Service provider must make access offer

A2.99 The *service provider* must, acting as a *reasonable and prudent person*, give an *access offer* to the *applicant* as soon as practicable, and in any event must (subject to clause A2.100) do so within:

- (a) for a *class 1 application* — [*x*]⁶⁵⁰ *business days* after the application is lodged; or
- (b) for a *class 2 application* — [*x*]⁶⁵¹ *business days* after the application is lodged; or
- (c) for a *class 3 application* — as soon as practicable after the application is lodged, having regard to the nature of the application.

Extension of time to perform obligations

A2.100 If:

- (a) the *service provider* (acting as a *reasonable and prudent person*) has requested further information from the *applicant* under clause A2.28 which it reasonably requires to process the application; and
- (b) the request was made as soon as the *service provider* became aware that it required the information; and
- (c) the *service provider* has expeditiously and diligently progressed the *processing* of the application before making the request, after receiving the information, and (to the extent possible) between making the request and receiving the information,

then the time period for complying with any other obligation under this *applications and queuing policy* is extended by an amount of time equal to the time taken by the *applicant* to comply with the request.

A2.101 An *applicant* and the *service provider* may agree to deal with any matter in connection with the *applicant's* application in a manner different to the treatment of the matter in this *applications and queuing policy* as long as the ability of the *service provider* to provide a *covered service* that is sought by another *applicant* is not impeded.

⁶⁵⁰ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*, if applicable. Unless the *Authority* considers that the *Code objective* and the objectives in section 5.7 require otherwise, the value inserted for variable [*x*] should not exceed 5.

⁶⁵¹ To be inserted when the *model applications and queuing policy* is incorporated into an *access arrangement*, if applicable. Unless the *Authority* considers that the *Code objective* and the objectives in section 5.7 require otherwise, the value inserted for variable [*x*] should not exceed 10.

A2.102 Without limiting the generality of clause A2.101, an *applicant* and the *service provider* may agree to extend any one or more of any of the time periods set out in this *applications and queuing policy* on one or more occasions, and:

- (a) the time period is extended by the amount of time agreed; and
- (b) unless otherwise agreed, the time for complying with any other obligation is extended by the same amount of time.

Terms of access offer – If application requests reference service

A2.103 If an application requests a *reference service* on terms materially the same as those set out for the *reference service* in the *access arrangement*, then:

- (a) if the application is a *class 1 application* — the *access offer* must be on materially the same terms as those requested in the application except (subject to clause A2.104) for the terms relating to any security or other prudential requirements, which must be determined in accordance with clauses A2.86 and A2.87; and
- (b) if the application is a *class 2 application* — the *access offer* must be on materially the same terms as those requested in the application except (subject to clause A2.104) for the terms relating to any security or other prudential requirements, which must be determined in accordance with clauses A2.86 and A2.87; and
- (c) if the application is a *class 3 application* — the *access offer* must be on materially the same terms as those requested in the application except (subject to clause A2.104) for the terms relating to:
 - (i) any *contribution* (including the terms of any works contract or *payment contract*); and
 - (ii) any other provisions necessary to deal with any *required work*; and
 - (iii) the *services start date*, however the *access offer* must not specify an earlier *services start date* where doing so may impede the ability of the *service provider* to provide a *covered service* that is sought by another *applicant*; and
 - (iv) any security or other prudential requirements, which must be determined in accordance with clauses A2.86 and A2.86(b)(iii).⁶⁵²

A2.104 Any terms in an *access offer* under clause A2.103(c) or clause A2.103(b) dealing with a matter listed under that clause must be:

- (a) consistent with the *Code objective*; and
- (b) reasonable; and
- (c) subject to clauses A2.104(a) and A2.104(b), as similar as practicable to any terms requested in the application dealing with the matter.

⁶⁵² Clause A2.103 amended by WAGG No 180, 22 October 2008

Terms of access offer – If application requests non-reference service

A2.105 If an application requests a non-*reference service* then the terms of the *access offer* must be:

- (a) consistent with the *Code objective*; and
- (b) reasonable; and
- (c) subject to clauses A2.105(a) and A2.105(b), as similar as practicable to any terms requested in the application dealing with the relevant matter.

Arbitrator's powers preserved

A2.106 Nothing in clauses A2.103 to A2.105 limits the *arbitrator's* power to make an award compelling the *service provider* to provide *access* to a *covered service* on terms specified in the award.

Access offer is not a contract

A2.107 Despite the giving of an *access offer* by the *service provider* to the *applicant*, the *service provider* and the *applicant* will not be taken to have entered into an *access contract* until the *applicant* has *signed* that document.

Applicant's options on receipt of an access offer

A2.108 The *applicant* must as soon as practicable, and in any event within 30 *business days*, after receipt of an *access offer*, either:

- (a) *sign* the *access offer*, thereby entering into an *access contract*; or
- (b) by notice to the *service provider* reject the *access offer* and request amendments to the application; or
- (c) by notice to the *service provider* withdraw the application,

and if 30 *business days* after receipt of the *access offer* the *applicant* has not complied with any of clauses A2.108(a), A2.108(b), or A2.108(c), then (unless the *arbitrator* makes an order extending the time limit on the ground that the delay is beyond the *applicant's* reasonable control) the *applicant* is to be taken to have withdrawn its application.

A2.109 If the *applicant* rejects an *access offer* and requests amendments to the application under clause A2.108(b), the *service provider* must:

- (a) deal with the amended application in accordance with clauses A2.73 to A2.75; and
- (b) make a further *access offer* to the *applicant* which incorporates the *applicant's* requested amendments as soon as practicable in accordance with this *applications and queuing policy*.

If applicant accepts access offer

A2.110 If the *applicant signs* the *access offer*, it must:

- (a) forthwith give written notice of the *signing* to the *service provider*;
- (b) as soon as practicable procure the stamping of the *signed access contract*;
and
- (c) as soon as practicable thereafter give to the *service provider* at least one original copy of the *signed* and stamped *access contract*.

A2.111 Upon an *applicant signing* an *access offer*, the application in response to which the *access offer* was made ceases to exist.

Appendix 2A – Transitional Western Power Network Applications and Queuing Policy⁶⁵³

⁶⁵³ Appendix 2A inserted by WAGG No 134, 30 July 2021

Appendix 3 – Model Standard access contract

654

{This Appendix 3 contains four parts.

Part A contains definitions and commencement provisions, and is included in all *access contracts*.

Part B contains provisions dealing with *capacity services*. It forms part of the *capacity contract*.

Part C contains provisions dealing with technical compliance. It forms part of the *technical compliance contract*.

Part D contains general contractual provisions, and is included in all *access contracts*.

An *access contract* can comprise:

- a “**capacity contract**” based on Part B, together with Parts A and D; and
- a “**technical compliance contract**” based on Part C, together with Parts A and D; and
- a contract which is both a “**capacity contract**” and a “**technical compliance contract**”, containing all four Parts.}

This Appendix 3 leaves some matters to be completed. These matters are noted in square brackets, and fall into two categories:

- Matters which are to be completed when an *access contract* is incorporated into an *access arrangement* is approved by the *Authority* under Chapter 4. Without limiting the *Authority’s* discretion or duties, the way these matters are dealt with must be consistent with the *Code objective* and section 5.4(a).
- Matters which are to be agreed by the *parties* during the *access contract* negotiations, or determined by the *arbitrator* when determining an *access dispute*.

Footnotes following each matter in square brackets denote which category the matter falls into, and provide guidance as to the content of the matter. The footnotes form part of this model *standard access contract* and have legal effect.

Agreement dated

Parties

This is a contract between

[Insert name of service provider]⁶⁵⁵ ("**service provider**")

and

[Insert name of user]⁶⁵⁶ ("**UserCo**")

[X]⁶⁵⁷

Background

- (a) *UserCo* has made an *access application* under the *access arrangement*.
- (b) *Service provider* has made an offer, in accordance with the *access arrangement*, to provide *covered services* to *UserCo*.
- (c) *UserCo* has accepted the offer.
- (d) [X]⁶⁵⁸

Part A – Interpretation and introduction

{Note: Refer to clause A3.11 for when this Part A applies.}

Definitions and interpretation

A3.2 In this contract the following terms have the following meanings, unless the contrary intention is apparent:

"access arrangement" means the *access arrangement* approved in respect of the *network* under the *Code*.

"access rights", in clauses A3.103 to A3.105, means all or part of *UserCo's* rights under this contract to obtain a *covered service*.

"accounting period" means [X]⁶⁵⁹.

⁶⁵⁵ To be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁶⁵⁶ To be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁶⁵⁷ If there is to be an *indemnifier*, insert name of *indemnifier* and add: ("**indemnifier**"). Whether there is to be an indemnifier is to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁶⁵⁸ If there is to be an *indemnifier*, add: " (d) The *indemnifier* has agreed to indemnify *service provider* in respect of certain of *UserCo's liabilities*."

⁶⁵⁹ Insert the period in respect of which invoices are rendered. To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access*

“**Act**” means the *Electricity Industry Act 2004*.

“**affected obligation**”, in respect of a *force majeure event*, means the obligation (other than an obligation to pay money) that the *affected person* is unable, wholly or in part to perform because of the *force majeure event*.

“**affected person**”, in respect of a *force majeure event*, means a *party* who is unable, wholly or in part, to perform an *affected obligation*.

“**affected service**” has the meaning given to it in clause A3.42(b).

“**affected service period**”⁶⁶⁰ has the meaning given to it in clause A3.42(b).

“**applications and queuing policy**” means the *applications and queuing policy* in the *access arrangement*.

“**augmentation**”, in relation to the *network*, means an increase in the capability of the *network* to provide *covered services*.⁶⁶¹

“**authorised officer**” means the authorised officer of a *party* as specified in Schedule 9 to whom notice, approval, consent or other communications may be given.

“**Authority**” means the Economic Regulation Authority established by the *Economic Regulation Authority Act 2003*.

“**bare transfer**” means a *transfer* of all or part of *UserCo's access rights* in which *UserCo's* obligations under this contract, and all other terms of this contract, remain in full force and effect after the *transfer*.

“**business day**” means a day that is not a Saturday, Sunday or public holiday throughout Western Australia.

“**capacity**” refers to the capacity of the *network* or a *connection point* to transfer electricity.

“**capacity contract**” means an *access contract* (as defined in the *Code*) containing provisions materially equivalent to those in Parts A, B and D of this contract.

“**capacity increase notice**” has the meaning given to it in clause A3.17.

“**CEO meeting**” means a meeting under clause A3.97 between the senior executive officers of each *party* to attempt to resolve a dispute.

“**charge**” for a service for an *accounting period* means the amount that is payable by *UserCo* to *service provider* for the service, calculated by applying the *tariff* for the service, during the *accounting period*.

arrangement may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁶⁶⁰ Clause A3.2 amended by WAGG No 207, 8 November 2005

⁶⁶¹ Clause A3.2 amended by WAGG No 180, 22 October 2008

“**claim**” means any claim, demand, action or proceeding made or instituted against a *party* in respect of which that *party* may under this contract, seek to claim indemnity under this contract against the other *party*.

“**Code**” means the Electricity Networks Access Code 2004.

“**Code objective**” has the meaning given to it in section 2.1 of the *Code*.

“**commencement date**” means the date specified in item 1⁶⁶² of Schedule 1.

“**common service**” means a *covered service* that is ancillary to the provision of one or more of *entry services*, *exit services* and *network use of system services* that ensures the reliability of the *network* or otherwise provides benefits to *users* of the *network*, the costs of which cannot reasonably be allocated to one or more particular *users* and so need to be allocated across all *users*.

“**communication**” means a notice, approval, consent or other communication given or made under this contract.

“**confidential information**” means information which is confidential under clause A3.109.

“**connect**” means to form a physical link to or through the *network*.

“**connection assets**”, for a *connection point*, means all of the *network assets* that are used only in order to provide *covered services* at the *connection point*.

“**connection point**” means a point on the *network* identified in this contract as an *entry point* or *exit point* under this contract.

“**connection service**” means the right to *connect facilities and equipment* at a *connection point*.

{Note: A *connection service* is the right to physically *connect* to the *network*, and will regulate technical compliance etc. It is not the same thing as an *entry service* or *exit service*, which are the right to *transfer* electricity.}

“**contestable**”, in relation to a *consumer*, means a *consumer* whose *load* exceeds the threshold prescribed under Schedule 6 clause 2(1b) of the *Electricity Transmission and Distribution Systems (Access) Act 1994* or another enactment.⁶⁶³

“**contracted point**” has the meaning given to it in clause A3.19(b)(i).

“**contract maximum demand**” or “**CMD**” for a *connection point* means the maximum amount of electricity that *UserCo* may *transfer* out of the *network* at the *connection point* being either:

- (a) the amount specified in Schedule 3 from time to time in respect of the *connection point*; or

⁶⁶² Clause A3.2 amended by WAGG No 207, 8 November 2005

⁶⁶³ Appendix 3 clause A3.2 amended by WAGG No 59, 31 March 2006

- (b) if no amount is specified in Schedule 3, the maximum amount of electricity permitted to be transferred through the *connection assets* at the *connection point* under the *technical rules*.

{Note: A *user* is free under the *Code* to seek *access* to a service with a varying *CMD*, which will be a *non-reference service*.}

“contracted capacity” for a *connection point* means:

- (a) for the electricity transferred into the *network*, the *DSOC*; and
(b) for the electricity transferred out of the *network*, the *CMD*.

“contribution” means any amount (which may be either an up-front amount or a periodic amount, as agreed between the *parties*) as specified in Schedule 5.⁶⁶⁴

“contributions policy” means the policy contained in the *access arrangement* dealing with *contributions* by *users*.⁶⁶⁵

“Corporations Act” means the *Corporations Act 2001* of the Commonwealth.

“covered service” means a service provided by means of the *network*, including:

- (a) a *connection service*; or
(b) an *entry service* or *exit service*; or
(c) a *network use of system service*; or
(d) a *common service*, or
(e) a service ancillary to the *services* listed in paragraphs (a) to (d) above,

but does not include an *excluded service*.⁶⁶⁶

“CPI” means the Consumer Price Index (all groups) for the Weighted Average of Eight Capital Cities *published* by the Australian Bureau of Statistics from time to time or, if the Consumer Price Index (all groups) for the Weighted Average of Eight Capital Cities ceases to be *published*, such alternative index as *service provider* acting reasonably and in good faith may determine, and in all cases the *CPI* figure is to be adjusted to correct for any effects of a change in the rate of *GST*.

“curtailment” includes a whole or partial curtailment or whole or partial interruption of a service.

“customer transfer code” means a code made under section 39(1) or section 39(2a) of the *Act* in respect of a matter referred to in section 39(2)(b) of the *Act*.

“default”, in relation to a *party*, is defined in clause A3.85.

⁶⁶⁴ Clause A3.2 amended by WAGG No 180, 22 October 2008

⁶⁶⁵ Clause A3.2 amended by WAGG No 180, 22 October 2008

⁶⁶⁶ Clause A3.2 amended by WAGG No 180, 22 October 2008

“**designated controller**”, where applicable, in respect of a *connection point*, is determined in accordance with clauses A3.36 to A3.39.

“**designated point**” has the meaning given to it in clause A3.36.

“**destination point**” has the meaning given to it in clause A3.19(b).

“**direct damage**” suffered by a person means loss or damage suffered by the person which is not *indirect damage*.

“**disconnect**”, in respect of a *connection point*, means to operate switching or other equipment so as to prevent the *transfer* of electricity through the *connection point*.

“**discounted rate**” means $[x]^{667}$ % p.a.

“**dispute**” means any dispute or difference concerning:

- (a) the construction of; or
- (b) anything contained in or arising out of; or
- (c) the rights, obligations, duties or liabilities of a *party* under,

this contract.

“**DSOC**” or “**declared sent out capacity**” for a *connection point* means the maximum amount of electricity that *UserCo* may *transfer* into the *network* at the *connection point*, being either:

- (a) the amount specified in Schedule 3 from time to time; or
- (b) if no amount is specified in Schedule 3, the maximum amount of electricity permitted to be transferred through the *connection assets* at the *connection point* under the *technical rules*.

{Note: A *user* is free under the *Code* to seek *access* to a service with a varying *DSOC*, which will be a non-*reference service*.}

“**due date**” means the date $[x]^{668}$ *business days* after a *party* receives a *tax invoice* issued under clause A3.44 or A3.45.

“**efficiently minimising costs**” means *service provider* incurring no more costs than would be incurred by a prudent *service provider*, acting efficiently, in accordance with

⁶⁶⁷ To be completed – for example this could be a reference to the overdraft rate *published* by a major bank. To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁶⁶⁸ Insert the number of days to be allowed for payment. To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award. Unless the *Authority* or *arbitrator* consider that a different value will better achieve the *Code objective*, 10 business days should be used.

good electricity industry practice, seeking to achieve the lowest sustainable cost of delivering the *services*.

“Electricity Distribution Regulations” means the *Electricity Distribution Regulations 1997*.

“Electricity Transmission Regulations” means the *Electricity Transmission Regulations 1996*.

“emergency” has the meaning given to it in clause A3.126.

“end date” for a *connection point*, means the date specified as such in Schedule 3 for the *connection point*.

“entry point” means a point on the *covered network* identified as such in this contract at which, subject to this contract, electricity is more likely to be transferred into the *network* than transferred out of the *network*.

“entry service” means a *covered service* provided by *service provider* at an *entry point* under which *UserCo* may *transfer* electricity into the *network* at the *entry point*.

“excluded service” means a service provided by means of the *network*, including:

- (a) a *connection service*; or
- (b) an *entry service* or *exit service*; or
- (c) a *network use of system service*; or
- (d) a *common service*; or
- (e) a service ancillary to the *services* listed in paragraphs (a) to (d) above

which meets the following criteria:

- (f) the supply of the service is subject to effective competition; and
- (g) the cost of the service is able to be excluded from consideration for *price control* purposes without departing from the *Code objective*.⁶⁶⁹

“exit point” means a point on the *covered network* identified as such in this contract at which, subject to this contract, electricity is more likely to be transferred out of the *network* than transferred into the *network*.

“exit service” means a *covered service* provided by *service provider* at an *exit point* under which *UserCo* may *transfer* electricity out of the *network* at the *exit point*.

“facilities and equipment”, in relation to a *connection point*, means the apparatus, equipment, plant and buildings used for or in connection with generating, consuming and transporting electricity at the *connection point*.

⁶⁶⁹ Clause A3.2 amended by WAGG No 180, 22 October 2008

“financial provision”, in relation to a *contribution*, means the payment by *UserCo* of a *contribution* by way of either a periodic financial payment or an up front financial payment, as agreed, in accordance with Schedule 5.⁶⁷⁰

“force majeure” in respect of a *party* means an event or circumstance beyond the *party’s* control, and which the *party* acting as a *reasonable and prudent person* is not able to prevent or overcome, including (where the foregoing conditions are satisfied):

- (a) any act of God, lightning, earthquake, storm, fire, flood, subsidence, land slide, mud slide, wash-out, explosion or natural disaster; or
- (b) any insurrection, revolution or civil disorder, act of public enemies, malicious damage, sabotage, vandalism, war (whether declared or undeclared) or a military operation, blockade or riot; or
- (c) any determination, award or order of any court or tribunal, or any regulatory authority or the award of any *arbitrator* arising after the *commencement date*; or
- (d) any act or omission of government or any government or regulatory department, body, instrumentality, ministry, agency, fire brigade; or
- (e) any inability or delay in obtaining any governmental, quasi-governmental or regulatory approval, consent, permit, licence or authority; or
- (f) any industrial disputes of any kind, strike, lock-out, ban, limitation or other industrial disturbances; or
- (g) any significant plant or equipment failure which could not have been avoided by the exercise of *good electricity industry practice*; or
- (h) any act or omission of any person with *facilities and equipment* connected to the *network* which frustrates the *party’s* ability to perform its obligations under this contract; or
- (i) any application of any *law* of the Commonwealth, any Commonwealth authority, the State, any State authority or any local government; or
- (j) accidents, weather and acts of third parties (such as generators and other *users* of electricity) that affect the quality, frequency and continuity of the supply of electricity.

“force majeure event” means an event of *force majeure*.

“generate” means to produce electricity.

“generating plant” in relation to a *connection point* means all *facilities and equipment* involved in generating electricity.

“good electricity industry practice” means the exercise of that degree of skill, diligence, prudence and foresight that a skilled and experienced person would reasonably and ordinarily exercise under comparable conditions and circumstances

⁶⁷⁰ Clause A3.2 amended by WAGG No 180, 22 October 2008

consistent with applicable *laws* and applicable recognised codes, standards and guidelines.

“**GST**” means goods and *services* tax or similar value added tax levied or imposed in Australia on a taxable supply under the *GST Act* or otherwise.

“**GST Act**” means the *A New Tax System (Goods and Services Tax) Act 1999* of the Commonwealth.

“**guest party**” has the meaning given to it in clause A3.92.

“**host party**” has the meaning given to it in clause A3.92.

“**indemnified party**” has the meaning given to it in clause A3.75.

“**indemnifying party**” has the meaning given to it in clause A3.75.

“**indirect damage**” suffered by a person means:

- (a) any consequential loss, consequential damage or special damages however caused or suffered by the person including any:
 - (i) loss of (or loss of anticipated) opportunity, use, production, revenue, income, profits, business and savings; or
 - (ii) loss due to business interruption; or
 - (iii) increased costs; or
 - (iv) punitive or exemplary damages,whether or not the consequential loss or damage or special damage was foreseeable; or
- (b) in respect of contractual damages, damages which would fall within the second limb of the rule in *Hadley v Baxendale* [1854] 9 Exch. 341; or
- (c) any liability of the person to any other person, or any claim, demand, action or proceeding brought against the person by any other person, and the costs and expenses connected with the claim.

“**information provider**”, in relation to *confidential information*, means the *party* providing the information.

“**information recipient**”, in relation to *confidential information*, means the *recipient* of the information.

“**insolvency event**” in respect of a *party* means any one or more of:

- (a) any suspension or cessation to payment of all or a class of its debts by an insolvent within the meaning of section 95A of the *Corporations Act 2001* of the Commonwealth; or
- (b) any execution or other process of any court or authority issued against or levied upon any material part of that *party's* property or assets; or

- (c) a petition or application is presented (and not withdrawn within 10 *business days*) or an order is made or a resolution is passed for the winding up or dissolution without winding up of that *party* otherwise than for the purpose of reconstruction or amalgamation under a scheme; or
- (d) a receiver or a receiver and manager of the undertaking or any material part thereof of that *party* is appointed; or
- (e) that *party* proposes to enter into or enters into any arrangement, reconstruction or composition with or for the benefit of its creditors; or
- (f) an administrator of that *party* is appointed or the board of directors of that *party* passes a resolution to the effect that is specified in section 436A(1) of the *Corporations Act 2001* of the Commonwealth; or
- (g) that *party* fails (as defined by section 459F of the *Corporations Act 2001* of the Commonwealth) to comply with a statutory demand; or
- (h) a controller (as defined in the *Corporations Act 2001* of the Commonwealth) is appointed in respect of that *party* or the whole or a material part of that *party's* undertaking, property or assets; or
- (i) application is made to a Court for an order in respect of that *party* under Part 2F.1 of the *Corporations Act 2001* of the Commonwealth; or
- (j) an event referred to in section 459C(2) of the *Corporations Act 2001* of the Commonwealth occurs in respect of that *party*; or
- (k) anything analogous or having a substantially similar effect to any of the events specified above occurs under the *law* of any applicable jurisdiction.

“integrated provider” means:

- (a) [not used]⁶⁷¹
- (b) if *service provider* is not Western Power Corporation - *service provider*, if under section 13.31⁶⁷² of the *Code*, *service provider* has been given an exemption from section 13.11(a) of the *Code*.

“interconnected system” means an electricity system comprising two or more *networks* interconnected with each other, and in relation to the *network* means an *interconnected system* of which the *network* is a part.

“law” means “written laws” and “statutory instruments” as defined in the *Code*, orders given or made under a written law or statutory instrument as so defined or by a government agency or authority, Codes of Practice and Australian Standards and rules of the general law including the common law and equity.

“load” means the amount of electrical power transferred out of the *network* at a *connection point* at a specified time.

⁶⁷¹ Clause A3.2 amended by WAGG No 180, 22 October 2008

⁶⁷² Appendix 3 clause A3.2 amended by WAGG No 59, 31 March 2006

“**maintain**” includes (as necessary and as applicable) calibrate, test, verify, renew, replace, repair and update.

“**market rules**” means the ‘market rules’ referred to in section 123(1) of the *Act*.

“**metering equipment**” means equipment to measure and record electricity as transferred to or from the *network* at a *connection point*.

“**network**” means the *network* (as defined in the *Code*) owned, operated or owned and operated by *service provider* in respect of which access is given under this contract.

“**network assets**”, in relation to the *network*, means the apparatus, equipment, plant and buildings used to provide or in connection with providing *covered services*. on the *network*, which assets are either *connection assets* or *shared assets*.

“**network business**” means the part of an *integrated provider’s* business and functions which is responsible for the operation and maintenance of the *network* and the provision of *covered services* by means of the *network*.

“**other business**” means the part or parts of an *integrated provider’s* business which are not the *network business*, and includes any part or parts of the *integrated provider’s* business and functions which acquire *covered services* from the *network business*.

“**party**” means *service provider* or *UserCo* and “**parties**” means both of them.⁶⁷³

“**payment error**” means any underpayment or overpayment by a *party* of any amount in respect of an invoice.

“**possession**” includes custody, control, and an immediate right to possession, custody, or control.

“**prescribed rate**” means the *discounted rate* plus 3% p.a.

“**price list**” means the most recent price list *published* under the *access arrangement* in accordance with the *Code*.

“**reasonable and prudent person**” means a person acting in good faith and in accordance with *good electricity industry practice*.

“**receipt date**” has the meaning given to it in clause A3.96.

“**related body corporate**”, in relation to a body corporate, means a body corporate that is a *related body corporate* to the first-mentioned body corporate under section 50 of the *Corporations Act 2001* of the Commonwealth.

“**relocation**” has the meaning given to it in clause A3.19.

“**representatives meeting**” means a meeting under clause A3.96 between a duly authorised representative of each *party* to attempt to resolve a dispute.

⁶⁷³ If there is to be an *indemnifier*, insert after “both of them.”: “In relation to *indemnifier*, “**other party**” means *service provider*.”

“**service**”, in respect of a *connection point*, means a service to be provided under this contract in respect of the *connection point* as specified in Schedule 2, and if applicable (including if the service is an *entry service* or an *exit service*) includes the *transfer* of electricity at a *connection point*.

“**service provider’s default**” means an event of *default* by *service provider*.

“**service provider’s premises**” means the land on which the *service provider’s works* are located.

“**service provider’s works**” means the works referred to in Schedule 6.

“**service standards**” for a service means:

- (a) the technical standard, and reliability, of delivered electricity specified for the service in Schedule 2; or
- (b) if nothing is specified for the service in Schedule 2 — the service standard (as defined in the *Code*) applying in respect of the service under the *access arrangement*.

“**shared assets**” means *network assets* which are not *connection assets*.

“**standing charges**” has the meaning given to it in clause A3.42(a).

“**start date**”, for a *connection point*, means the date specified as such in Schedule 3 for the *connection point*.

“**supplementary matters**” means the following matters: balancing; line losses; metering; ancillary *services*; stand-by; trading; settlement; and, any other matter in respect of which arrangements must exist between *UserCo* and *service provider* to enable the efficient operation of the *network* and to facilitate *access* to *services* under this contract, in accordance with the *Code objective*.

“**system operator**” for the *network* means, unless the *technical rules* provide otherwise, the person or persons who:

- (a) operate and control the system operation control centre; or
- (b) where there is no system operation control centre — is responsible for the control of the *network* through monitoring, switching and dispatch; or
- (c) where the system operation control centre and another party are both responsible for the control of the *network* through monitoring, switching and dispatch — perform either (a) or (b).

“**tariff**”, for a service, means the tariff specified for the service in Schedule 4.

“**tax invoice**” has the meaning given to that term in the *GST Act*.

“**technical compliance contract**” means an *access contract* (as defined in the *Code*) containing provisions materially equivalent to those in Parts A, C and D of this contract.

“**technical rules**” means the *technical rules* applying from time to time to the *network* under Chapter 12 of the *Code*.

“**term**” means the term of this contract which commences on the *commencement date* and ends on the *termination date*.

“**termination date**” means the date specified in item 2⁶⁷⁴ of Schedule 1.

“**third party recipient**” means any person to whom the information *recipient* discloses *confidential information*, or allows *confidential information* to be disclosed.

“**transfer**”, when used in clauses A3.105 and A3.106, includes assign and novate.

“**transport**” includes transmit and distribute.

“**uncontracted point**” has the meaning given to it in clause A3.19(b)(ii).

“**undisputed portion**” means, subject to clause A3.45(d), an amount shown on a *tax invoice* which a *party* does not dispute to be payable.

“**unpaid portion**” has the meaning given to it in clause A3.51(b).

“**user**” means a person, including a generator or a *consumer*, who is party to a *contract for services* with a *service provider*, and under section 13.4(e) of the *Code* includes an *other business* as a party to a deemed *access contract* (where the terms “generator”, “*consumer*”, “*access contract*”, “*other business*” and “*deemed access contract*” have the meanings they are given in the *Code*).⁶⁷⁵

“**UserCo’s default**” means an event of *default* by *UserCo*.

“**UserCo’s premises**” means the land on which *UserCo’s* works are located.

“**UserCo’s works**” means the works referred to in Schedule 7.

“**variation request**”, in relation to a *connection point*, means a request from *UserCo* to *service provider* to vary the *contracted capacity* at the *connection point*.

“**visitors**” means the customers, invitees, licensees and visitors of a *party*.

“**workers**” means the directors, officers, servants, employees, agents and contractors of a *party*.

“**year**” means calendar year.

Interpretation

A3.3 In this contract, unless the contrary intention appears:

- (a) a reference to:
 - (i) one gender includes any other gender; and
 - (ii) the singular includes the plural and the plural includes the singular; and

⁶⁷⁴ Clause A3.2 amended by WAGG No 207, 8 November 2005

⁶⁷⁵ Clause A3.2 amended by WAGG No 180, 22 October 2008

- (iii) an officer or body of persons includes any other officer or body for the time being exercising the powers or performing the functions of that officer or body; and
 - (iv) this contract or any other instrument includes any variation or replacement of it; and
 - (v) a reference to a “**law**” includes any amendment or re-enactment of it that is for the time being in force, and includes all laws made under it from time to time; and
 - (vi) “**under**” includes “by”, “by virtue of”, “pursuant to” and “in accordance with”; and
 - (vii) “**day**” means a calendar day; and
 - (viii) “**person**” includes a public body, company, or association or body of persons, corporate or unincorporated; and
 - (ix) a person includes a reference to the person's personal representatives, executors, administrators, successors and permitted assigns; and
 - (x) all monetary amounts are in Australian dollars and are exclusive of GST; and
- (b) if a period of time is specified and dates from a given day or the day of an act or event, it is to be calculated exclusive of that day; and
 - (c) headings are for convenience only and do not affect the interpretation, or form part of, this contract; and
 - (d) “**copy**” includes a facsimile copy, photocopy or (subject to the Electronic Communication Protocol in Schedule 10) electronic copy; and
 - (e) “**including**” and similar expressions are not words of limitation; and
 - (f) where a word or expression is given a particular meaning, other parts of speech and grammatical forms of that word or expression have a corresponding meaning; and
 - (g) where italic typeface has been applied to some words and expressions, it is solely to indicate that those words or expressions may be defined in clause A3.2 or elsewhere, and in interpreting this contract, the fact that italic typeface has or has not been applied to a word or expression is to be disregarded (but nothing in this clause A3.3(g) limits the application of clause A3.2); and
 - (h) where information in this contract is set out in braces (namely “{” and “}”), whether or not preceded by the expression “Note”, “Outline” or “Example”, the information:
 - (i) is provided for information only and does not form part of this contract; and

- (ii) is to be disregarded in interpreting this contract; and
- (iii) might not reflect amendments to this contract or other documents or laws; and
- (i) a reference to:
 - (i) this contract includes any schedule to this contract; and
 - (ii) a clause is a reference to a clause of this contract.

A3.4 Unless the contrary intention is apparent, the rules of interpretation in the *Interpretation Act 1984* apply to the interpretation of this contract.

Duration

A3.5 Commencement and term

- (a) This contract commences on the *commencement date*.
- (b) This contract ends on the *termination date* (unless terminated earlier in accordance with this contract).

{Note: During the *term* of this contract (i.e. between the *commencement date* and the *termination date*) *service provider* must provide the *services* to *UserCo*. However, for each *connection point*, the obligation on *service provider* to provide those *services* is determined by the *start date* and *end date* for each service.}

A3.6 Option to extend term

⁶⁷⁶

A3.7 Conditions Precedent

⁶⁷⁷

There must be both a capacity contract and a technical compliance contract

A3.8 For each *connection point*, there must be:

- (a) a *capacity contract*; and
- (b) a *technical compliance contract*,

in respect of the *connection point*.

{Note: This contract may deal with one, or more than one, connection⁶⁷⁸ point.}

⁶⁷⁶ Insert option provisions if applicable. To be inserted in the *access contract* by agreement between the parties or arbitrated award. Consequential amendments may be needed to the duration provisions and definitions.

⁶⁷⁷ Insert conditions precedent if applicable. To be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁶⁷⁸ Clause A3.8 amended by WAGG No 207, 8 November 2005

- A3.9 Without limiting the ways in which clause A3.8 may be satisfied, clause A3.8 is satisfied if the *capacity contract* and *technical compliance contract* are both contained in this contract.
- A3.10 *Service provider* is not required to provide *services* at a *connection point* whenever, and for so long as clause A3.8 is not complied with for the *connection point*.

When the parts of this contract apply

- A3.11 For each *connection point*:
- (a) Parts A and D of this contract apply; and
 - (b) if this contract is expressed in Schedule 3 to be a *capacity contract* for the *connection point* — Part B of this contract applies; and
 - (c) if this contract is expressed in Schedule 3 to be a *technical compliance contract* for the *connection point* — Part C of this contract applies.

{Note: This contract may be expressed to be both a capacity contract and a *technical compliance contract*.}

Part B – Capacity Provisions

{Note: Refer to clause A3.11 for when this Part B applies.}

Provision and use

- A3.12 For each *connection point*, on and from the *start date* and up to and including the *end date*:
- (a) *service provider* must provide the *services*; and
 - (b) *UserCo* must pay for and may use the *services*.

Contracted capacity

- A3.13 Subject to this contract, to the extent that a service at a *connection point* relates to *capacity*, *service provider* must provide the service up to the *contracted capacity* for the *connection point*.

Contracted maximum demand and declared sent-out capacity

- A3.14 For each *connection point*, *UserCo* must endeavour as a *reasonable and prudent person* to ensure that:
- (a) the amount of electricity transferred out of the *network* by or on behalf of *UserCo* does not exceed the *CMD*; and
 - (b) the amount of electricity transferred into the *network* by or on behalf of *UserCo* does not exceed the *DSOC*.

Variation to contracted capacity

- A3.15 *UserCo* may submit to *service provider* a *variation request* in relation to a *connection point*.
- A3.16 Subject to clause A3.17, within 10 *business days* after receipt of a *variation request*, *service provider* must determine, and notify *UserCo*, whether or not it accepts the *variation request*.
- A3.17 If in a *variation request* *UserCo* requests *service provider* to increase the *contracted capacity* at a *connection point* ("**capacity increase notice**"), *service provider* must notify *UserCo* that it accepts the *variation request* and the time that the acceptance takes effect, unless:
- (a) accepting the *capacity increase notice* would be likely to impede the ability of *service provider* to provide a service that is sought in an *access application* lodged by another *applicant* under the *applications and queuing policy*; or
 - (b) it is likely that work would be required in response to the *capacity increase notice*,

in either or both cases *service provider* must by notice reject the *capacity increase notice* and state in the notice that to increase its *capacity* as described in the *capacity increase notice* *UserCo* must make an application under the *applications and queuing policy*.⁶⁷⁹

{Note: If *UserCo* wishes to obtain capacity at a *connection point* which is not already specified in Schedule 3, *UserCo* must make an *access application* under the *applications and queuing policy*.}

- A3.18 The *parties* must update Schedule 3 following any variation made in accordance with clauses A3.15 to and A3.17.

Relocation

- A3.19 A "*relocation*" comprises *UserCo*:
- (a) reducing its *capacity* at a *connection point*; and
 - (b) making a corresponding increase in its *capacity* at another *connection point* ("**destination point**") which may be either:
 - (i) a *connection point* at which *UserCo* already has *capacity* ("**contracted point**"); or
 - (ii) a *connection point* at which *UserCo* does not already have *capacity* ("**uncontracted point**").
- A3.20 *UserCo* may apply to *service provider* to undertake a *relocation*, and subject to clauses A3.21, A3.22 and A3.23 *service provider* must permit the *relocation* within 10 *business days* after the application.

⁶⁷⁹ Clause A3.17 amended by WAGG No 180, 22 October 2008

A3.21 Subject to clause A3.23, if the *destination point* is a *contracted point*, then *UserCo* must lodge a *capacity increase notice* or an *access application*, as applicable, in respect of the *capacity* sought to be relocated to the *destination point*, and the *relocation* must not take place until permitted under the *applications and queuing policy*.

A3.22 Subject to clause A3.23, if the *destination point* is an *uncontracted point*, then *UserCo* must lodge an *access application* in respect of the *capacity* sought to be relocated to the *destination point*, and the *relocation* must not take place until permitted under the *applications and queuing policy*.

A3.23 *Service provider* may:

- (a) withhold its consent to a reduction under clause A3.19(a) only on reasonable commercial grounds; and
- (b) impose conditions in respect of a reduction under clause A3.19(a) only to the extent that they are reasonable on commercial grounds.

{An example of a matter that would be reasonable for the purposes of clause A3.23 is *service provider* specifying that, as a condition of its agreement to a *relocation*, the *service provider* must receive at least the same amount of revenue as it would have received before the *relocation*, or more revenue if *tariffs* at the *destination point* are higher.}

A3.24 The *parties* must update Schedule 3 following any variation made in accordance with clause A3.20.

Customer transfer

{Note: See section 5.7(f) of the *Code*.}

A3.25 If a *customer transfer code* places obligations on a *party* in respect of *capacity* or *services* under this contract, the *party* must comply with the obligations.

Provisions of access arrangement on supplementary matters apply

A3.26 The provisions of the *access arrangement* in respect of *supplementary matters* which are incorporated in the *access arrangement* under section 5.27 of the *Code* apply also as terms of this contract, to the extent they are expressed to do so.

Curtailment

A3.27 *Service provider* may, in accordance with *good electricity industry practice*, curtail the provision of *services* in respect of a *connection point*:

- (a) to carry out planned work or maintenance to the *network*; or
- (b) to carry out unplanned maintenance to the *network* where *service provider* considers it necessary to do so to avoid injury to any person or material damage to any property or the environment; or

- (c) in the event of breakdown of or damage to the *network* that affects *service provider's* ability to provide *services* at that *connection point*; or
- (d) if a *force majeure event* occurs affecting *service provider's* ability to provide *services* at the *connection point* for so long as *service provider's* ability to provide *services* is affected by the *force majeure event*; or
- (e) to the extent necessary for *service provider* to comply with a *law*.⁶⁸⁰

A3.28 *Service provider* must keep the extent and duration of any *curtailment* under clause A3.27 to the minimum reasonably required in accordance with *good electricity industry practice*.

A3.29 *Service provider* must use reasonable endeavours to notify *UserCo* of any *curtailment* under clause A3.27 as soon as practicable.

A3.30 If *service provider* notifies *UserCo* of a *curtailment* of *services* under clauses A3.27 to A3.29 in respect of a *connection point*, *UserCo* (acting to the standard of a *reasonable and prudent person*) must comply with any reasonable requirements set out in the notice concerning the *curtailment*.

Title to electricity

A3.31 Title to electricity which is transferred into the *network* at a *connection point* passes from *UserCo* to *service provider* at the time it passes through the *connection point*.

A3.32 Title to electricity which is transferred out of the *network* at a *connection point* passes from *service provider* to *UserCo* at the time it passes through the *connection point*.

A3.33 To avoid doubt, nothing in, and nothing done under or in connection with, this contract causes *UserCo* to acquire any right, title or interest in or to the *network* or any part of it.

A3.34 The operation of clause A3.33 may be displaced by an express provision of this contract.

A3.35 Subject to clause A3.27, upon the *transfer* from *UserCo* to *service provider* of title to and *possession* of a quantity of electricity delivered at an *entry point*, *UserCo* becomes entitled to receive an equivalent quantity of electricity from *service provider* at an *exit point*.

Designated controllers

A3.36 Points which require a designated controller

Each of the following is a “**designated point**” for which there must be a *designated controller*:

- (a) an *entry point* specified in Schedule 3 at which the installed *capacity* of the *facilities and equipment* to *transfer* electricity into the *network* exceeds 30 KVA; and

⁶⁸⁰ Clause A3.27 amended by WAGG No 180, 22 October 2008

- (b) an *exit point* specified in Schedule 3 at which [x].⁶⁸¹

A3.37 **Selecting the designated controller**

- (a) Unless otherwise notified by *UserCo* under clause A3.37(b), the *designated controller* for a *connection point* is the *designated controller* specified in Schedule 3.
- (b) Where:
 - (i) no *designated controller* is specified in Schedule 3 for a *designated point* or *service provider* has objected to the *designated controller* nominated by *UserCo* — *UserCo* must; and
 - (ii) *UserCo* wishes to change the *designated controller* for a *designated point* — *UserCo* may,

by notice to *service provider* nominate a person who owns, operates or controls the *facilities and equipment* at the *designated point* as the *designated controller* for the *designated point* and the person nominated is the *designated controller* from the time of the notice or a later time specified in the notice.
- (c) *Service provider*, acting as a *reasonable and prudent person*, may at any time on reasonable technical or commercial grounds object to the *designated controller* for a *designated point*, in which case *UserCo* must, under clause A3.37(b), either dispute *service provider's* objection under clause A3.96 or nominate a different person as *designated controller*.
- (d) The *parties* must amend Schedule 3 following any variation made in accordance with clause A3.37(b).

A3.38 **User must procure designated controller's compliance**

For each *designated point* *UserCo* must (unless *UserCo* is the *designated controller*) ensure that the *designated controller* complies, and will continue to comply, with the following provisions of this contract, (for which purpose, references to "*UserCo*" in the provisions are to be read as references to "*designated controller*"):

- (a) clauses A3.92 to A3.95 (*access to premises*); and
- (b) clause A3.120 (*notices*); and
- (c) clause A3.55 (*good electricity industry practice*); and
- (d) clause A3.56 (*cooperation*); and
- (e) clause A3.61 (*technical rules*).

⁶⁸¹ To be completed – the test for when an exit point needs a *designated controller*. To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award. [Footnote amended by WAGG No 207, 8 November 2005]

A3.39 UserCo must satisfy service provider of its arrangements with designated controller

- (a) On reasonable request from *service provider*, *UserCo* must (unless the *designated controller* has already entered into an agreement under clause A3.39(b)(i) or A3.39(b)(ii)) provide evidence to *service provider's* satisfaction as a *reasonable and prudent person* that *UserCo* is complying, and will continue to comply, with clause A3.38.
- (b) If *UserCo* does not satisfy *service provider* under clause A3.39(a), *service provider* may curtail the provision of *services* in respect of the *connection point* until the *designated controller* has either:
 - (i) entered into a *technical compliance contract* with *service provider* in respect of the *connection point*; or
 - (ii) otherwise agreed in writing with *service provider* to be bound by the clauses specified in clause A3.38.

{Note: One way for the agreement in clause A3.39(b)(ii) to be reached would be for the *designated controller* to sign this contract as a *party* in respect of the relevant clauses.}

Tariff and charges

A3.40 Tariff

[RETAIN ONE ONLY OF THE FOLLOWING TWO OPTIONS, EITHER:

OPTION A:

- (a) The *tariff* payable under this contract for a service is the *tariff* specified in the *price list* from time to time for the service.
- (b) If:
 - (i) no *price list* is *published* by the *Authority* on the date required under the *Code*, or
 - (ii) a purported *price list* which does not comply with the *access arrangement* is *published*,

then to the extent that the effect of a *price list* (if it had been *published* on the date required under the *Code* and had been compliant with the *access arrangement*) would have been to reduce the *tariff* payable by *UserCo*, then *UserCo* may recover the *tariff* reduction as an overpayment under clause A3.48.

- (c) If applicable, the *tariff* payable under clause A3.40(a) for a service ("**contracted service**") after the end of the current *access arrangement period* is to be determined as follows:
 - (i) if the new *access arrangement* contains a *reference service* ("**equivalent reference service**") which is materially the same as

the contracted service — then the *tariff* for the contracted service is to be the *reference tariff* for the equivalent *reference service*; and

- (ii) if the new *access arrangement* does not contain an equivalent *reference service*, or if for any reason there is no new *access arrangement* — then the *tariff* for a year will be the *tariff* in the final *price list* which *service provider* was required to *publish* under the current *access arrangement*, adjusted annually every $[x]^{682}$ by an amount equal to $[x]^{683}$ % of the change in *CPI* from the previous adjustment date.

- (d) Clause A3.40(c) applies, with appropriate modifications, in respect of the end of each successive *access arrangement period*.

OR OPTION B:

- (a) The *tariff* payable under this contract for a service is the *tariff* specified in the *price list* most recently *published* before the *commencement date* for the service, and any subsequent *price lists* are to be disregarded.
- (b) *Tariffs* determined under clause A3.40(a) are to be adjusted annually every $[x]^{684}$ by an amount equal to $[x]^{685}$ % of the change in *CPI* from the previous adjustment date.

WHICHEVER IS APPLICABLE]⁶⁸⁶

A3.41 Charges

UserCo must pay *service provider* the *charge* for each service calculated at the *tariff* determined under clause A3.40.

⁶⁸² Insert the adjustment date. To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁶⁸³ Insert the percentage of the change in *CPI* from the previous adjustment date. To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award. Unless the *Authority* or *arbitrator* consider that a different value will better achieve the *Code objective*, 67% of *CPI* should be used.

⁶⁸⁴ Insert the adjustment date. To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁶⁸⁵ Insert the percentage of the change in *CPI* from the previous adjustment date. To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award. Unless the *Authority* or *arbitrator* consider that a different value will better achieve the *Code objective*, 67% of *CPI* should be used.

⁶⁸⁶ Unless the *Authority* considers that a different approach will better achieve the *Code objective*, the standard *access contract* must offer *UserCo* the option, at the time it enters into the contract, to make a once-off election for the *term* of the contract as to whether it will pay the *reference tariff* as in effect from time to time (Option A), or whether it will lock in the *reference tariff* in effect at the time of contracting, to be escalated at a percentage of *CPI* (Option B). If Option A is chosen, definitions need to be added to clause A3.2. [Footnote amended by WAGG No 207, 8 November 2005]

A3.42 Charges during service provider's force majeure event

- (a) This clause A3.42 applies in respect of any service for which some or all of the *charges* ("**standing charges**") are payable whether or not *UserCo* makes use of the service.
- (b) If a service ("**affected service**") is unavailable for any consecutive period of 2 days or longer ("**affected service period**") due to a *force majeure event* where *service provider* is the *affected person*, then, for the whole of the *affected service period*, *UserCo* is relieved of its obligation under clause A3.41 and instead must pay 10% of the *standing charges* for the affected service.

A3.43 Contributions

If the *parties* have agreed that *UserCo* must pay a *contribution* the *parties* must comply with the provisions set out in Schedule 5 regarding the *contribution*.⁶⁸⁷

Invoicing and payment

A3.44 Service provider invoices

Service provider must, within 10 *business days* after the end of an *accounting period*, issue to *UserCo* a *tax invoice* for the *accounting period* showing:

- (a) all amounts payable by *UserCo* to *service provider* under this contract; and
- (b) all outstanding amounts as at the end of the *accounting period* and interest payable on those amounts; and
- (c) GST payable under clause A3.50.

At the same time as issuing a *tax invoice* under this clause A3.44, *service provider* must provide to *UserCo*, in *electronic form*, the metering information used to calculate the *charges* shown on the *tax invoice* in sufficient detail to enable *UserCo* to understand how *service provider* calculated the *charges*.

A3.45 User invoices

- (a) At the same time as *service provider* issues to *UserCo* a *tax invoice* for the *accounting period* under clause A3.44, *service provider* must provide *UserCo* with all information necessary for *UserCo* to determine any amounts payable by *service provider* to *UserCo*.
- (b) *UserCo* must, within 5 *business days* after receiving the information under clause A3.45(a), issue to *service provider* a *tax invoice* for the *accounting period* showing:
 - (i) all amounts payable by *service provider* to *UserCo* under this contract, which amounts may be calculated using the information

⁶⁸⁷ Clause A3.43 amended by WAGG No 180, 22 October 2008

- provided to *UserCo* by *service provider* under clause A3.45(a);⁶⁸⁸ and
- (ii) all outstanding amounts as at the end of the *accounting period* and interest payable on those amounts; and
 - (iii) GST payable under clause A3.50.
- (c) If *UserCo* disputes the information provided by *service provider* under clause A3.45(a), then:
- (i) *UserCo* may issue a *tax invoice* under clause A3.45(b) for an amount *UserCo* (acting as a *reasonable and prudent person*) estimates to be the correct amount payable; and
 - (ii) *UserCo* must before the *due date* of the *tax invoice* under clause A3.45(b), give notice to *service provider* that it disputes the information provided under clause A3.45(a) and provide in that notice full details of the dispute.
- (d) Clause A3.47 applies in respect of a *tax invoice* issued under clause A3.45(b), for the purposes of which the “**undisputed portion**” is taken to be an amount calculated in accordance with the information provided by *service provider* under clause A3.45(a).

A3.46 Payment of invoices

- (a) Each *party* which receives a *tax invoice* under clause A3.44 or A3.45, must on or before the *due date* pay to the *party* issuing the *tax invoice* all amounts shown on the *tax invoice* which are payable under the contract.
- (b) If a *party* fails to comply with clause A3.46(a) then, without prejudice to the other *party's* other rights, the *party* must pay interest on any unpaid amount, such interest to be calculated daily at the *prescribed rate* from the *due date* until payment.

A3.47 Disputed invoices

- (a) If a *party* disputes any amount set out in a *tax invoice* issued under clause A3.44 or A3.45, then that *party* must pay the *undisputed portion* (if any) and must, prior to the *due date* of the *tax invoice*, give notice to the other *party* that it disputes the amount and provide in that notice full details of the dispute.
- (b) Any amount withheld by a *party* under clause A3.47(a) but subsequently found to have been payable is, without prejudice to the relevant other *party's* other rights, to attract interest calculated daily at the *prescribed rate* from the *due date* of the *tax invoice* until payment.
- (c) Any amount paid by a *party* under clause A3.47(a) but subsequently found not to have been payable is, without prejudice to that *party's* other rights, to attract interest calculated daily at the *discounted rate* from the date the *party* paid the amount to the date the relevant other *party* repays the amount.

⁶⁸⁸ Clause A3.45 amended by WAGG No 180, 22 October 2008

A3.48 Under and over payments

- (a) If a *party* detects a *payment error* by a *party* of any amount within 18 calendar months after the *payment error*:
 - (i) the *party* must give notice to the other *party* of the *payment error*, and
 - (ii) an adjusting payment must be made by the appropriate *party* within 10 *business days* of the notice.
- (b) Subject to clause A3.48(c), the adjusting payment must, without prejudice to the *party's* other rights, include interest calculated daily at the *discounted rate* from the date of the *payment error* until the date of the adjusting payment.
- (c) An adjusting payment by a *party* will not attract interest under clause A3.48(b) if the underpayment was the result of an error by the other *party*.

A3.49 Interest on overdue payments

If a *party* defaults in due and punctual payment of a *tax invoice*:

- (a) clauses A3.85 to A3.91 apply; and
- (b) the overdue payments attract interest payable at the *prescribed rate* until the *default* is remedied.

A3.50 GST

- (a) Unless expressly included, the consideration for any supply under or in connection with this contract (including any *tariff* derived from a *price list*) is *GST* exclusive.
- (b) To the extent that any supply made under or in connection with this contract is a taxable supply, the consideration for that supply is increased by an amount determined by the supplier, not exceeding the amount of the consideration (or its market value) multiplied by the rate at which *GST* is imposed in respect of the supply.
- (c) Without limiting the obligation to provide a *tax invoice* under clauses A3.44 and A3.45, the supplier must issue a *tax invoice* to the *recipient* of a supply to which clause A3.50(b) applies before the payment of the *GST* inclusive consideration determined under that clause.
- (d) If a *party* is entitled under this contract to be reimbursed or indemnified by another *party* for a cost or expense incurred in connection with this contract, the reimbursement or indemnity payment must not include any *GST* component of the cost or expense for which an input tax credit may be claimed by the *party* entitled to be reimbursed or indemnified, or by its representative member.
- (e) Definitions in the *GST Act* apply also in this clause A3.50 unless the context indicates otherwise.

Security

A3.51 If, at any time, *service provider* determines that *UserCo's*⁶⁸⁹ technical or financial resources are such that a *reasonable and prudent person* would consider there to be a material risk that *UserCo* will be unable to meet its obligations under this contract, then *service provider* may, subject to clause A3.51(b)(iii), do either or both of the following:

- (a) require *UserCo*, at *UserCo's* election, to:⁶⁹⁰
 - (i) pay in advance the *charges* for up to 2 months' *services*; or
 - (ii) provide a bank guarantee in terms acceptable to *service provider* (acting reasonably), guaranteeing the *charges* for 2 months' *services*; or
 - (iii) procure from *UserCo's* parent company a guarantee substantially in the form set out in Schedule 11;

and

- (b) if clause A3.43 applies and any amount of the *contribution* remains unpaid or unprovided, require *UserCo* (in addition to *UserCo's* obligations under clause A3.51(a)), at *UserCo's* election, to:⁶⁹¹
 - (i) pay to *service provider* in full an amount equal to:
 - A. if the *contribution* is a *financial provision* — the net present value of the unpaid amounts of the *financial provision*; or
 - B. if the *contribution* is a *provision in kind* — the net present value of the likely cost to the *service provider* of completing the *provision in kind* (which must not exceed the amount that would be spent by a prudent *service provider* *efficiently minimising costs* of completing the *provision in kind*);each in this clause referred to as the “**unpaid portion**”; or
- (ii) provide a bank guarantee in terms acceptable to *service provider* (acting reasonably), guaranteeing the *unpaid portion*; or

⁶⁸⁹ If there is to be an *indemnifier*, replace “*UserCo's*” with “either or both of *UserCo's* or *indemnifier's*”.

⁶⁹⁰ If there is to be an *indemnifier*, replace “require *UserCo*, at *UserCo's* election, to” with “require *UserCo* to nominate which of *UserCo* or *Indemnifier* is to provide the following security (“**nominated person**”), and then require the *nominated person*, at *UserCo's* election, to:”.

⁶⁹¹ If there is to be an *indemnifier*, replace “require *UserCo* (in addition to *UserCo's* obligations under clause A3.51(a)) at *UserCo's* election, to:” with “require *UserCo* (in addition to *UserCo's* obligations under clause A3.51(a)), to nominate which of *UserCo* or *indemnifier* is to provide the following security (“**nominated person**”), and then require the *nominated person*, at *UserCo's* election, to:”.

- (iii) procure from *UserCo's*⁶⁹² parent company a guarantee substantially in the form set out in Schedule 11 guaranteeing the *unpaid portion*.⁶⁹³

A3.52 If *service provider* requires *UserCo* to provide security under clause A3.51, then *UserCo* may propose alternative arrangements (for example, more frequent payment) to manage *service provider's* financial risk under this contract, and if so, *service provider* and *UserCo* must negotiate as *reasonable and prudent persons*, with a view to agreeing alternative arrangements which meet the following objectives:

- (a) minimising the extent to which the requirements of clause A3.51 constitute a barrier to *UserCo's* entry to a market; and
- (b) not contravening section 115 of the *Act* and not otherwise hindering *UserCo's* ability to compete in upstream or downstream markets,

but also in the view of a *reasonable and prudent person*:

- (c) reasonably addressing the risk to *service provider* that *UserCo*⁶⁹⁴ may be unable to meet its obligations under this contract; and
- (d) being reasonably practicable for the *service provider* to administer.

A3.53 If the *parties* fail to agree on alternative arrangements under clause A3.52, then:

- (a) *UserCo* must comply with clause A3.51 unless the matter is the subject of a dispute under clause A3.53(b); and
- (b) the matter may be the subject of a dispute under this contract, in which case the dispute resolver may either:
 - (i) determine the terms of an appropriate alternative arrangement in which case *UserCo* must comply with those terms; or
 - (ii) determine that no alternative arrangement would meet the objectives in clause A3.52 in which case *UserCo* must comply with clause A3.51.

Part C – Technical Compliance Provisions

{Note: refer to clause A3.11 for when this Part C applies.}

Good electricity industry practice

A3.54 *Service provider* must comply with *good electricity industry practice* when providing *services* and otherwise when acting, or not acting, in connection with this contract.

A3.55 *UserCo* must comply with *good electricity industry practice* in receiving *services* and otherwise when acting, or not acting, in connection with this contract.

⁶⁹² If there is to be an *indemnifier*, replace "*UserCo's*" with the "*nominated person's*".

⁶⁹³ Clause A3.51(b) amended by WAGG No 180, 22 October 2008

⁶⁹⁴ If there is to be an *indemnifier*, replace "*UserCo*" with "*UserCo* or *indemnifier*, as applicable,".

Cooperation

- A3.56 *UserCo* and *service provider* (each acting as *reasonable and prudent persons*) must cooperate and coordinate with each other where reasonably necessary in relation to:
- (a) the planning, development, inspection, testing and commissioning of *facilities and equipment* for a *connection point* and *network assets* for the *network*; and
 - (b) the development and implementation of maintenance schedules for *facilities and equipment* for a *connection point* and *network assets* for the *network*.

Directions from system operator

- A3.57 Without limiting the generality of clause A3.56 *UserCo* and *service provider* must comply with any directions given by *system operator*.

User must provide information

- A3.58 *Service provider* may as a *reasonable and prudent person*, in respect of a *connection point*, make a reasonable request for *generation* forecast information or *load* forecast information, as applicable.
- A3.59 A request under clause A3.58 must not be made more than once in any 12 month period except in an accident, emergency, potential danger or other extraordinary circumstances.
- A3.60 *UserCo* must comply with *service provider's* reasonable request under clause A3.58.

Technical rules

- A3.61 *Service provider* and *UserCo* must each comply with the *technical rules*.

Actions of third parties causing user to breach technical rules

- A3.62 If the actions of another person (including a customer of *UserCo*) cause *UserCo* to breach the *technical rules*, then *UserCo* is not in breach of clause A3.61 and is not liable for any breach of the *technical rules* unless *UserCo*:
- (a) has been negligent; or
 - (b) has not acted as a *reasonable and prudent person*.
- A3.63 Nothing in clause A3.62 limits the operation of clauses A3.71 or A3.80 in respect of either *UserCo* or *service provider*.

Tariff and charges

- A3.64 [X]⁶⁹⁵

⁶⁹⁵ If this *access contract* is a *technical compliance contract* only, and any *tariff* or *charge* applies, insert clauses A3.40 to A3.43 here.

Invoicing and payment

A3.65 [X]⁶⁹⁶

Security

A3.66 [X]⁶⁹⁷

Part D – Common Provisions

{Note: Refer to clause A3.11 for when this Part D applies.}

Service provider must comply with service standards

A3.67 *Service provider* must provide the *services* to *UserCo* in accordance with the *service standards*.

Representations and warranties

A3.68 **User's representations and warranties**

- (a) *UserCo* represents and warrants to *service provider* that:
- (i) *UserCo* has complied with the *applications and queuing policy* in the *access arrangement* and the requirements in the *Code* in respect of its *access application* under the *access arrangement*; and
 - (ii) *UserCo's* obligations under this contract are valid and binding and are enforceable against *UserCo* in accordance with their terms; and
 - (iii) this contract and any other transaction under it does not contravene *UserCo's*⁶⁹⁸ constituent documents or any *law* or any of *UserCo's* obligations or undertakings by which *UserCo* or any of *UserCo's* assets are bound or cause to be exceeded any limitation on *UserCo's* or *UserCo's* directors' powers; and
 - (iv) neither *UserCo* nor any of its related bodies corporate have immunity from the jurisdiction of a court or from legal process (whether through service of notice, attachment prior to judgment, attachment in aid of execution, execution or otherwise).

⁶⁹⁶ If this *access contract* is a *technical compliance contract* only, and any *tariff* or *charge* applies, insert clauses A3.44 to A3.50 here.

⁶⁹⁷ If this *access contract* is a *technical compliance contract* only, and the *service provider* is permitted by the *access arrangement* to seek security in respect of such a contract, insert clauses A3.51 to A3.53 here.

⁶⁹⁸ Clause A3.68 amended by WAGG No 180, 22 October 2008

(b) The representations and warranties in clause A3.68(a) are to be taken to be made on each day on which:

- (i) this contract is in effect; or
- (ii) any amount payable by *UserCo* to *service provider* under this contract is or may be outstanding.

A3.69 [Indemnifier's representation and warranty]

⁶⁹⁹

A3.70 Service provider's representations and warranties

(a) *Service provider* represents and warrants to *UserCo* that:

- (i) *service provider* complied with the *applications and queuing policy* in the *access arrangement* and the requirements in the *Code* in respect of *UserCo's access application* under the *access arrangement*; and
- (ii) *service provider's* obligations under this contract are valid and binding and are enforceable against *service provider* in accordance with their terms; and
- (iii) this contract and any other transaction under it does not contravene *service provider's* constituent documents or any *law* or any of *service provider's* obligations or undertakings by which *service provider* or any of *service provider's* assets are bound or cause to be exceeded any limitation on *service provider's* or *service provider's* directors' powers; and
- (iv) neither *service provider* nor any of its related bodies corporate have immunity from the jurisdiction of a court or from legal process (whether through service of notice, attachment prior to judgment, attachment in aid of execution, execution or otherwise).

(b) The representations and warranties in clause A3.70(a) are to be taken to be made on each day on which:

- (i) this contract is in effect; or
- (ii) any amount payable by *service provider* to *UserCo* under this contract is or may be outstanding.

⁶⁹⁹ If there is to be an *indemnifier*, add a new clause under this heading: "The *indemnifier* represents and warrants to *service provider* that as at the *commencement date*, there has been no material change in the *indemnifier's* financial position since the date *service provider* received information from the *indemnifier* stating that financial position."

Liability and indemnity

A3.71 Liability for direct damage

Subject to the terms of this contract, a *party* who:

- (a) is negligent; or
- (b) commits a *default* under this contract,

is liable to the other *party* for, and must indemnify the other *party* against, any *direct damage* caused by, consequent upon or arising out of the negligence or *default*.

A3.72 Fraud

A *party* who is fraudulent in respect of its obligations to the other *party* under this contract, is liable to the other *party*⁷⁰⁰ for, and is to indemnify the other *party*⁷⁰¹ against, any damage caused by, consequent upon or arising out of the fraud. In this case, the exclusion of *indirect damage* in clause A3.73(a) does not apply.

A3.73 Exclusion of indirect damage

- (a) Subject to clause A3.73(a)(ii):
 - (i) *UserCo*⁷⁰² is not in any circumstances to be liable to *service provider* for any *indirect damage* suffered by *service provider*, however arising; and
 - (ii) *service provider* is not in any circumstances to be liable to *UserCo*⁷⁰³ for any *indirect damage* suffered by *UserCo*⁷⁰⁴, however arising.
- (b) Where this contract states that “[t]he exclusion of *indirect damage* in clause A3.73(a) does not apply”, or words to a similar effect, in relation to a matter, then:
 - (i) the exclusion of *indirect damage* in clause A3.73(a) does not apply in relation to that matter; and
 - (ii) the parties’ liability in relation to the matter is to be determined by *law*, and to avoid doubt the definition of *indirect damage* in this contract is to be disregarded for the purposes of that determination.

⁷⁰⁰ If the *party* is *service provider*, and if there is to be an *indemnifier*, replace “the other *party*” with “either *UserCo* or *indemnifier*”.

⁷⁰¹ If the *party* is *service provider*, and if there is to be an *indemnifier*, replace “the other *party*” with “both *UserCo* and *indemnifier*”.

⁷⁰² If there is to be an *indemnifier*, replace “*UserCo*” with “either or both of *UserCo* or *indemnifier*”.

⁷⁰³ If there is to be an *indemnifier*, replace “*UserCo*” with “either or both of *UserCo* or *indemnifier*”.

⁷⁰⁴ If there is to be an *indemnifier*, replace “*UserCo*” with “either or both of *UserCo* or *indemnifier*”.

A3.74 Limitation of liability

The maximum liability of:

- (a) *service provider* to *UserCo*⁷⁰⁵ under and in connection with this contract is limited to an amount of \$[x]⁷⁰⁶; or
- (b) *UserCo*⁷⁰⁷ to *service provider* under and in connection with this contract is limited to an amount of \$[x]⁷⁰⁸.

A3.75 Procedure for party seeking to rely on indemnity

If any claim, demand, action or proceeding (collectively “**claim**”) is made or instituted against a *party*⁷⁰⁹ in respect of which that *party*⁷¹⁰ (“**indemnified party**”) may under this contract seek to claim indemnity under this contract against the other *party*⁷¹¹ (“**indemnifying party**”), the following procedure applies:

- (a) *indemnified party* must give notice of the *claim* to the *indemnifying party* as soon as reasonably practicable; and
- (b) *indemnified party* must not admit, compromise, settle or pay any *claim* or take any other steps which may in any way prejudice the defence or challenge of the *claim* without the prior written consent of the *indemnifying party* (which must not be unreasonably withheld) except as may be reasonably required in order to defend any judgment against *indemnified party* (to avoid doubt, Part 1E of the *Civil Liability Act 2002* applies in respect of any ‘apology’ (as defined in section 5AF of that Act) given by the *indemnified party*); and
- (c) *indemnified party* must permit the *indemnifying party* at the *indemnifying party’s* expense to take any reasonable action in the name of *indemnified party* to defend or otherwise settle the *claim* as *indemnifying party* may reasonably require; and

⁷⁰⁵ If there is to be an *indemnifier*, replace “*UserCo*” with “either or both of *UserCo* or *indemnifier*”.

⁷⁰⁶ Insert the maximum amount of *service provider’s* liability to *UserCo* under and in connection with this contract, and insert what this cap applies to (e.g. whether this is per event, in a time period, over the life of the contract, etc). To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁷⁰⁷ If there is to be an *indemnifier*, replace “*UserCo*” with “both *UserCo* and *indemnifier* collectively”.

⁷⁰⁸ Insert the maximum amount of *UserCo’s* liability to *service provider* under and in connection with this contract, and insert what this cap applies to (e.g. whether this is per event, in a time period, over the life of the contract, etc). To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁷⁰⁹ If the party is *UserCo*, and if there is to be an *indemnifier*, replace “the *party*” with “either or both of *UserCo* or *indemnifier*”.

⁷¹⁰ If the party is *UserCo*, and if there is to be an *indemnifier*, replace “the *party*” with “either or both of *UserCo* or *indemnifier*”.

⁷¹¹ If the other party is *UserCo* and if there is to be an *indemnifier*, then replace “the other *party*” with “either or both of *UserCo* or *indemnifier*”.

- (d) *indemnified party* must ensure that *indemnifying party* and its representatives are given reasonable access to any of the documents, records, staff, premises and advisers of the *indemnified party* as may be reasonably required by *indemnifying party* in relation to any action taken or proposed to be taken by *indemnifying party* under clause A3.75(c).

A3.76 Mitigation of losses

A *party*⁷¹² must take such action as is reasonably required to mitigate any loss to it for which indemnity may be claimed under this contract or otherwise.

A3.77 Obligation to pay and right to indemnities survives termination

- (a) A *party's*⁷¹³ obligation to pay an amount to another *party* under this contract is a continuing obligation, separate and independent from the other obligations of the *party*⁷¹⁴ and survives termination of this contract.
- (b) Each indemnity in this contract is a continuing obligation, separate and independent from the other obligations of the *parties*⁷¹⁵ and survives termination of this contract. It is not necessary for a *party*⁷¹⁶ to incur expense or make payment before enforcing a right of indemnity conferred by this contract.

Insurances

A3.78 UserCo's insurances

- (a) Subject to clause A3.78(b), *UserCo* must obtain and *maintain* insurance covering those matters, and for the amounts, referred to in Item 1 of Schedule 8.
- (b) To the extent that *service provider* consents (such consent not to be unreasonably withheld), *UserCo* may self-insure for some or all of the matters and amounts referred to in Item 1 of Schedule 8.
- (c) *UserCo* must, before the *commencement date* and at such other times as *service provider* shall reasonably request in writing (such request not to be made more than once in respect of a 12 month period unless extraordinary circumstances apply), provide *service provider* with certificates of currency for the insurances required under clause A3.78(a) or reasonable details of *UserCo's* arrangements under clause A3.78(b), as the case may be.

⁷¹² If there is to be an *indemnifier*, replace "a *party*" with "a *party* and *indemnifier*".

⁷¹³ If there is to be an *indemnifier*, replace "a *party*" with "a *party* and *indemnifier*".

⁷¹⁴ If the *party* is *UserCo* and if there is to be an *indemnifier*, replace "the *party*" with "either or both of *UserCo* or *indemnifier*".

⁷¹⁵ If there is to be an *indemnifier*, replace "the *parties*" with "both the *parties* and *indemnifier*".

⁷¹⁶ If there is to be an *indemnifier*, replace "*party*" with "either or both of *party* or *indemnifier*".

A3.79 Service provider's insurances⁷¹⁷

- (a) Subject to clause A3.79(b), *service provider* must obtain and *maintain* insurance covering those matters and for the amounts referred to in Item 2 of Schedule 8.
- (b) To the extent that *UserCo* consents (such consent not to be unreasonably withheld), *service provider* may self-insure for some or all of the matters and amounts referred to in Item 2 of Schedule 8.
- (c) *Service provider* must, before the *commencement date* and at such other times as *UserCo* reasonably requests in writing (such request not to be made more than once in respect of a 12 month period unless extraordinary circumstances apply), provide *UserCo* with certificates of currency for the insurances required under clause A3.79(a) or reasonable details of *service providers* arrangements under clause A3.79(b), as the case may be.

Force majeure

- A3.80 If a person (“**affected person**”) is unable wholly or in part to perform any obligation (“**affected obligation**”) under this contract (other than an obligation to pay money) because of the occurrence of a *force majeure event*, then, subject to these clauses A3.80 to A3.84, the *affected person* is released from liability for failing to perform the *affected obligation* to the extent that and for so long as the *affected person's* ability to perform the *affected obligation* is affected by the *force majeure event*.
- A3.81 Without limiting clause A3.80, *service provider's* obligation in respect of a *connection point* to provide the *services* is suspended during any period that the provision of the *services* in respect of that *connection point* is curtailed under clause A3.27, to the extent of the *curtailment*.
- A3.82 Subject to clauses A3.83 and A3.84, if a *force majeure event* occurs and the *affected person* is unable wholly or in part to perform any obligation under this contract, then the *affected person* must:
- (a) notify the other *party* if the *force majeure event* continues for a period of two days or longer; and
 - (b) use reasonable endeavours (including incurring any reasonable expenditure of funds and rescheduling personnel and resources) to:
 - (i) mitigate the consequences; and
 - (ii) minimise any resulting delay in the performance of the *affected obligation*.
- A3.83 If an *affected person* fails to comply with clause A3.82(b)(ii), then the only consequence of that failure is that the period of suspension of the *affected obligation*

⁷¹⁷ This clause assumes that *service provider's* self-insurance choices are dealt with on a *user-by- user* basis. A *service provider* may propose to the Authority an alternative approach for inclusion in the *access arrangement*, for example one in which the matters on which the *service provider* may self-insure are prescribed in the *access arrangement*, and the *Authority* may approve such an alternative approach.

is reduced by the period of any delay in the performance of the *affected obligation* attributable to that failure.

A3.84 The settlement of a labour dispute which constitutes a *force majeure event* is a matter which is within the absolute discretion of the *affected person*.

Default

A3.85 **Default**

A *party* is in “**default**” if:

- (a) that *party* defaults in the due and punctual payment, at the time and in the manner required for payment by this contract, of any amount payable under this contract; or
- (b) that *party* defaults in the due and punctual performance or observance of any of its obligations contained or implied by operation of *law* in this contract; or
- (c) an *insolvency event* occurs in respect of that *party*; or
- (d) that *party* materially breaches any representation or warranty given to the other *party* under this contract.

A3.86 **Default by UserCo**

In the event of *UserCo's default*, then *service provider* may:

- (a) notify *UserCo* of *UserCo's default* and require *UserCo* to remedy *UserCo's default*; or
- (b) if *UserCo's default* is a *default* in the payment of any amount and has not been remedied by the end of the third *business day* after the notice was given, *disconnect*, or curtail the provision of *services* in respect of, all or any of *UserCo's connection points* from the *network* whilst *UserCo's default* is continuing; or
- (c) if *UserCo's default* is any other type of *default* and at the end of the fifth *business day* after the notice was given:
 - (i) *UserCo's default* has not been remedied; or
 - (ii) *UserCo* has not to the reasonable satisfaction of *service provider* begun remedying *UserCo's default* or has begun remedying but is not, in the reasonable opinion of the *service provider*, diligently proceeding to remedy *UserCo's default*,

disconnect, or curtail the provision of *services* in respect of, all or any of *UserCo's connection points* from the *network* whilst *UserCo's default* is continuing; and
- (d) if *UserCo's default* has not been remedied at the end of the 20th *business day* after the notice was given, terminate this contract.

A3.87 *UserCo's default* under clause A3.86 does not prejudice the rights or remedies accrued to *service provider* at the date of *UserCo's default*.

A3.88 Default by service provider

In the event of *service provider's default*, *UserCo* may:

- (a) notify *service provider* of *service provider's default* and require *service provider* to remedy the *default*; and
- (b) if *service provider's default* has not been remedied at the end of the 20th *business day* after the notice was given:
 - (i) terminate this contract; or
 - (ii) withhold payment of any *charges* payable by *UserCo* from the date of *default* under this contract for so long as the *default* continues unremedied (and no interest is payable by *UserCo* on any amounts so withheld provided they are paid within 10 *business days* after the *default* is remedied).

A3.89 *Service provider's default* under clause A3.88 does not prejudice the rights or remedies accrued to *UserCo* at the date of *service provider's default*.

Termination

A3.90 Termination

- (a) Subject to clause A3.90(b), this contract terminates on the *termination date*.
- (b) This contract may be terminated before the *termination date* by:
 - (i) written agreement between *service provider* and *UserCo*; or
 - (ii) notice by either *party* at any time at which this contract does not include at least one *connection point*; or
 - (iii) notice by either *party* where there is a *default* by the other *party* under this contract, subject to clauses A3.86 or A3.88 as the case may be; or
 - (iv) notice by either *party* to an *affected person* if a *force majeure event* occurs and the *affected person* is unable wholly or in part to perform any obligation under this contract and the *force majeure event* continues for a period of greater than 180 days in aggregate in any 12 month period.
- (c) On termination of this contract *service provider* may *disconnect* any one or more of *UserCo's connection points*.
- (d) On termination of this contract, unless alternative provisions are agreed:
 - (i) *service provider* may dismantle, decommission and remove *service provider's works* and any *metering equipment* installed on *UserCo's* premises; and

- (ii) in accordance with *service provider's* instructions, *UserCo* must dismantle and decommission or remove any of *UserCo's* works at or connected to any *connection point* that is located on *service provider's premises* and is not otherwise required under another contract.

A3.91 Termination of this contract under clause A3.90(b) does not prejudice the rights or remedies accrued to either *party* at the date of termination.

Access to premises

A3.92 Each *party* ("**host party**") must allow, or use its reasonable endeavours to procure for, the other *party* ("**guest party**") all reasonable rights of entry:

- (a) for the purposes of constructing, installing, operating, *maintaining* and verifying the accuracy of any *metering equipment*, other equipment or thing; and
- (b) to inspect for safety or other *reasons* the construction, installation, operation, maintenance and repair of any *metering equipment*, other equipment or thing; and
- (c) for any other reasonable purpose connected with or arising out of this contract.

A3.93 Any entry under clause A3.92 is made in all respects at the expense and risk of the *guest party*, who must, subject to clauses A3.73 and A3.74, make good any damage occasioned by or resulting from the entry, other than to the extent the damage is caused by:

- (a) fair wear and tear; or
- (b) the negligence or *default* of *host party* or its *workers* or *visitors*;
- (c) *a force majeure event*.

A3.94 A *guest party* must:

- (a) before exercising a right of entry under clause A3.92, give reasonable notice to the *host party* specifying the purpose, proposed time and estimated duration of entry, except where it is not practicable to do so due to any accident, emergency, potential danger or other extraordinary circumstance; and
- (b) while exercising a right of entry under clause A3.92:
 - (i) act as a *reasonable and prudent person*; and
 - (ii) without limiting clause A3.94(b)(i), take steps that are reasonable in the circumstances to ensure that during the entry its *workers* and *visitors* cause as little inconvenience to the *host party* as possible, except to the extent that it is not practicable to do so due to any accident, emergency, potential danger or other extraordinary circumstance, and at all times comply with:

- A. all reasonable health and safety standards, induction and supervision requirements and other requirements of the *host party*; and
- B. all reasonable and lawful directions by or on behalf of the *host party*.

A3.95 To the extent that any equipment or thing is located on the premises of a third person, the *parties* must use their reasonable endeavours to secure for either or both of the *parties* a reasonable right of entry to the third person's premises.

Disputes

A3.96 If a dispute arises between the *parties*, either *party* may give to the other *party* written notice setting out the material particulars of the dispute and requiring duly authorised representatives of each *party* to meet at a place, agreed between the *parties*, within 10 *business days* of the date of receipt of such notice by the relevant *party* ("**receipt date**"), to attempt in good faith by way of discussions and using their best endeavours to resolve the dispute ("**representatives meeting**") and the *parties* must do so.

A3.97 If the dispute is not resolved (as evidenced by the terms of a written settlement signed by each *party's* duly authorised representative) within 20 *business days* after the *receipt date* then the senior executive officer of each *party* must meet at a place agreed between the *parties* within 30 *business days* after the *receipt date* and must attempt in good faith by way of discussions and using their best endeavours to resolve the dispute within 35 *business days* after the *receipt date* ("**CEO meeting**").

A3.98 A *representatives meeting* in clause A3.96 or *CEO meeting* in clause A3.97 may be conducted in person, by telephone, video-conference or similar method of real time communication.

A3.99 If, after complying with the process set out in clauses A3.96 and A3.97 a dispute is not resolved, then either *party* may commence an action to resolve the dispute through litigation and other court processes.

{Note: The *parties* may, if they agree, endeavour to resolve a dispute through mediation, conciliation, arbitration or other alternative resolution methods rather than commencing an action to resolve the dispute through litigation.}

A3.100 A *party* must continue to perform its obligations under this contract despite the existence of a dispute, unless otherwise agreed.

Set off

A3.101 A *party* ("**first party**") may set off any amount due for payment by it to the other *party* under this contract against any amount which is due for payment by the other *party* to the *first party* under this contract.

A3.102 Except as permitted in clause A3.101, no set off is permitted by either *party* in connection with this contract, whether under this contract or otherwise.

Transfer by user

A3.103 Subject to clause A3.104, *UserCo* may make a *bare transfer* of its *access rights* without *service provider's* prior consent.

A3.104 If *UserCo* makes a *bare transfer*, *UserCo* must notify *service provider* of:

- (a) the identity of the transferee; and
- (b) the nature of the transferred *access rights*,

before the transferee may commence using the transferred *access rights*.

A3.105 For a *transfer* other than a *bare transfer*, *UserCo* may *transfer* its *access rights* (subject to clause A3.106) and subject to the *service provider's* prior written consent and such conditions as the *service provider* may impose.

A3.106 For a *transfer* other than a *bare transfer*, *service provider* may:

- (a) withhold its consent in clause A3.105 only on reasonable commercial or technical grounds; and
- (b) impose conditions in respect of the *transfer*, but only to the extent that they are reasonable on commercial and technical grounds.

Corporate restructuring of service provider⁷¹⁸

A3.107 If *service provider* is restructured:

- (a) in accordance with government policy by *law*; or
- (b) through other means, including the:
 - (i) use of subsidiary or *associated* companies; or
 - (ii) *transfer* of assets, rights and liabilities,

then the rights and obligations of *service provider* under this contract are assigned to the appropriate legal entity pursuant to the restructure.

A3.108 A restructure, *transfer* or assignment under clause A3.107 does not require *UserCo's* approval or consent.

⁷¹⁸ This clause to be omitted from *standard access contract* unless *service provider* is a wholly state-owned corporation.

Confidentiality

A3.109 Confidential information

This contract and information exchanged between the *parties* under this contract or during the negotiations preceding this contract is confidential to them if:

- (a) the information disclosed contains a notification by the disclosing *party* that the information is confidential; or
- (b) the circumstances in which the information was disclosed or the nature of the information disclosed may reasonably be considered as being confidential; or
- (c) the information constitutes trade secrets; or
- (d) the information has a commercial value to a *party* which would be destroyed or diminished by the publication of the information; or
- (e) the information relates to the business, professional, commercial or financial affairs of a *party* and the value to the *party* would be destroyed or diminished by the publication of the information.

A3.110 Clause A3.109 does not apply to information which, without breach of this contract or other breach of confidence:

- (a) is or becomes generally and publicly available⁷¹⁹; or
- (b) is lawfully obtained by a *party* from a person other than a *party* or a *related body corporate* of a *party* where such person is entitled to disclose the *confidential information*; or
- (c) is, at the date of this contract, lawfully in the *possession* of the *recipient* of the *confidential information* through sources other than the *party* which supplied the information.

A3.111 Prohibited disclosure

Subject to clause A3.112, an information *recipient* must not disclose or allow to be disclosed any *confidential information* to a *third party recipient*.

A3.112 Permitted disclosure

- (a) An information *recipient* may disclose or allow to be disclosed any *confidential information* to a *third party recipient* in the following circumstances:
 - (i) with written consent of the *information provider*; or
 - (ii) to employees, a *related body corporate* or legal advisers, auditors or other consultants of the *party* requiring information for the

⁷¹⁹ Appendix 3 clause A3.110 amended by WAGG No 207, 8 November 2005

purposes of this contract or for the purposes of providing professional advice in relation to this contract; or

- (iii) to a bona fide proposed assignee of a *party* to this contract or registered shareholder of 20 percent or more of the voting shares in a *party*; or
 - (iv) if required by *law* or by an authority which has jurisdiction over a *party* or any of its related bodies corporate or by the rules of a stock exchange which has jurisdiction over a *party* or any of its related bodies corporate; or
 - (v) if required for the purposes of prosecuting or defending a dispute or if otherwise required in connection with legal proceedings related to this contract.
- (b) Nothing in clause A3.112(a) limits *service provider's* obligations to comply with Chapter 13 of the *Code*.

A3.113 **Third party disclosure**

An information *recipient* disclosing information under clause A3.112(a) must:

- (a) use all reasonable endeavours to ensure that a *third party recipient* does not disclose the *confidential information* except in the circumstances permitted in clause A3.112(a); and
- (b) notify the *third party recipient* that it has a duty of confidence to the *information provider* in respect of the *confidential information*; and
- (c) except to the extent that the *third party recipient* is under an existing enforceable legal obligation to maintain the confidence of the *confidential information* as contemplated in clause A3.113(b), procure a written confidentiality undertaking from the *third party recipient* consistent with clauses A3.109 to A3.118.

A3.114 **No unauthorised copying**

A *party* must not copy any document containing the other *party's confidential information* except as necessary to perform this contract.

A3.115 **Secure storage**

A *party* must ensure that proper and secure storage is provided for the *confidential information* while in *possession* of a *party*, provided that if a *party* is a corporation it may retain any such documents or parts of documents that form part of board papers (or other formal approval processes) of such corporation and which are required to be retained by that corporation in accordance with usual corporate governance requirements.

A3.116 **Return of materials**

A *party* must return all documents containing the other *party's confidential information*, including all copies, to the other *party* on termination or expiration of this contract, or upon request by the other *party*, destroy all such documents.

A3.117 Remedies

Each *party* acknowledges and agrees that any breach or threatened breach of clauses A3.109 to A3.118 may cause a *party* immediate and irreparable harm for which damages alone may not be an adequate remedy. Consequently, each *party* has the right, in addition to any other remedies available at *law* or equity, to seek injunctive relief or compel specific performances of these clauses A3.109 to A3.118 in respect of any such breach or threatened breach.

A3.118 Survival of obligations

- (a) Clauses A3.109 to A3.118 survive the termination of this contract and remain enforceable for a period of 7 years from the date of such termination.
- (b) Any person who ceases to be a *party* to this contract continues to be bound by these clauses A3.109 to A3.118.

Ring fencing

A3.119 If *service provider* is an *integrated provider*, then a court or tribunal in considering whether:

- (a) representations made by *workers* of the *other business* can be attributed to the *network business*, or vice versa; or
- (b) a notice or other information given to a worker of the *other business* has been communicated, or should be deemed to have been communicated, to the *network business*, or vice versa; or
- (c) a contract entered into by the *other business* expresses or implies an intention to vary this contract, or vice versa,

must have regard to:

- (d) the fact that *service provider* comprises a *network business* and an *other business* and the distribution of personnel and responsibilities between those businesses; and
- (e) *service provider's* obligations under Chapter 13 of the *Code* (and, if *service provider* is Electricity Networks Corporation, any regulations made under section 62 of the *Electricity Corporations Act 2005*⁷²⁰) and anything done or not done by the *service provider* in connection with those obligations.

Notices

A3.120 Requirements for notices

Except as provided in clause A3.121, a communication must be:

- (a) in writing (which includes any *electronic form* capable of being reduced to paper writing by being printed); and

⁷²⁰ Appendix 3 clause A3.119(e) amended by WAGG No 59, 31 March 2006

- (b) delivered or sent to the address of the addressee as specified in Schedule 9 by one or more of the following means:
 - (i) by hand delivery; or
 - (ii) by ordinary letter post (airmail if posted to or from a place outside Australia); or
 - (iii) by way of a courier service for hand delivery; or
 - (iv) by facsimile to the facsimile number of the addressee, or
 - (v) by email, as specified in the Electronic Communications Protocol in Schedule 10.

A3.121 Operational and urgent notices

Where this contract expressly provides, and where the *parties* agree in writing:

- (a) notices of a day to day operational nature; or
- (b) notices given in an operational emergency,

may be given orally and confirmed in writing within 5 *business days*.

A3.122 Notice takes effect

Subject to clause A3.123, a communication takes effect from the later of:

- (a) the time it is received; and
- (b) any later time specified in the communication.

A3.123 Deemed receipt

For the purposes of this contract:

- (a) a communication delivered by hand to the address of a *party* (including where a reputable courier service is used for that purpose) is deemed to be received if it is handed (with or without acknowledgment of delivery) to any person at the address who, in the reasonable judgment of the person making the delivery (upon making appropriate enquiries):
 - (i) appears to be; and
 - (ii) represents himself or herself as,

a representative of the *party* to whom the communication is addressed.
- (b) a communication which is posted is deemed to be received by the *party* to whom the communication is addressed:
 - (i) where the communication is sent from outside the country of the address to which it is sent – on the 10th *business day* after the day of posting; and

- (ii) otherwise – on the third *business day* after the day of posting.
- (c) a communication sent by facsimile transmission which is transmitted:
 - (i) prior to 3 p.m. on a *business day* is deemed to have been received by the *party* on that *business day* at the *recipient's* location; and
 - (ii) after 3 p.m. on a *business day*, or on a day which is not a *business day*, is deemed to have been received by the *party* on the first *business day* at the *recipient's* location following the date of transmission,

provided that the sender of the communication is able to produce a transmission log generated by the sender's facsimile machine (or other facsimile transmission device), showing successful uninterrupted facsimile transmission of all pages of the relevant communication to the facsimile number of the addressee.

- (d) a communication sent electronically is deemed to be received by the *party* in accordance with Schedule 10.

A3.124 **Change of address**

A *party* may at any time, by notice given to the other *party* to this contract, designate a different address or facsimile number for the purpose of these clauses A3.120 to A3.124.

Miscellaneous

A3.125 **Compliance**

Each *party* to this contract must comply with all applicable *laws*.

A3.126 **Variation**

- (a) Subject clause A3.126(b), a purported agreement between *service provider* and *UserCo* to revoke, substitute or amend any provision of this contract has no effect unless it is in writing.
- (b) Clause A3.126(a) does not prevent *UserCo* and *service provider* from agreeing by non-written means under clause A3.121 to revoke, substitute or amend any provision of this contract in an accident, emergency, potential danger or other unavoidable cause or extraordinary circumstance (each in this clause an "**emergency**"), provided that the non-written revocation, substitution or amendment applies only while the effects of the *emergency* subsist.

A3.127 **No third party benefit**

This contract does not confer any right or benefit on a person other than *UserCo* and *service provider*, despite the person being named or identified, or belonging to a class of persons named or identified, in this contract.

A3.128 Stamp duty

UserCo is liable for and must pay all stamp duties that are assessed on this contract.

A3.129 Costs

Each *party* must pay its own costs, *charges*, expenses, disbursements or fees in relation to:

- (a) the negotiation, preparation, execution, performance, amendment or registration of, or any notice given or made; and
- (b) the performance of any action by that *party* in compliance with any liability arising,

under this contract, or any agreement or document executed or effected under this contract, unless this contract provides otherwise.

A3.130 Waiver

A provision of this contract may only be waived by a *party* giving written notice signed by a duly authorised representative to the other *party*.

A3.131 Entire Agreement

This contract constitutes the entire agreement between the *parties* as to its subject matter and, to the extent permitted by *law*, supersedes all previous agreements, arrangements, representations or understandings.

A3.132 Severance

If the whole or any part of this contract is void, unenforceable or illegal in a jurisdiction, it is severed for that jurisdiction. The remainder of this contract has full force and effect and the validity or enforceability of the provision in any other jurisdiction is not affected. This clause A3.132 has no effect if the severance alters the basic nature of this contract or is contrary to public policy.

A3.133 Counterpart execution

- (a) This contract may be executed in counterpart.
- (b) Upon each *party* having executed and forwarded to the other *party* a fully signed counterpart of this contract, it is deemed to be properly executed by all *parties*.

A3.134 Further assurance

Each *party* agrees, at its own expense, on the request of another *party*, to do everything reasonably necessary to give effect to this contract and the transactions contemplated by it, including, but not limited to, the execution of documents.

A3.135 Authorised officers

- (a) Notice, approval, consent or other communication given under this contract may be given by an *authorised officer* of a *party* specified in Schedule 9 to an *authorised officer* of another *party* specified in Schedule 9.
- (b) A *party* may at any time, by notice given to the other *party*, add or replace an *authorised officer* for the purposes of clause A3.135(a).

A3.136 Merger

The warranties, undertakings and indemnities in this contract do not merge on termination of this contract.

A3.137 Remedies

The rights, powers and remedies provided in this contract are cumulative with and not exclusive of the rights, powers or remedies provided by *law* independently of this contract.

A3.138 Governing law

- (a) This contract and the transactions contemplated by this contract are governed by the law in force in Western Australia.
- (b) Without limiting clause A3.138(a), each *party* irrevocably and unconditionally submits to the non-exclusive jurisdiction of the Courts of Western Australia and the Courts of appeal from them for the purpose of determining any dispute concerning this contract or the transactions contemplated by this contract.

[Execution clauses to be inserted.]

Schedule 1 to Appendix 3 – Access Contract Information

1.	<i>Commencement Date</i>	
2.	<i>Termination Date</i>	

Schedule 2 to Appendix 3 – Services

	Type of service	Specified	Service standard
1.	<i>Connection service</i>		
2.	<i>Entry or Exit service</i>		
3.	<i>Network use of system service</i>		
4.	<i>Common service</i>		

Schedule 3 to Appendix 3 – Details of Connection Points and Metering Points

<i>Connection point</i>	<i>Capacity contract</i> (Tick if applicable)	<i>Technical compliance contract</i> (Tick if applicable)	<i>Type of connection point</i> (i.e. entry point or exit point)	<i>Start Date</i>	<i>End Date</i>	<i>CMD</i> (KW / KVA) (if applicable)	<i>DSOC</i> (KW / KVA) (if applicable)	<i>Designated controller</i> ⁷²¹ (if applicable)

Schedule 4 to Appendix 3 - Tariffs

[X]⁷²²

Schedule 5 to Appendix 3 - Contribution (Provision in Kind Contract or Payment Contract) ⁷²³

[X]⁷²⁴

Schedule 6 to Appendix 3 – Service provider’s works

[Details to be included in addition to other matters:

- (a) description of *service provider’s works* including reference to specifications; and
- (b) timetable for construction of *service provider’s works*]. ⁷²⁵

Schedule 7 to Appendix 3 – UserCo’s works

[Details to be included in addition to other matters:

- (a) description of *UserCo’s works* to be carried out by *UserCo*; and
- (b) terms of construction of *UserCo’s works*; and
- (c) timetable for construction of *UserCo’s works*; and
- (d) terms of *transfer* of *UserCo’s works* to *service provider* (if any); and
- (e) testing and commissioning; and

⁷²¹ To be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁷²² To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 4. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁷²³ Heading amended by WAGG No 180, 22 October 2008

⁷²⁴ Provisions to be inserted as agreed between the *parties* or determined in an arbitrated award in accordance with the *capital contributions policy* in the *service provider’s access arrangement*.

⁷²⁵ Provisions to be inserted as agreed between the *parties* or determined in an arbitrated award in accordance with the *service provider’s access arrangement*.

- (f) protocols for maintenance co-ordination.] ⁷²⁶

Schedule 8 to Appendix 3 – Insurances and Limitation of Liability

1. UserCo insurances

[To be completed. For example the required insurances may include:

- (a) public liability – up to \$x million; and
- (b) workers' compensation – up to \$y million; and
- (c) other insurances as appropriate.] ⁷²⁷

2. Service provider insurances

[To be completed. For example the required insurances may include:

- (a) public liability – up to \$x million; and
- (b) workers' compensation – up to \$y million; and
- (c) other insurances as appropriate.] ⁷²⁸

Schedule 9 to Appendix 3 – Notices

1

	Subject	Information
	Address for service of notices/ place of business	
	<i>Authorised officers</i>	
	Email address	
	Facsimile number	

2 Service provider

	Subject	Information
	Address for service of notices/ place of business	
	<i>Authorised officers</i>	
	Email address	
	Facsimile number	

⁷²⁶ Provisions to be inserted as agreed between the *parties* or determined in an arbitrated award in accordance with the *service provider's access arrangement*.

⁷²⁷ Provisions to be inserted as agreed between the *parties* or determined in an arbitrated award in accordance with the *service provider's access arrangement*.

⁷²⁸ Provisions to be inserted as agreed between the *parties* or determined in an arbitrated award in accordance with the *service provider's access arrangement*.

Schedule 10 to Appendix 3 - Electronic Communications Protocol

1. Interpretation

In this schedule:

“**addressee**” means the person to whose *email* address an *email* is sent.

“**automated response message**” means an *email* (“reply email”) sent automatically upon receipt of an *email* (“original email”), where the reply *email* is sent from an *addressee’s information system* to the *originator* of the original *email*, acknowledging that the original *email* has been received by the *addressee’s information system* and containing:

- (a) the name of the *originator* of the original *email*; and
- (b) at least the time, date and subject title of the original *email*; and

{Note: The easiest means to record this information may be to include the whole of the original *email*, preferably excluding attachments, within the reply *email*.}

- (c) the name of the *addressee* of the original *email*; and
- (d) the date and time the original *email* was received by the *addressee’s information system* (which in the absence of evidence to the contrary is taken to be the creation date of the reply *email*).

“**data**” includes the whole or part of a computer program within the meaning of the *Copyright Act 1968* of the Commonwealth.

“**email**” means a communication of *information* by means of guided or unguided electromagnetic energy, or both, by way of packet *transfer* between and within computer networks using the TCP/IP protocol.

“**email address**” means the address nominated in the third item of Tables 1 and 2⁷²⁹ of Schedule 9, being an address which is a combination of a personal identifier and a machine/network identifier, which are together capable of being resolved by computer networks transmitting *email* using the TCP/IP protocol, so that *email* is transmitted to the *person* providing that email address.

“**information**” means information in the form of data, text, images or sound.

“**information system**” means a system for generating, sending, receiving, storing or otherwise processing *emails*.

“**originator**” means the *person* who sends an *email* to an *addressee*.

“**place of business**” means a place of business nominated under the first item of Tables 1 and 2⁷³⁰ of Schedule 9 and in relation to a government, a government

⁷²⁹ Clause 1, Schedule 10 to Appendix 3 amended by WAGG No 207, 8 November 2005

⁷³⁰ Clause 1, Schedule 10 to Appendix 3 amended by WAGG No 207, 8 November 2005

authority or a non-profit body, includes a place where any operations or activities are carried out by that government, authority or body.

“**purported originator**” means the *person* on the face of the email who appears to be, or purports to be the *originator*, including by purported compliance with clause 5.

2. Parties to establish email addresses

Service provider and *UserCo* must:

- (a) from time to time, nominate a *place of business* and establish an *email address* to be used for the *communications* under this contract; and
- (b) use reasonable endeavours to ensure that the *information system*, on which *emails* addressed to the *email address* are received, is operational:
 - (i) a 24 hours-a-day; and
 - (ii) 7 days-a-week,to receive *emails* and send *automated response messages* as required by this contract; and
- (c) as soon as practicable notify the other *party* of its *place of business* and *email address* and of any change in each of them; and
- (d) establish a mechanism to generate an *automated response message* for each *email* (other than an *automated response message*) received at the *email address*.

3. Requirement for automated response message

- (a) An *email* is neither given nor received under this contract until the *originator* receives the *addressee's automated response message* for the *email*.
- (b) It is the *originator's* responsibility for each attempted *email* to verify that it receives an *automated response message*, and if it does not receive an *automated response message* arrange either for:
 - (i) retransmission of the *email*; or
 - (ii) communication of the *information* by an alternative medium (but this clause 2(b) does not limit the *addressee's* responsibilities under clause 2(d)).
- (c) If the *originator* receives an *automated response message* for an *email*, then (unless the *addressee* proves otherwise) for the purposes of this contract the:
 - (i) *originator* has sent; and
 - (ii) *addressee* has received,the *email* at the date and time shown in the *automated response message*.
- (d) It is the *addressee's* responsibility for each *email* for which the *addressee's information system* generates an *automated response message* to:

- (e) read the *email* and the *information* it contains, and if applicable communicate it to the appropriate *worker* within the *addressee's* organisation; and
- (f) if necessary, notify the *originator* of any difficulty in opening, reading, decompressing or otherwise *accessing* (in a form reasonably readable) any *information* contained in the *email*; and
- (g) if it appears to the *addressee* that the *addressee* was not the intended or correct *recipient* of the *information* in the *email*, communicate this fact to the *originator*.

4. Location

Unless otherwise agreed between the *originator* and the *addressee* of an *email*, the email and the *information* it contains is deemed to have been sent from the *originator's place of business* and received at the *addressee's place of business*.

5. Attribution of emails and reliance

Except to the extent that:

- (a) the *purported originator* of an *email* and the *addressee* of the *email* agree otherwise; or
- (b) the *purported originator* of an *email* proves otherwise,

the *addressee* of an *email* in respect of which an *automated response notice* has been given may assume for all purposes under this contract that the:

- (c) *purported originator* of the *email* is the *originator* of the *email*; and
- (d) *email* was sent by, or with the knowledge and express authority of, the *purported originator*.

6. Signatures

For the purposes of this contract, an *email* must identify the *originator*.

7. Information format

An *originator* must use reasonable endeavours, in selecting the data format for *information* contained in an *email*, to adopt a consistent format over time to facilitate any automated processing of the *information* by the *addressee*.

Schedule 11 to Appendix 3 - Guarantee

DEED dated [to be completed]

PARTIES

1. [### ACN ### a company registered in ### of ###] ("**Guarantor**"); and
2. [### ACN ### a company registered in ### of ###] ("**Service provider**").

BACKGROUND

- A The *service provider* may in its discretion provide *services* to [###] ("**UserCo**") under an *access contract* at the request of each of *UserCo* and the *guarantor*.
- B The *guarantor* wishes to execute this *guarantee* to secure payment of all amounts payable under the *access contract* to the *service provider*.

1. GUARANTEE

The *guarantor* unconditionally and irrevocably guarantees as a continuing security to the *service provider* payment by *UserCo* of all moneys and liabilities due and/or payable from or by *UserCo* to the *service provider* under or in connection with the contract dated [###] ("**access contract**") created between *UserCo* and the *service provider* ("**secured moneys**"), including moneys and liabilities incurred or arising:

- (a) (**liability**): at any present or future time, whether actually or contingently;
- (b) (**default**): as a result of any breach of or default under the *access contract*; and/or
- (c) (**account**): by way of principal, interest, cost, charge, expense, disbursement, fee, tax, stamp or other duty, indemnity, damages or monetary judicial order.

2. SECURED MONEYS

2.1 Demand Payment

The *guarantor* must pay to the *service provider*, upon demand by the *service provider* at any present or future time, the amount of the *secured moneys* due from and payable by *UserCo* to the *service provider* at that time under, and in the manner and currency specified in, the *access contract*.

2.2 Costs

The *guarantor* must at any present or future time indemnify the *service provider* upon demand for any cost, *charge*, expense, disbursement, fee, tax or stamp or other duty incurred by the *service provider* at any time in connection with the *access contract*, this *guarantee* or the *secured moneys* relating to:

- (a) (**security agreements**): preparation, negotiation, execution or performance, or any termination, amendment, consent, claim, demand or waiver;
- (b) (**security rights**): any exercise or enforcement of any right or power conferred on the *service provider*;

- (c) (**credit increases**): any extension of further, additional or increased credit or financial accommodation by the *service provider*, or agreement by the *service provider* to increase the amount secured; and/or
- (d) (**payments**): the receipt or payment of any moneys, including moneys paid by the *service provider* by way of reimbursement to any third *party*.

2.3 Set-Off Exclusion

The *guarantor* must make any payment required under this *guarantee* without set-off or other deduction, except for the deduction or withholding of any tax compelled by *law*.

3. INDEMNITY

The *guarantor* must as a separate and additional liability of the *guarantor* as a principal debtor, and not as a surety, indemnify the *service provider* against, and pay to the *service provider* upon demand by the *service provider* an amount equal to, all *secured moneys* that are or may become invalid, unenforceable, illegal or irrecoverable for any reason or under any circumstances as a liability to the *service provider* by the *guarantor* as a surety, despite any other provision of this *guarantee*.

4. GUARANTEE PROTECTION

This *guarantee*, and the liability of the *guarantor* under this *guarantee*, is not affected at any time by:

- (a) (**waiver**): the granting to any person by the *service provider* of any waiver;
- (b) (**agreements**): any agreement, deed or document created with, or action or omission performed, representation made or non-disclosure of any fact or information by, the *service provider* or any person;
- (c) (**secured moneys**): any increase or variation in the amount of the *secured moneys* occurring for any reason;
- (d) (**document amendment**): any amendment to or *transfer*, release or termination of any agreement, deed or document or any right, power or liability of any person under any agreement, whether for or without consideration;
- (e) (**enforcement decisions**): any exercise or enforcement, or any failure or invalidity in, the exercise or enforcement by the *service provider* of any right or power conferred on the *service provider* under any agreement, deed or document or by *law*;
- (f) (**invalidity**): any actual or potential invalidity, unenforceability, illegality or irrecoverability of any agreement, deed or document or consent or any payment made or due to the *service provider* under any agreement for any reason;
- (g) (**incapacity**): any incapacity or absence of power or authorisation of, or other fact relating to, any person in connection with the execution of any agreement, deed or document or otherwise, including any change in the constitution or membership of any person; or
- (h) (**residual**): any other breach, default, waiver or fact which, except for this provision, might legally operate:
 - (i) to release or *discharge* or have any prejudicial effect on; or

- (ii) in any manner to release or discharge the *guarantor* from performance of, or limit or provide a defence to any legal action to enforce,

this *guarantee*, or any liability of the *guarantor* under or in connection with this *guarantee*.

5. TERMINATION

The *guarantor* is not entitled to terminate or limit this *guarantee*, or any liability of the *guarantor* under this *guarantee*, until the *secured moneys* have been paid in full.

6. GOVERNING LAW

This *guarantee* is governed by and construed under the law of the State of Western Australia.

7. GENERAL

7.1 Continuing Security

This *guarantee* is a continuing security and is not wholly or partially discharged by the payment at any time of any *secured moneys*, settlement of account or other fact and applies to the balance of the *secured moneys* at any time until a final termination of this *guarantee* by the *service provider*.

7.2 Further Assurance

The *guarantor* must upon request by the *service provider* at any time execute any document and perform any action necessary to give full effect to this *guarantee*, whether prior or subsequent to performance of this *guarantee*.

7.3 Waivers

Any failure or delay by the *service provider* to exercise any right or power under this *guarantee* does not operate as a waiver and the single or partial exercise of any right or power by the *service provider* does not preclude any other or further exercise of that or any other right or power by the *service provider*.

EXECUTED as a deed.

[Execution clauses for guarantee to be inserted]

Appendix 3A – Transitional Western Power Network standard access contract⁷³¹

⁷³¹ Appendix 3A inserted by WAGG No 134, 30 July 2021

Appendix 4 – Model Contributions Policy⁷³²

{Outline: See section 5.12}⁷³³

This Appendix 4 leaves some matters to be completed when a *contributions policy* is incorporated into an *access arrangement*. These are shown as variables in square brackets, eg. “[x]”.

The variable can be a simple absolute number or may follow a more sophisticated structure designed by the *service provider* to best suit the characteristics of its *covered network* and business.

The variables proposed by a *service provider* are subject to approval by the *Authority* under Chapter 4, and (without limiting the *Authority’s* discretion or duties) must be consistent with the *Code objective* and section 5.12.

If an *access arrangement* is to include *contributions* in the *capital base* under section 6.51A(b), the *Authority* should consider whether, and if so how, the *contributions policy* in the *access arrangement* should differ from this *model contributions policy*.

This *model contributions policy* does not provide for *contributions* under section 5.17A or a *headworks scheme*. If the *contributions policy* in the *access arrangement* is to provide for *contributions* under section 5.17A or a *headworks scheme*, then the *Authority* should consider how the *contributions policy* should differ from this *model contributions policy*.

Footnotes following each matter in square brackets contain instructions to the *Authority*. The footnotes form part of this *model contributions policy* and, like these introductory notes, have legal effect.⁷³⁴

Subappendix 4.1 – Introductory

Definitions and interpretation

A4.1 In this *contributions policy*, unless the contrary intention is apparent⁷³⁵

“**Code**” means the *Electricity Networks Access Code 2004*.

“**Code objective**” has the meaning given to it in section 2.1 of the *Code*.

“**new service**” has the meaning given to it in clause A4.4.⁷³⁶

⁷³⁷

⁷³² Heading to Appendix 4 amended by WAGG No 180, 22 October 2008

⁷³³ Appendix 4 amended by WAGG No 207, 8 November 2005

⁷³⁴ Appendix 4 amended by WAGG No 152, 1 September 2006; Appendix 4 amended by WAGG No 206, 8 December 2006; Appendix 4 amended by WAGG No 137, 29 June 2007; Appendix 4 amended by WAGG No 180, 22 October 2008

⁷³⁵ Clause A4.1 amended by WAGG No 180, 22 October 2008

⁷³⁶ Clause A4.1 amended by WAGG No 180, 22 October 2008

⁷³⁷ Clause A4.1 amended by WAGG No 180, 22 October 2008

“**payment contract**” has the meaning given to it in clause A4.14(a). “**provision in kind**” has the meaning given to it in clause A4.13.

“**provision in kind contract**” has the meaning given to it in clause A4.13(a).

“**reasonable time**” is to be determined in accordance with clause A4.9.

“**relevant applicant**” means an *applicant* seeking a *new service*.

738

A4.2 Unless the contrary intention is apparent, a term with a defined meaning in the *Code* has the same meaning in this *contributions policy*.⁷³⁹

A4.3 Unless the contrary intention is apparent:

- (a) a rule of interpretation in the *Code*; and
- (b) the *Interpretation Act 1984*,

apply to the interpretation of this *contributions policy*.⁷⁴⁰

Application of this contributions policy⁷⁴¹

A4.4 If it is necessary for a *service provider* to undertake *required work* in order to provide to an *applicant* (“**relevant applicant**”) a *covered service* (“**new service**”) sought in an *access application*, then this *contributions policy* applies.⁷⁴²

Subappendix 4.2 – Contributions⁷⁴³

Contribution⁷⁴⁴

A4.5 In this *contributions policy* and subject to clause A4.6, the *contribution* for any *required work* is:

- (a) in respect of the *forecast new facilities investment* in the *required work*:
 - (i) the amount of *forecast new facilities investment* in the *required work* which is permitted to be included in a *contribution* under section 5.14 of the *Code*; plus
 - (ii) a *reasonable rate of return*, determined under clause A4.9, on the amount determined under clause A4.5(a)(i);

⁷³⁸ Clause A4.1 amended by WAGG No 180, 22 October 2008

⁷³⁹ 5 Clause A4.2 amended by WAGG No 180, 22 October 2008

⁷⁴⁰ Clause A4.3 amended by WAGG No 180, 22 October 2008

⁷⁴¹ Heading to clause A4.4 amended by WAGG No 180, 22 October 2008

⁷⁴² Clause A4.4 amended by WAGG No 180, 22 October 2008

⁷⁴³ Heading to Sub-appendix 4.2 amended by WAGG No 180, 22 October 2008

⁷⁴⁴ Heading to clause A4.5 amended by WAGG No 180, 22 October 2008

and

- (b) in respect of the *non-capital costs* of the *required work*, the amount of forecast *non-capital costs* in the non-capital work which is permitted to be included in a *contribution* under section 5.14 of the *Code*.⁷⁴⁵

A4.6 A *contribution* must not exceed the amount that would be required by a prudent *service provider* acting efficiently, in accordance with *good electricity industry practice*, seeking to achieve the lowest sustainable cost of providing the *new services*.⁷⁴⁶

A4.7 If it is necessary for a *service provider* to undertake *required work* to provide *new services* to more than one *relevant applicant*, the *service provider* must calculate the *contribution* for the *required work* as set out in clause A4.5 and must, acting as a *reasonable and prudent person*, apportion the amount calculated under clause A4.5 between the *relevant applicants* in accordance with the *Code objective* to determine each *relevant applicant's contribution*.⁷⁴⁷

A4.8 If the application of this *contributions policy* in relation to required work produces a *contribution* amount that is greater than zero, the *service provider* is not required to undertake the *required work* unless the *relevant applicant* agrees to provide the *contribution* to the *service provider* in accordance with this *contributions policy*.⁷⁴⁸

Reasonable rate of return

A4.9 For the purposes of clause A4.5(b), a *reasonable rate of return* is to be determined by the *service provider* as a *reasonable and prudent person* in accordance with the *Code objective* over a *reasonable time* having regard to the risk associated with the *required work*.⁷⁴⁹

A4.10 For the purposes of clause A4.9, a *reasonable time* is to be determined having regard to:

- (a) the anticipated commercial life of any new facility which results from the *required work*, up to a maximum of 15 years; and
- (b) the purpose for which the *relevant applicant* requires the *new services*.⁷⁵⁰

Manner of contribution

A4.11 A *contribution* may be made:

- (a) by the *relevant applicant* by way of either:
 - (i) subject to clause A4.13, *provision in kind*; or

⁷⁴⁵ Clause A4.5 amended by WAGG No 180, 22 October 2008

⁷⁴⁶ Clause A4.6 amended by WAGG No 180, 22 October 2008

⁷⁴⁷ Clause A4.7 amended by WAGG No 180, 22 October 2008

⁷⁴⁸ Clause A4.8 amended by WAGG No 180, 22 October 2008

⁷⁴⁹ Clause A4.9 amended by WAGG No 180, 22 October 2008

⁷⁵⁰ Clause A4.10 amended by WAGG No 180, 22 October 2008

- (ii) subject to clauses A4.12 and A4.14, a financial payment comprising either:
 - A. periodic financial payments; or
 - B. an up-front financial payment;

or

 - (b) by the State under the Regional Electricity Supply Policy or otherwise.⁷⁵¹
- A4.12 The *relevant applicant* may elect under clause A4.11(a)(ii)A to make the *contribution* by way of a periodic financial payment if:
- (a) the *contribution* meets any materiality thresholds below which an periodic financial payment will not apply, for example in terms of one or more of the following in respect of *required work*:
 - (i) a minimum capital cost of \$[x]⁷⁵²; or
 - (ii) a minimum amount of \$[x]⁷⁵³ per period for a periodic financial payment.
 - (b) if requested, the *relevant applicant* provides reasonable security to the *service provider* in the *payment contract* under clause A4.14(a) for the payment of the periodic financial payment over the period referred to in clause A4.10(a).⁷⁵⁴

Provision of contribution in kind⁷⁵⁵

- A4.13 The *service provider* may agree to the *relevant applicant* providing or procuring the *required work*, or part of the *required work*, under clause A4.11(a)(i) itself (“**provision in kind**”), in which case:
- (a) the *access contract* or another contract (either in this context a *provision in kind contract*) must deal with the parties’ rights and obligations in relation to the *provision in kind*; and
 - (b) the terms of the *provision in kind contract* are to be negotiated between the *service provider* and the *relevant applicant*, and failing agreement may be the subject of an *access dispute*; and
 - (c) unless the *provision in kind contract* provides otherwise, title to the *required work* passes to the *service provider* on commissioning; and

⁷⁵¹ Clause A4.11 amended by WAGG No 180, 22 October 2008

⁷⁵² To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 5. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁷⁵³ To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 5. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁷⁵⁴ Clause A4.12 amended by WAGG No 180, 22 October 2008

⁷⁵⁵ Heading to clause A4.13 amended by WAGG No 180, 22 October 2008

- (d) if any materiality threshold is met, the *provision in kind contract* must provide for the *service provider* to recoup from other *users* who subsequently benefit from the *required work*, and rebate to the *relevant applicant*, an appropriate amount to reflect the benefit the other *users* receive from the *provision in kind*.⁷⁵⁶

Provision of contribution by financial payment⁷⁵⁷

A4.14 If the *user* elects to make a periodic financial payment under clause A4.11(a)(ii)A or an up-front payment under clause A4.11(a)(ii)B (“**financial provision**”), then:

- (a) the terms of the *access contract* or another contract (either in this context a *payment contract*) must deal with the parties’ rights and obligations in relation to the *financial provision* including (in the case of the up-front payment) regarding security for the *relevant applicant* and must be negotiated between the *service provider* and the *relevant applicant*, and failing agreement may be the subject of an *access dispute*; and
- (b) unless the *payment contract* provides otherwise, title to the *required work* remains with the *service provider* despite the *financial provision*; and
- (c) the *payment contract* must provide:
 - (i) in the case of a periodic payment — for the periodic payments to be adjusted when other *users* subsequently benefit from the *required work*, to ensure that the *relevant applicant* pays no more than a fair share having regard to the benefit the other *users* receive from the *financial provision*; or
 - (ii) in the case of an up-front payment, if any materiality threshold is met — for the *service provider* to recoup from other *users* who subsequently benefit from the *required work*, and rebate to the *relevant applicant*, an appropriate amount to reflect the benefit the other *users* receive from the *financial provision*.⁷⁵⁸

Rebates and recoupment

A4.15 The *contributions policy* may specify materiality thresholds below which any recoupment and rebate mechanism under clause A4.13(d) or A4.14(c)(ii) will not apply, for example in terms of one or more of the following in respect of *required work*:

- (a) a minimum capital cost of \$[x]⁷⁵⁹; or

⁷⁵⁶ Clause A4.13 amended by WAGG No 180, 22 October 2008

⁷⁵⁷ Heading to clause A4.14 amended by WAGG No 180, 22 October 2008

⁷⁵⁸ Clause A4.14 amended by WAGG No 180, 22 October 2008

⁷⁵⁹ To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 5. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

- (b) a minimum amount of \$[x]⁷⁶⁰ to be recouped from or rebated to a *user*; or
- (c) a maximum period of [x]⁷⁶¹ months over which the mechanism may operate.⁷⁶²

Subappendix 4.3 – [Not used]⁷⁶³

A4.16 [Not used]

A4.17 [Not used]

A4.18 [Not used]

A4.19 [Not used]

A4.20 [Not used]

A4.21 [Not used]

⁷⁶⁰ To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 5. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁷⁶¹ To be inserted in the *access arrangement* and approved by the *Authority* under Chapter 5. To the extent that the *Authority* so approves, the *access arrangement* may leave this to be inserted in the *access contract* by agreement between the parties or arbitrated award.

⁷⁶² Clause A4.15 amended by WAGG No 180, 22 October 2008

⁷⁶³ Sub-appendix 4.3 comprising clauses A4.16 – A4.21 deleted by WAGG No 180, 22 October 2008

Appendix 4A – Transitional Western Power Network Contributions Policy⁷⁶⁴

⁷⁶⁴ Appendix 4A inserted by WAGG No 134, 30 July 2021

Appendix 5 – Procedural Rules for Arbitration

{Outline: See section 10.2.}

Application

- A5.1 This Appendix 5 applies if:
- (a) in accordance with the *Code*, a *service provider* or another person notifies the *Authority* that an *access dispute* exists; and
 - (b) notification of the dispute is not withdrawn in accordance with the *Code*.

Definitions

- A5.2 In this Appendix 5 “**Court**” means the Supreme Court.

Informality and expedition

- A5.3 Subject to the *Code*, *proceedings* must be conducted with as little formality and technicality, and with as much expedition, as the requirements of this Appendix 5 and Chapter 10, and a proper hearing and determination of a dispute, permit.
- A5.4 The *arbitrator* may from time to time make orders regulating the conduct of, and regulating parties’ conduct in relation to, *proceedings* which are directed towards achieving the objective in clause A5.3.
- A5.5 The *parties* to an *access dispute* must at all times conduct themselves in a manner which is directed towards achieving the objective in clause A5.3.
- A5.6 An order under clause A5.4 is not an award.

Arbitrator may request information

- A5.7 The *arbitrator* may request the *Authority* to give to the *arbitrator* any information in the *Authority’s* possession that is relevant to the *access dispute*.
- A5.8 The *Authority* is to give the *arbitrator* the information requested, whether or not it is confidential and whether or not it came into the *Authority’s* possession for the purposes of the arbitration.
- A5.9 If the *Authority* gives the *arbitrator* information that is confidential, the *Authority* is to identify the nature and extent of the confidentiality and subject to clause A5.10, the *arbitrator* is to treat the information accordingly.
- A5.10 To the extent necessary to comply with the rules of natural justice, the *arbitrator* may disclose to the *parties* any information provided by the *Authority* whether or not it is confidential, but the *arbitrator* may make an order under clause A5.25 or a determination under clause A5.39 in respect of such information.

Hearing to be in private

- A5.11 Subject to Subchapter 10.3 and clause A5.12, *proceedings* are to be heard in private.

- A5.12 If the *parties* agree, *proceedings* or part of the *proceedings* may be conducted in public.
- A5.13 The *arbitrator* may give written directions as to the persons who may be present at *proceedings* that are conducted in private.
- A5.14 In giving directions under clause A5.13, the *arbitrator* must have regard to the wishes of the *parties* and the need for commercial confidentiality.

Right to representation

- A5.15 Subject to section 10.14, in *proceedings*, a party may appear in person or be represented by someone else.

Procedure

- A5.16 In *proceedings*, the *arbitrator*:
- (a) is not bound by technicalities, legal forms or rules of evidence; and
 - (b) must act as speedily as a proper consideration of the *access dispute* allows, having regard to the need to carefully and quickly inquire into and investigate the dispute and all matters affecting the merits, and fair settlement, of the *access dispute*; and
 - (c) may gather information about any matter relevant to the *access dispute* in any way the *arbitrator* thinks appropriate.
- A5.17 To the extent necessary to comply with the rules of natural justice, the *arbitrator* may disclose to the *parties* any information gathered by the *arbitrator* under clause A5.16(c) whether or not it is confidential, but the *arbitrator* may make an order under clause A5.25 or a determination under clause A5.39 in respect of such information.
- A5.18 The *arbitrator* may determine the periods that are reasonably necessary for the fair and adequate presentation of the respective cases of the *parties* in the arbitration hearing, and may require that the cases be presented within those periods.
- A5.19 The *arbitrator* may require evidence or argument to be presented in writing, and may decide the matters on which the *arbitrator* will hear oral evidence or argument.
- A5.20 The *arbitrator* may determine that all or part of *proceedings* are to be conducted by:
- (a) telephone; or
 - (b) closed circuit television; or
 - (c) any other means of communication.

Particular powers of arbitrator

- A5.21 The *arbitrator* may do any of the following things for the purpose of determining an *access dispute*:
- (a) give a direction in the course of, or for the purpose of, *proceedings*; and

- (b) make an interim determination; and
- (c) hear and determine the *proceedings* in the absence of a *party* who has been given notice of the hearing; and
- (d) sit at any place; and
- (e) adjourn to any time and place; and
- (f) refer any matter to an independent expert and accept the expert's report as evidence.

Determinations

A5.22 If the *arbitrator* makes a determination or interim determination it must:

- (a) make it in writing, signed by the *arbitrator*; and
- (b) include *reasons* in the determination.

A5.23 If a determination of an *arbitrator* under this Appendix 5 contains:

- (a) a clerical mistake; or
- (b) an error arising from an accidental slip or omission; or
- (c) a material mathematical miscalculation or a material mistake in the description of any person, thing or matter referred to in the determination; or
- (d) a defect in form,

the *arbitrator* may correct the determination or the Court, on the application of a *party*, may make an order correcting the determination.

Contempt

A5.24 A person must not do any act or thing in relation to the arbitration of an *access dispute* that would be a contempt of court if the *arbitrator* were a court of record.

Disclosure of information

A5.25 The *arbitrator* may (subject to the rules of natural justice) give an oral or written order to a person not to divulge or communicate to anyone else specified information that was given to the person in the course of proceedings unless the person has the *arbitrator's* permission.

A5.26 A person must not contravene an order under clause A5.25.

Power to take evidence on oath or affirmation

A5.27 The *arbitrator* may take evidence on oath or affirmation and for that purpose the *arbitrator* may administer an oath or affirmation.

A5.28 The *arbitrator* may summon a person to appear before the *arbitrator* to give evidence and to produce such documents (if any) as are referred to in the summons.

A5.29 The powers contained in clauses A5.27 and A5.28 may only be exercised for the purposes of arbitrating an *access dispute*.

Failing to attend as a witness

A5.30 A person who is served with a summons to appear as a witness before the *arbitrator* must not, without reasonable excuse:

- (a) fail to attend as required by the summons; or
- (b) fail to appear and report himself or herself from day to day unless excused, or released from further attendance, by the *arbitrator*.

Failing to answer questions etc.

A5.31 A person appearing as a witness before the *arbitrator* must not, without reasonable excuse:

- (a) refuse or fail to be sworn or to make an affirmation; or
- (b) refuse or fail to answer a question that the person is required to answer by the *arbitrator*, or
- (c) refuse or fail to produce a document that he or she is required to produce by a summons served on it.

A5.32 The determination as to what is a reasonable excuse for the purposes of clause A5.31 is solely in the discretion of the *arbitrator*.

A5.33 It is a reasonable excuse for the purposes of clause A5.31 for an individual to refuse or fail to answer a question or produce a document on the ground that the answer or the production of the document might tend to incriminate the individual or to expose the individual to a penalty.

A5.34 Clause A5.33 does not limit what is a reasonable excuse for the purposes of clause A5.31.

Intimidation etc.

A5.35 A person must not:

- (a) threaten, intimidate or coerce another person; or
- (b) cause or procure damage, loss or disadvantage to another person, because that other person:
- (c) proposes to produce, or has produced, documents to the *arbitrator*; or
- (d) proposes to appear, or has appeared, as a witness before the *arbitrator*.

Party may request arbitrator to treat material as confidential

A5.36 A *party* to *proceedings* may:

- (a) inform the *arbitrator* that, in the *party's* opinion, a specified part of a document contains confidential commercial information; and
- (b) request the *arbitrator* not to give a copy of that part to another *party*.

A5.37 On receiving the request, the *arbitrator* must:

- (a) inform the other *party* or *parties* that the request has been made and of the general nature of the matters to which the relevant part of the document relates; and
- (b) ask the other *party* or *parties* whether there is any objection to the *arbitrator* complying with the request.

A5.38 If there is an objection to the *arbitrator* complying with a request, the *party* objecting may inform the *arbitrator* of its objection and of the *reasons* for it.

A5.39 After considering:

- (a) a request;
- (b) any objection; and
- (c) any further submissions that a *party* has made in relation to the request,

the *arbitrator* may (subject to the rules of natural justice) make a determination:

- (d) to not give to the other *party* or *parties* a copy of so much of the document as contains confidential commercial information that the *arbitrator* thinks should not be given; or
- (e) to give the other *party* or another specified *party* a copy of the whole, or part, of the part of the document that contains *confidential information* subject to a condition that the *party* give an undertaking not to disclose the information to another person except to the extent specified by the *arbitrator* and subject to such other conditions as the *arbitrator* determines.

A5.40 If any person (other than the *arbitrator*), in breach of a determination under clause A5.39, discloses information (other than information which has lawfully entered the public domain or which must be disclosed under a *written law*) that the *arbitrator* has determined under clause A5.39 is confidential commercial information, then a person affected by the breach may sue for damages..

Costs

A5.41 The costs of *proceedings* are to be dealt with in accordance with section 10.37⁷⁶⁵.

⁷⁶⁵ Appendix 5 clause A5.41 amended by WAGG No 207, 8 November 2005

Appeal to Court

A5.42 A *party* may appeal to the *Supreme Court*, on a question of law, from a determination of an *arbitrator* under this Appendix 5.

A5.43 An appeal must be instituted:

- (a) not later than the 28th day after the day on which the decision is made or within such further period as the *Supreme Court* (whether before or after the end of that day) allows; and
- (b) in accordance with the rules of the *Supreme Court*.

A5.44 The *Supreme Court* may make an order staying or otherwise affecting the operation or implementation of the determination of the *arbitrator* that the *Supreme Court* thinks appropriate to secure the effectiveness of the hearing and determination of the appeal.

Copies of decisions to be given to the Authority

A5.45 Where the *arbitrator* is required to give a copy of a draft decision or final decision to the *parties* to an *access dispute*, the *arbitrator* is to also give a copy of the decision to the *Authority*.

Effect of appointment of new arbitrator on evidence previously given and awards and determinations previously made

A5.46 Where a new person takes over the functions of *arbitrator* in place of a previous *arbitrator* who has begun but not completed the hearing and determination of an *access dispute*:

- (a) the new *arbitrator* may order the *proceedings* to be re-heard:
 - (i) in full, in which case all evidence heard by the previous *arbitrator* is to be disregarded by the new *arbitrator* unless resubmitted or retendered; or
 - (ii) in part, in which case any evidence heard by the previous *arbitrator* during the parts of the *proceedings* which are re-heard is to be disregarded by the new *arbitrator* unless resubmitted or retendered;
- (b) if no order is made under clause A5.46(a), then the *proceedings* are to continue as though the new *arbitrator* had been present from the commencement of the *proceedings*;
- (c) if an order is made under clause A5.46(a)(ii), then:
 - (i) the *proceedings* are to continue as though the new *arbitrator* had been present during the earlier *proceedings*; and
 - (ii) the new *arbitrator* is to treat any evidence given, document produced or thing done in the course of the earlier *proceedings* in the same manner in all respects as if it had been given, produced or done in the course of the *proceedings* conducted by the new *arbitrator*;

- (d) any interim determination made in the course of the earlier *proceedings* is by force of this Appendix 5 to be taken to have been made by the new *arbitrator*; and
- (e) the new *arbitrator* may adopt and act on any determination of a matter made in the course of the earlier *proceedings* without applying his or her own judgment to the matter.

A5.47 In clause A5.46, “earlier proceedings” means the *proceedings* or parts of the *proceedings* which the new *arbitrator* does not order to be re-heard under clause A5.46(a)(ii).

Decision of the Arbitrator

A5.48 Unless the *arbitrator* has terminated the *proceedings* under section 10.18, the *arbitrator* must require the *parties* to make submissions to the *arbitrator* regarding the *access dispute* by a specified date.

A5.49 In making a decision under section 10.17 of the *Code*, the *arbitrator*:

- (a) must consider submissions received from the *parties* before the date specified by the *arbitrator* under clause A5.48 and may consider submissions received after that date;
- (b) may provide a draft decision to the *parties* and if it does so must request submissions from the *parties* by a specified date;
- (c) if applicable, must consider submissions received from the *parties* before the date specified by the *arbitrator* under clause A5.49(b) and may consider submissions received after that date; and sub-clause
- (d) must provide a final decision to the *parties*.

A5.50 The *arbitrator* may by whatever means it considers appropriate seek written submissions from persons who are not *parties* to the dispute and subject to the rules of natural justice may have regard to those submissions in making its decision under section 10.17 of the *Code*.

A5.51 The *arbitrator* must provide a final decision under section 10.17 of the *Code* within three months of requiring *parties* to make submissions under clause A5.48. The *arbitrator* must also ensure that there is a period of at least 10 *business days*:

- (a) between requiring *parties* to make submissions under clause A5.48 and the last day for such submissions specified by the *arbitrator*; and
- (b) between providing a draft decision to the *parties* under clause A5.49(b) and the last day for submissions on the draft decision specified by the *arbitrator*.

in all other respects the timing for the taking of each of the steps set out in clause A5.49 is a matter for the *arbitrator* to determine.

A5.52 The *arbitrator* may increase the period of three months specified in clause A5.51 by periods of up to one month on one or more occasions provided it provides the *parties* (and each person who has made a written submission to the *arbitrator*) with a notice of the decision to increase the period.

A5.53 A *service provider* must comply with a decision of the *arbitrator* made under this Appendix 5 from the date specified by the *arbitrator*.

Appendix 6 – Matters to be Addressed by Technical Rules

{Outline: See section⁷⁶⁶ 12.32}

- A6.1 Subject to clause A6.2, *technical rules* must address at least the following matters:⁷⁶⁷
- (a) performance standards in respect of *service standard* parameters; and
 - (b) the identity of the *system operator* for the *network*; and
 - (c) the technical requirements that apply to the design and operation of *facilities and equipment* connected to the *network*; and
 - (d) the standards which apply to the operation of the *network*, including in emergency situations; and
 - (e) obligations to test *facilities and equipment* in order to demonstrate compliance with the *technical rules*; and
 - (f) procedures that apply if the *service provider* believes that any part of *facilities and equipment* does not comply with the *technical rules*; and
 - (g) procedures that apply to the inspection of *facilities and equipment* connected to the *network*; and
 - (h) the standards which apply to control and protection settings for *facilities and equipment* connected to the *network*; and
 - (i) procedures that apply to the commissioning and testing of new *facilities and equipment* connected to the *network*; and
 - (j) procedures that apply to the disconnection of *facilities and equipment* from the *network*; and
 - (k) the information that a *user* must provide to the *service provider* in relation to the operation of *facilities and equipment* connected to the *network*; and
 - (l) the *generation* and *load* forecast information that *users, consumers* and *generators* must provide to the *service provider*; and
 - (m) *network* planning criteria, which must address at least the following matters:
 - (i) contingency criteria; and
 - (ii) steady-state criteria including:
 - A. frequency limits; and

⁷⁶⁶ Appendix 6 amended by WAGG No 207, 8 November 2005

⁷⁶⁷ Clause A6.1 amended by WAGG No 157, 18 September 2020

- B. voltage limits; and
- C. thermal rating criteria; and
- D. fault rating criteria; and
- E. maximum protection clearing times; and
- F. auto reclosing policy; and
- G. insulation coordination standard; and
- (iii) stability criteria including:
 - A. rotor angle stability criteria; and
 - B. frequency stability criteria; and
 - C. voltage stability criteria; and
- (iv) quality of supply criteria including:
 - A. voltage fluctuation criteria; and
 - B. harmonic voltage criteria; and
 - C. harmonic current criteria; and
 - D. voltage unbalance criteria; and
 - E. electro-magnetic interference criteria; and
- (v) construction standards criteria; and
- (n) *curtailment of services* including matters such as:
 - (i) planned and unplanned maintenance, testing or repair of the *network*; and
 - (ii) breakdown of or damage to the *network*; and
 - (iii) events of *force majeure*; and
 - (iv) the *service provider's* obligations to comply with a written law or a *statutory instrument*.

A6.2 *Technical rules* are not required to address the matters listed in clause A6.1 to the extent that these matters are dealt with in Chapter 3, Chapter 3A, Chapter 3B, Appendix 12 or Appendix 13 of the *WEM Rules*.⁷⁶⁸

⁷⁶⁸ Clause A6.2 inserted by WAGG No 157, 18 September 2020

Appendix 7 – General process for public consultation

{Outline: Appendix 7 is cited in certain places throughout the *Code*.}

Application of this Appendix 7

A7.1 If this *Code* states that a *matter for consultation*

- (a) must be the subject of public consultation under this Appendix 7 or
- (b) may be the subject of public consultation under this Appendix 7, and the *decision maker* chooses to undertake public consultation under this Appendix 7,

then the *decision maker* must comply with this Appendix 7.

A7.2 If this *Code* requires:

- (a) public consultation in relation to a *matter for consultation* to be completed; or
- (b) a decision or determination relating to a *matter for consultation* to be made,

within a specified period of time, the *decision maker* must complete the public consultation or make the decision or determination, as applicable, in accordance with this Appendix 7 and within the specified time.

Where the decision maker is not the Authority

A7.3 Where the *decision maker* is required under this Appendix 7 to *publish* a thing and:

- (a) the *decision maker* is the *Authority* - the *Authority* must *publish* the thing; and
- (b) is someone other than the *Authority* -
 - (i) the *decision maker* must provide a copy of the thing to the *Authority*; and
 - (ii) once a copy of the thing is provided to the *Authority*, the *Authority* must forthwith *publish* the thing; and
 - (iii) for the purposes of this Appendix 7, the thing is *published* from the time that the *Authority publishes* it

Issues paper

A7.4 The *decision maker* may produce and *publish* an issues paper examining the issues relating to the *matter for consultation*.

Submissions from the service provider

A7.5 Where the *decision maker* is someone other than the *service provider* and is required to invite submissions from the public in relation to a *matter for consultation* in relation to a *covered network* it must also invite submissions from the *service provider*.

First round public submissions

A7.6 The *decision maker* must *publish* an invitation for submissions in relation to a *matter for consultation*.

A7.7 A *decision maker* must specify in its invitation for submissions under clause A7.6 the length of time it will allow for the making of submissions on a *matter for consultation* in accordance with clause A7.9.

A7.8 A person may make a submission on a *matter for consultation* within the period of time specified by the *decision maker*.

A7.9 The time specified by the *decision maker* for the making of submissions must be at least 10 *business days* after the invitation is *published*, and must be at least 10 *business days* after any issues paper was *published* under clause A7.4.⁷⁶⁹

Draft decision by the Decision Maker

A7.10 Subject to clause A7.21, the *decision maker* must consider any submissions made on the *matter for consultation*.

A7.11 The *decision maker* may make a draft decision if, in the opinion of the *decision maker* the circumstances warrant the making of a draft decision.

A7.12 If the *decision maker* determines that a draft decision is warranted, the *decision maker* must *publish* the draft decision within 2 months after the *due date* for submissions under clause A7.7.

Second round public submissions (if applicable)

A7.13 Clauses A7.14⁷⁷⁰ to A7.17 apply only if the *decision maker* makes a draft decision under clause A7.11.

A7.14 The *decision maker* must *publish* an invitation for submissions on the draft decision at the time it *publishes* the draft decision.

A7.15 A *decision maker* must specify in its invitation for submissions under clause A7.14 the length of time it will allow for the making of submissions on a *matter for consultation* in accordance with clause A7.17.⁷⁷¹

A7.16 A person may make a submission on the draft decision to the *decision maker* within the time period specified by the *decision maker*.

⁷⁶⁹ Clause A7.9 amended by WAGG No 134, 30 July 2021

⁷⁷⁰ Appendix 7 clause A7.13 amended by WAGG No 207, 8 November 2005

⁷⁷¹ Clause A7.15 amended by WAGG No 180, 22 October 2008

A7.17 The time specified by the *decision maker* for the making of submissions on the draft decision must be at least 10 *business days* after the draft decision is *published*.⁷⁷²

Final decision by decision maker

A7.18 Subject to clause A7.21, the *decision maker* must consider any submissions and make a final decision in relation to the *matter for consultation*.⁷⁷³

A7.19 The time for the *decision maker* to make and *publish* its final decision is:

- (a) where a draft decision has been made, within 30 *business days* after the *due date* for submissions under clause A7.15; or
- (b) otherwise, within 2 months after the *due date* for submissions under clause A7.7.

Publication of submissions

A7.20 The *decision maker* must *publish* all submissions made under this Appendix 7.

Late submissions

A7.21 The *decision maker* may, consider any submission made after the time for making that submission has expired.

Additional consultation⁷⁷⁴

A7.22 The *decision maker* may undertake additional consultation at any point during the process if required.⁷⁷⁵

Extension of deadlines⁷⁷⁶

A7.23 The *decision maker* may on one or more occasions extend any time limit specified in this Appendix 7 for a period determined by the *decision maker* if, and only to the extent that, the *decision maker* first reasonably determines that:

- (a) a longer period of time is essential for due consideration of all the matters under consideration or satisfactory performance of its obligations under this Code, or both; and
- (b) the *decision maker* has taken all reasonable steps to fully utilise the times and processes provided for in this Appendix 7.⁷⁷⁷

⁷⁷² Clause A7.17 amended by WAGG No 134, 30 July 2021

⁷⁷³ Clause A7.18 amended by WAGG No 180, 22 October 2008

⁷⁷⁴ Heading to clause A7.22 inserted by WAGG No 134, 30 July 2021

⁷⁷⁵ Clause A7.22 inserted by WAGG No 134, 30 July 2021

⁷⁷⁶ Heading to clause A7.23 inserted by WAGG No 134, 30 July 2021

⁷⁷⁷ Clause A7.23 inserted by WAGG No 134, 30 July 2021

A7.24 The *decision maker* must not exercise the power in clause A7.23 to extend a time limit unless, before the day on which the time would otherwise have expired, it *publishes* notice of, and reasons for, its decision to extend the time limit.⁷⁷⁸

⁷⁷⁸ Clause A7.24 inserted by WAGG No 134, 30 July 2021

Appendix 8 — Detailed provisions regarding contributions for certain work on the Western Power Network⁷⁷⁹

Definitions

A8.1 In this Appendix 8, unless the contrary intention is apparent—

“**average cost**” for a scheme means the *total scheme cost* divided by the total number of *connection points* covered by the *scheme*.

“**commercial premises**” means *premises* on which electricity is consumed predominantly for commercial use.

“**member**” in respect of a scheme means a person who has initiated or joined a *scheme* under the SES.

“**pillar**” means a ground mounted apparatus forming part of the *Western Power Network*⁷⁸⁰ located on or near a property boundary and to which the *consumer* mains of a premises are connected in order to obtain electricity.

“**pole to pillar connection**” means the provision to a residential premises of an underground 415 V or 240 V supply via a *pillar connection*.

“**premises**” has the meaning given to it in the *Electricity Act 1945 (WA)*.

“**primary production premises**” means premises owned or occupied by a *consumer* who is assessed as carrying on a primary production business under the *Income Tax Assessment Act 1997*.

“**residential premises**” means *premises* on which electricity is consumed predominantly for domestic use.

“**scheme**” means an arrangement with respect to a particular *SES work* or a particular interconnected series of *SES works* under the *SES*.⁷⁸¹

“**SES**” and “**Supply Extension Scheme**” means the approach to *Western Power Network* work under clauses A8.8 to A8.15.⁷⁸²

“**SES work**” means a *required work* which is an extension of the *Western Power Network* to *connect*—

- (a) a primary production premises; or

⁷⁷⁹ Appendix 8 inserted by WAGG No 137, 29 June 2007; Heading of Appendix 8 amended by WAGG No 180, 22 October 2008

⁷⁸⁰ Clause A8.1 amended by WAGG No 180, 22 October 2008

⁷⁸¹ Clause A8.1 amended by WAGG No 180, 22 October 2008

⁷⁸² Clause A8.1 amended by WAGG No 180, 22 October 2008

- (b) one residential premises on a lot (excluding a residential premises in respect of which a pole to pillar connection is required under a *written law* or *statutory instrument*).⁷⁸³

“**standard dwelling**” means a *residential premises* that is located on a lot that is zoned residential, or otherwise permitted to be used for residential purposes under any town planning scheme applying to that lot (excluding lots zoned special rural residential); and has

- (a) a *load* of no more than 63 amperes single-phase 240 volt or 32 amperes three- phased 415 volt; and
- (b) sufficient *Western Power Network* capacity available to it, to supply the applicable *load*.⁷⁸⁴

“**subdivision**” means a subdivision of land which requires or has received approval under section 135 of the *Planning and Development Act 2005* (WA), the *Strata Titles Act 1985* (WA) or an equivalent written law.

“**substantial consumer**” means an *applicant* who the *service provider* forecasts to *consume* in excess of 10% of the total annual electricity consumption in respect of a *premises*.

“**temporary connection**” means a non-permanent connection to the *Western Power Network* that is undertaken to provide supply to activities such as, but not limited to, outdoor functions (such as fairs and concerts), non-standard builder supplies (such as city or commercial developments) and connections to premises during renovations.⁷⁸⁵

“**total cost**” for a scheme means the sum of the *forecast* cost for the *SES work* for which the *scheme* was initiated plus the *forecast* cost for each *SES work* for an *applicant* which subsequently joins the *scheme*.⁷⁸⁶

“**unmetered connection**” means a type of *connection point* described in clause 3.9(2) of the *Electricity Metering Code 2005* established under section 39(2)(a) of the *Act*.

Scope of Appendix 8 work to Western Power Network⁷⁸⁷

A8.2 This Appendix 8 applies only in respect of the following work in connection with the *Western Power Network* (“**Appendix 8 work**”)—

- (a) a *subdivision* under clause A8.4; and
- (b) a *pole to pillar connection* under clauses A8.5 to A8.6; and
- (c) the development of buildings under clause A8.7; and
- (d) a *Supply Extension Scheme* under clauses A8.8 to A8.15; and

⁷⁸³ Clause A8.1 amended by WAGG No 180, 22 October 2008

⁷⁸⁴ Clause A8.1 amended by WAGG No 180, 22 October 2008

⁷⁸⁵ Clause A8.1 amended by WAGG No 180, 22 October 2008

⁷⁸⁶ Clause A8.1 amended by WAGG No 180, 22 October 2008

⁷⁸⁷ Heading to clause A8.2 amended by WAGG No 180, 22 October 2008

- (e) *work* in excess of standard requirements under clause A8.16; and
- (f) specified *temporary connections* under clause A8.17 and A8.18; and
- (g) streetlights, *unmetered connections*, *relocations*, undergrounding and some *temporary connections* under clause A8.19.⁷⁸⁸

General principles

A8.3 A *contribution* for *Appendix 8 work* (other than a flat fee under clauses A8.5 and A8.17) must not exceed the forecast cost that would be forecast to be incurred for the *work* by a *service provider efficiently minimising costs*.⁷⁸⁹

Subdivisions

A8.4 The maximum *contribution* for an *applicant* who—

- (a) undertakes a *subdivision*; and
- (b) seeks *work* (other than a *pole to pillar connection*) to be undertaken on the *distribution system* to service the *subdivision*,

is the forecast cost for any *required work* which is or will be located within the boundaries of, or adjacent to, the land being *subdivided*.⁷⁹⁰

Pole to pillar connections

A8.5 The maximum *contribution* for a pole to pillar connection is a flat fee determined under clause A8.6.⁷⁹¹

A8.6 Electricity Networks Corporation may from time to time set a flat fee for *pole to pillar connections*, which fee must be calculated to the standard of a *reasonable and prudent person* and in such a way that, over a reasonable forecasting period, the forecast revenue from applying the flat fee to all *pole to pillar connections* installed during the period ("**forecast connections**") is forecast not to exceed—

- (a) the sum of *forecast cost*⁷⁹² which would be incurred for the forecast connections by a *service provider efficiently minimising costs*;

minus

- (b) the *anticipated incremental revenue* for the forecast connections.

⁷⁸⁸ Clause A8.2 amended by WAGG No 180, 22 October 2008

⁷⁸⁹ Clause A8.3 amended by WAGG No 180, 22 October 2008

⁷⁹⁰ Clause A8.4 amended by WAGG No 180, 22 October 2008

⁷⁹¹ Clause A8.5 amended by WAGG No 180, 22 October 2008

⁷⁹² Clause A8.6 amended by WAGG No 180, 22 October 2008

Development of buildings

A8.7 Where an *applicant* seeks a connection to the *Western Power Network* in respect of—

- (a) multiple *residential premises*, including multi-storey buildings, excluding—
 - (i) residential premises in respect of which a pole to pillar connection is required under a *written law* or *statutory instrument*; and
 - (ii) connections which are *SES work*;

or

- (b) commercial premises in relation to which the *applicant* will not become a substantial *consumer*; or
- (c) mixed residential premises and commercial premises in relation to which the *applicant* will not become a substantial *consumer*,

the maximum *contribution* by the *applicant* is the forecast cost for the *required work*.

⁷⁹³

The Supply Extension Scheme

Initiating or joining an SES

A8.8 An *applicant*, or group of *applicants*, for whom the *required work* comprises or includes SES work, may apply to Electricity Networks Corporation to either join an existing *scheme* or initiate a new *scheme*.⁷⁹⁴

A8.9 If the SES work sought by the *applicants* in clause A8.8 is to be connected to *network assets* which are covered by an existing scheme, then a new scheme must be initiated if—

- (a) the forecast cost for the *SES work* exceeds the average cost for the existing scheme; or
- (b) the existing scheme commenced more than 10 years ago.⁷⁹⁵

Contribution for applicant initiating a scheme

A8.10 If a single *applicant* initiates a scheme, the maximum *contribution* for the *applicant* is the forecast cost for the *SES work*.⁷⁹⁶

A8.11 If a group of *applicants* initiate a *scheme*, the maximum *contribution* for each *applicant* within the group is the average cost for the scheme.⁷⁹⁷

⁷⁹³ Clause A8.7 amended by WAGG No 180, 22 October 2008

⁷⁹⁴ Clause A8.8 amended by WAGG No 180, 22 October 2008

⁷⁹⁵ Clause A8.9 amended by WAGG No 180, 22 October 2008

⁷⁹⁶ Clause A8.10 amended by WAGG No 180, 22 October 2008

⁷⁹⁷ Clause A8.11 amended by WAGG No 180, 22 October 2008

Contribution for applicant joining an existing scheme

- A8.12 If an *applicant* joins an existing scheme, the maximum *contribution* for the *applicant* is the new average cost for the scheme, calculated by adding the forecast cost for the *required work* for the *applicant* to the previous total cost and calculating a new average cost taking into account the new *applicant's connection point*.⁷⁹⁸
- A8.13 In this circumstance the *contribution* to be made by the new *applicant* will comprise a component in payment of the forecast cost for the new connection, and a rebate component in accordance with clause A8.14 and A8.15.⁷⁹⁹

Rebate to continuing scheme members

- A8.14 If an *applicant* joining a *scheme* causes a decrease in the *average cost* for the *scheme*, Electricity Networks Corporation must, after it receives the *applicant's contribution* to join the scheme and the connection is completed, make a payment to the existing scheme members (excluding the *applicant*) of an amount equal to the difference between the *average cost* immediately before the *applicant* joined the *scheme* and the new average cost applying after the *applicant* joined.⁸⁰⁰

Rebates will not be paid after 10 years

- A8.15 To avoid doubt, the effect of clause A8.9(b) is that a rebate will only be paid under clause A8.14 within the first 10 years after a *scheme* commences.

Work in excess of standard requirements⁸⁰¹

- A8.16 If
- (a) an *applicant* seeks to have *work* undertaken ("**requested work**") which Electricity Networks Corporation, in accordance with *good electricity industry practice*, considers are in addition to what is required to meet standard supply arrangements; and
 - (b) the forecast cost for the *requested work* ("**requested cost**") exceeds the *forecast cost* which would be required if the connection was constructed in accordance with standard supply arrangements ("**standard cost**"),
- then—
- (c) the maximum *contribution* in respect of the *standard cost* is to be determined under the provisions of this *Code* and the *access arrangement* which apply to the type of connection in question; and
 - (d) in addition, the maximum *contribution* may include the difference between the *requested cost* and the *standard cost*.⁸⁰²

⁷⁹⁸ Clause A8.12 amended by WAGG No 180, 22 October 2008

⁷⁹⁹ Clause A8.13 amended by WAGG No 180, 22 October 2008

⁸⁰⁰ Clause A8.14 amended by WAGG No 180, 22 October 2008

⁸⁰¹ Heading to clause A8.16 amended by WAGG No 180, 22 October 2008

⁸⁰² Clause A8.16 amended by WAGG No 180, 22 October 2008

Temporary connections

- A8.17 If a flat fee is determined under clause A8.18 for a class of *temporary connection*, then the maximum *contribution* for the class of *temporary connection* is the flat fee.⁸⁰³
- A8.18 Electricity Networks Corporation may from time to time set a flat fee for *temporary connections*, which fee must be calculated to the standard of a *reasonable and prudent person* and in such a way that, over a reasonable forecasting period, the forecast revenue from applying the flat fee to all *temporary connections* installed during the period (“**forecast connections**”) is forecast not to exceed the sum of *forecast cost* which would be incurred for the *forecast connections* by a *service provider efficiently minimising costs*.⁸⁰⁴

Streetlights, unmetered connections, relocations, undergrounding and some temporary connections

- A8.19 The maximum *contribution* for an *applicant* who seeks—
- (a) a modified or new streetlight, including provision of a new streetlight asset;
 - (b) an *unmetered connection*;
 - (c) to have an existing *network asset* relocated;
 - (d) to have an existing overhead *network asset* or connection undergrounded;
 - (e) a *temporary connection* if Electricity Networks Corporation has not set a fee for that class of *temporary connection* under clause A8.18,
- is the *forecast cost* for the *required work*.⁸⁰⁵

If required work comprises more than just Appendix 8 work⁸⁰⁶

- A8.20 To avoid doubt, if *required work* comprises one or more items of *Appendix 8 work* and one or more other items of *work*, then unless the *service provider* and the *contributing user* agree otherwise, references in the *Code* to “*required work*” are to the *Appendix 8 work* and the other *work* collectively.⁸⁰⁷

⁸⁰³ Clause A8.17 amended by WAGG No 180, 22 October 2008

⁸⁰⁴ Clause A8.18 amended by WAGG No 180, 22 October 2008

⁸⁰⁵ 1 Clause A8.19 amended by WAGG No 180, 22 October 2008

⁸⁰⁶ Heading to clause A8.20 amended by WAGG No 180, 22 October 2008

⁸⁰⁷ Clause A8.20 inserted by WAGG No 176, 29 August 2007; Clause A8.20 amended by WAGG No 180, 22 October 2008

Appendix 9 — [Appendix not used]⁸⁰⁸

[Heading not used]⁸⁰⁹

A9.1 [not used]⁸¹⁰

[Heading not used]⁸¹¹

A9.2 [not used]⁸¹²

[Heading not used]⁸¹³

A9.3 [not used]⁸¹⁴

A9.4 [not used]⁸¹⁵

A9.5 [not used]⁸¹⁶

[Heading not used]⁸¹⁷

A9.6 [not used]⁸¹⁸

[Heading not used]⁸¹⁹

A9.7 [not used]⁸²⁰

A9.8 [not used]⁸²¹

A9.9 [not used]⁸²²

⁸⁰⁸ Heading amended by WAGG No 180, 22 October 2008; Heading deleted by WAGG No 157, 18 September 2020

⁸⁰⁹ Heading to clause A9.1 deleted by WAGG No 157, 18 September 2020

⁸¹⁰ Clause A9.1 deleted by WAGG No 157, 18 September 2020

⁸¹¹ Heading to clause A9.2 deleted by WAGG No 157, 18 September 2020

⁸¹² Clause A9.2 amended by WAGG No 180, 22 October 2008; Clause A9.2 deleted by WAGG No 157, 18 September 2020

⁸¹³ Heading to clause A9.3 deleted by WAGG No 157, 18 September 2020

⁸¹⁴ Clause A9.3 amended by WAGG No 180, 22 October 2008; Clause A9.3 deleted by WAGG No 157, 18 September 2020

⁸¹⁵ Clause A9.4 deleted by WAGG No 157, 18 September 2020

⁸¹⁶ Clause A9.5 deleted by WAGG No 157, 18 September 2020

⁸¹⁷ Heading to clause A9.6 deleted by WAGG No 157, 18 September 2020

⁸¹⁸ Clause A9.6 amended by WAGG No 180, 22 October 2008; Clause A9.6 deleted by WAGG No 157, 18 September 2020

⁸¹⁹ Heading to clause A9.7 deleted by WAGG No 157, 18 September 2020

⁸²⁰ Clause A9.7 amended by WAGG No 180, 22 October 2008; Clause A9.7 deleted by WAGG No 157, 18 September 2020

⁸²¹ Clause A9.8 deleted by WAGG No 157, 18 September 2020

⁸²² Clause A9.9 deleted by WAGG No 157, 18 September 2020

A9.10 [not used]⁸²³

[Heading not used]⁸²⁴

A9.11 [not used]⁸²⁵

A9.12 [not used]⁸²⁶

[Heading not used]⁸²⁷

A9.13 [not used]⁸²⁸

[Heading not used]⁸²⁹

A9.14 [not used]⁸³⁰

⁸²³ Clause A9.10 deleted by WAGG No 157, 18 September 2020

⁸²⁴ Heading to clause A9.11 deleted by WAGG No 157, 18 September 2020

⁸²⁵ Clause A9.11 deleted by WAGG No 157, 18 September 2020

⁸²⁶ Clause A9.12 deleted by WAGG No 157, 18 September 2020

⁸²⁷ Heading to clause A9.13 deleted by WAGG No 157, 18 September 2020

⁸²⁸ Clause A9.13 amended by WAGG No 180, 22 October 2008; Clause A9.13 deleted by WAGG No 157, 18 September 2020

⁸²⁹ Heading to clause A9.14 deleted by WAGG No 157, 18 September 2020

⁸³⁰ Appendix 9 inserted by WAGG No 137, 29 June 2007